


SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 US 50 80% Fed 20% State		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	2063	2063		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	16	16		
44000100	PAVEMENT REMOVAL	SQ YD	4131	4131		
44000600	SIDEWALK REMOVAL	SQ FT	18	18		
44004250	PAVED SHOULDER REMOVAL	SQ YD	920	920		
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	27	27		
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	48	48		
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	307	307		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2509	2509		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	2,537	2,537		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1615	1615		
50105220	PIPE CULVERT REMOVAL	FOOT	294	294		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 US 50 80% Fed 20% State		
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1		
54010303	PRECAST CONCRETE BOX CULVERTS 3' X 3'	FOOT	16	16		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4		
54214725	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	EACH	2	2		
5421C015	PIPE CULVERTS, CLASS C, TYPE 1 15" (TEMPORARY)	FOOT	88	88		
54248510	CONCRETE COLLAR	CU YD	0.4	0.4		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	148	148		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	180	180		
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	52	52		
60207205	CATCH BASINS, TYPE C, TYPE 4 FRAME AND GRATE	EACH	1	1		
60500040	REMOVING MANHOLES	EACH	1	1		



FILE NAME :	USER NAME = bergnd	DESIGNED -	REVISED 9-12-12
cr:\pwwork\pwwork\bergend\0816087\0876053-shr-plan.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000 / 1		CHECKED -	REVISED -
PLOT DATE = 6/15/2012		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 2 OF 4 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	21-1-1, 27-1	CLINTON	96	4
CONTRACT NO. 76D53				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				