

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 / 1 80% FED 20% STATE	0005 80% FED 10% STATE 10% WHITEHALL	0005 80% FED 10% STATE 10% WHITEHALL	CODE NO	ITEM	UNIT		0005 / 1 80% FED 20% STATE	0005 80% FED 10% STATE 10% WHITEHALL	0005 80% FED 10% STATE 10% WHITEHALL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	429	429			48203100	HOT-MIX ASPHALT SHOULDERS	TON	89	89		
20800150	TRENCH BACKFILL	CU YD	6	6			50105220	PIPE CULVERT REMOVAL	FOOT	56	56		
28000400	PERIMETER EROSION BARRIER	FOOT	25	25			54215763	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2		
28000500	INLET AND PIPE PROTECTION	EACH	1	1			54205473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	66	66		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	70	60	5.3	4.7	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
40600300	AGGREGATE (PRIME COAT)	TON	338	291	25	22	67100100	MOBILIZATION	L SUM	1	1		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4668	4024	330	314	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
40600990	TEMPORARY RAMP	SQ YD	1637	1637			70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9865	8531	706	628	70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	112684	96815	8395	7474	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
44200156	PAVEMENT PATCHING, TYPE II, 13"	SQ YD	60	60			70300100	SHORT TERM PAVEMENT MARKING	FOOT	9684	9684		
44200162	PAVEMENT PATCHING, TYPE IV, 13"	SQ YD	32	32									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	586	586									

▲ REVISED 9-10-12

FILE NAME: c:\pwwork\pwwork\conoverp\08280278\075725-shc-plan2.dgn	USER NAME: conoverp.j	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE. 733	SECTION (62,48)RS-3,5ORS-2	COUNTY GREENE	TOTAL SHEETS 16	SHEET NO. 3
PLOT SCALE: 1/8"=1'-0"	PLOT DATE: 6/29/2012	DRAWN: -	REVISOR: -	SCALE: 1"=100'	SHEET NO. 1 OF 2 SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 76F25	

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE	0005 80% FED 10% STATE 10% WHITEHALL	0005 80% FED 10% STATE 10% WHITEHALL	CODE NO	ITEM	UNIT		0005 80% FED 20% STATE		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	123	123		Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	93232	93232		+Z0076600	TRAINEES	HOUR	1,000	1,000			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	982	982		+Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1,000	1,000			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	224	224									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1076	1076									
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123	123									
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	93232	93232									
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	982	982									
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	224	224									
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	444	444									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	444	444									

*SPECIALTY ITEM REVISED 9-10-12 +0042