

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE URBAN 0014		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	30	30		
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	98	98		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	134	134		
40600990	TEMPORARY RAMP	SQ YD	47	47		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	202	202		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3		
40800030	AGGREGATE (PRIME COAT)	TON	2	2		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1	1		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	346	346		
50102400	CONCRETE REMOVAL	CU YD	10.9	10.9		
50300225	CONCRETE STRUCTURES	CU YD	0.9	0.9		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.9	10.9		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE URBAN 0014		
50300300	PROTECTIVE COAT	SQ YD	207	207		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1260	1260		
50800515	BAR SPLICERS	EACH	22	22		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	72	72		
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	713	713		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	106	106		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	982	982		