

# SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES |   |       |                  | CONSTRUCTION TYPE CODE |  |  | SUMMARY OF QUANTITIES |   |       |                  | CONSTRUCTION TYPE CODE |  |  |
|-----------------------|---|-------|------------------|------------------------|--|--|-----------------------|---|-------|------------------|------------------------|--|--|
| CODE NO               | ITEM  | UNIT  | TOTAL QUANTITIES | 100% STATE URBAN 0014  |  |  | CODE NO               | ITEM  | UNIT  | TOTAL QUANTITIES | 100% STATE URBAN 0014  |  |  |
| 70300220              | TEMPORARY PAVEMENT MARKING - LINE 4"                      | FOOT  | 3222             | 3222                   |  |  | * X7200200            | WIDE LOAD SIGNING   | L SUM | 1                | 1                      |  |  |
| 70300240              | TEMPORARY PAVEMENT MARKING - LINE 6"                      | FOOT  | 738              | 738                    |  |  | * X7801004            | WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 4"                 | FOOT  | 3272             | 3272                   |  |  |
| 70300280              | TEMPORARY PAVEMENT MARKING - LINE 24"                     | FOOT  | 44               | 44                     |  |  | Z0015802              | PLUG EXISTING DECK DRAINS   | EACH  | 20               | 20                     |  |  |
| 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL                        | SQ FT | 1490             | 1490                   |  |  | Z0016002              | DECK SLAB REPAIR (FULL DEPTH, TYPE II)                                  | SQ YD | 64               | 64                     |  |  |
| 70400100              | TEMPORARY CONCRETE BARRIER                                | FOOT  | 387.5            | 387.5                  |  |  | Z0016200              | DECK SLAB REPAIR (PARTIAL)  | SQ YD | 212              | 212                    |  |  |
| 70400200              | RELOCATE TEMPORARY CONCRETE BARRIER                       | FOOT  | 350              | 350                    |  |  | Z0030240              | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2           | EACH  | 1                | 1                      |  |  |
| 72400100              | REMOVE SIGN PANEL ASSEMBLY - TYPE A                       | EACH  | 2                | 2                      |  |  | * Z0030255            | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2 | EACH  | 1                | 1                      |  |  |
| 72400500              | RELOCATE SIGN PANEL ASSEMBLY - TYPE A                     | EACH  | 2                | 2                      |  |  | * Z0030320            | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2          | EACH  | 1                | 1                      |  |  |
| * 78100100            | RAISED REFLECTIVE PAVEMENT MARKER                         | EACH  | 10               | 10                     |  |  | Z0030340              | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2            | EACH  | 1                | 1                      |  |  |
| 78300100              | PAVEMENT MARKING REMOVAL                                  | SQ FT | 1091             | 1091                   |  |  |                       |   |       |                  |                        |  |  |
| X4401198              | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH           | SQ YD | 401              | 401                    |  |  |                       |   |       |                  |                        |  |  |
| X5030530              | FLOOR DRAIN EXTENSION                                     | EACH  | 10               | 10                     |  |  |                       |   |       |                  |                        |  |  |
| X7010202              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL) | EACH  | 1                | 1                      |  |  |                       |   |       |                  |                        |  |  |

\* SPECIALTY ITEM

|  |                    |            |           |   |                              |                     |                   |   |                    |                |
|--|--------------------|------------|-----------|---|------------------------------|---------------------|-------------------|---|--------------------|----------------|
| FILE NAME =<br>or:\pw\work\p\d\del\gelinh\d0292570\d076f62\ht-plan.dgn | USER NAME = gelinh | DESIGNED - | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b> | F.A. RTE.<br>CH 1   | SECTION<br>1-HB-1 | COUNTY<br>MADISON                               | TOTAL SHEETS<br>28 | SHEET NO.<br>4 |
| PLOT SCALE = 100.0000' / 1" IN.  |                    | CHECKED -  | REVISED - | SCALE: SHEET NO. OF SHEETS STA. TO STA.                   |                              | FED. ROAD DIST. NO. |                   | ILLINOIS FED. AID PROJECT<br>CONTRACT NO. 76F62 |                    |                |
| PLOT DATE = 7/3/2012   |                    | DATE -     | REVISED - |   |                              |                     |                   |   |                    |                |