

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	530
S 20800150	TRENCH BACKFILL	CU YD	4
S 21101805	COMPOST FURNISH AND PLACE, 2"	SO YD	1,277
S 25000210	SEEDING, CLASS 2A	ACRE	0.4
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	706
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60
28000305	TEMPORARY DITCH CHECKS	FOOT	40
28000400	PERIMETER EROSION BARRIER	FOOT	471
S 28100105	STONE RIPRAP, CLASS A3	SO YD	81
28200200	FILTER FABRIC	SO YD	81
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	803
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	466
40600300	AGGREGATE (PRIME COAT)	TON	9
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	694

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
40701911	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/2"	SO YD	719
44000100	PAVEMENT REMOVAL	SO YD	145
S 44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	6,200
44004250	PAVED SHOULDER REMOVAL	SO YD	495
48101200	AGGREGATE SHOULDERS, TYPE B	TON	33
S 48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	344
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	11
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1
60107600	PIPE UNDERDRAINS 4"	FOOT	506
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	15
66500105	WOVEN WIRE FENCE, 4'	FOOT	344
67100100	MOBILIZATION	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,003

* SPECIALTY ITEMS S - SEE JOB SPECIFIC SPECIAL PROVISIONS

FILE NAME : 0818896-shl-500.dgn	USER NAME : default	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT TIME : 1:51:38 PM	DRAWN -	REVISED -					9300	10-00048-01-PV	MONROE	33	03
	PLOT SCALE : 100.0000' / IN.	CHECKED -	REVISED -		SCALE: SHEET 01 OF 02 SHEETS STA. TO STA.			CONTRACT NO. 97505				
	PLOT DATE : 7/18/2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							