

**PAVEMENT MARKING SCHEDULE**

STATION	OFFSET	STATION	OFFSET	COMMENT	SHORT-TERM PAVT MKING (FOOT)	TEMP PVT MK LTR & SYM (SO FT)	TEMP PVT MK LINE 4 (FOOT)	TEMP PVT MK LINE 8 (FOOT)	TEMP PVT MK LINE 12 (FOOT)	TEMP PVT MK LINE 24 (FOOT)	WORK ZONE PAVT MK REM (SO FT)	THPL PVT MK LTR & SYM (NOTE 1) (SO FT)	THPL PVT MK LINE 4 (NOTE 1) (FOOT)	THPL PVT MK LINE 8 (NOTE 1) (FOOT)	THPL PVT MK LINE 12 (NOTE 1) (FOOT)	THPL PVT MK LINE 24 (NOTE 1) (FOOT)	RAISED REFL PAVT MKR (NOTE 2) (EACH)	PRISMATIC CURB REFL (EACH)	PAINT CURB (FOOT)
<b>PALMER ROAD</b>																			
52+58.62	RT/LT	59+08.80	RT/LT	SOLID EDGE LINE			1654				551		1654					5	58
52+65.00	LT	52+89.00	LT																
52+72.78	LT	54+26.78	LT	SOLID WHITE LINE			155				52		155				4		
52+72.78	LT	54+26.78	LT	ONE-WAY CRYSTAL															
53+47.29	LT			RIGHT TURN ARROW		16					16	16							
54+19.96	LT			RIGHT TURN ARROW		16					16	16							
54+26.78	LT	56+05.94	LT	2'-6" WHITE SKIP DASH			45				15		45						
55+36.85	RT	57+45.23	RT	LANE LINE	208						69								
55+36.85	RT	57+45.23	RT	SOLID WHITE LINE			208				69		208						
55+36.85	RT	57+45.23	RT	ONE-WAY CRYSTAL													5		
55+62.00	RT			LEFT TURN ARROW		16					16	16							
56+29.98	LT	57+47.53	LT															11	58
57+11.00	RT			LEFT TURN ARROW		16					16	16						7	58
58+43.96	CL	59+08.80	CL																
<b>OLD IL. ROUTE 3</b>																			
41+00.00	CL	43+33.00	CL	CENTER LINE	233						78								
41+00.00	RT/LT	44+54.00	RT/LT	SOLID EDGE LINE			997				332		997						
41+00.00	CL	43+33.00	CL	DOUBLE YELLOW CENTER LINE			466				155		466						
41+00.00	RT	42+00.00	RT	2'-6" WHITE SKIP DASH			25				8		25						
41+00.00	CL	42+29.00	CL	TWO-WAY AMBER													3		
42+00.00	RT	44+13.58	RT	LANE LINE	206						47								
42+00.00	RT	43+39.58	RT	SOLID WHITE LINE			136				45		136						
42+00.00	RT	43+39.58	RT	ONE-WAY CRYSTAL													5		
42+25.00	RT			THROUGH/LEFT ARROW		26					26	26							
42+25.00	RT			RIGHT TURN ARROW		16					16	16							
42+29.00	CL	43+33.00	RT	CENTER LINE	103						35								
42+29.00	CL	43+33.00	RT	DOUBLE YELLOW CENTER LINE			206				69		206						
42+29.00	CL	43+33.00	CL	ONE-WAY AMBER													2		
42+29.00	CL	43+33.00	RT	ONE-WAY AMBER													2		
42+81.00	RT	43+29.00	RT	SOLID YELLOW DIAGONAL				18			18			18					
43+31.00	RT			THROUGH/LEFT ARROW		26					26	26							
43+31.00	RT			RIGHT TURN ARROW		16					16	16							
43+33.13	RT	44+28.10	RT															12	68
43+37.00	RT	44+25.00	RT	SOLID WHITE LINE				427			285			427					
43+37.00	RT	44+25.00	RT	SOLID WHITE DIAGONAL					177		177				177				
43+90.20	RT	44+15.99	RT															12	76
44+04.00	RT			THROUGH/LEFT ARROW		26					26	26							
44+17.00	RT			STOP BAR	34						34					16			
44+17.00	RT			WHITE STOP BAR						16	32								
<b>GHEENT ROAD</b>																			
44+99.00	LT	45+42.00	RT	SOLID WHITE LINE				105			70			105					
44+99.00	LT	45+42.00	RT	SOLID WHITE DIAGONAL					41		41								
45+11.85	RT/LT	47+36.47	RT/LT	SOLID EDGE LINE			531				177		531						
45+22.00	LT			WHITE STOP BAR						14	28				14				
45+33.00	LT			RIGHT TURN ARROW		16					16	16							
45+33.80	RT	47+36.00	CL	CENTER LINE	204						67								
45+33.80	RT	47+36.00	CL	DOUBLE YELLOW CENTER LINE			408				136		408						
45+33.80	RT	47+36.00	CL	TWO-WAY AMBER													5		
45+34.00	RT			WHITE STOP BAR						15	30				15				
45+42.43	LT	46+00.00	LT	2'-6" WHITE SKIP DASH			15				5		15						
45+44.00	LT			STOP BAR	15						15								
45+44.00	RT			THROUGH/LEFT TURN ARROW		26					9	26							
<b>TOTAL</b>					1003	213	4846	532	236	45	2839	213	4846	532	236	45	26	47	318

**PAVEMENT MARKING NOTES:**

- SEE HIGHWAY STANDARD 780001 FOR PAVEMENT MARKING DETAILS.
- SEE HIGHWAY STANDARD 781001 FOR RAISED REFLECTIVE PAVEMENT MARKER DETAILS.  
RAISED REFLECTIVE PAVEMENT MARKER QUANTITY INCLUDES THE FOLLOWING TYPES:  

4 EACH	ONE-WAY AMBER MARKERS
14 EACH	ONE-WAY CRYSTAL MARKERS
8 EACH	TWO-WAY AMBER MARKERS
26 EACH	TOTAL