

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
60A62		* (1919.15, 2021-922 PT1 & PT2) R-1		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE																		
				URBAN ROADWAY	RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	COOT LIGHTING									
					016-W923	016-W931	STR NO 016-0142	STR NO 016-1148						Y000	Y007	Y007	SFTY-2A	SFTY-2A	Y002-1C	SFTY-3N	Y030-1E	Y032-1F
42101416	LUG SYSTEM COMPLETE 16'	EACH	1	1																		
44000100	PAVEMENT REMOVAL	SQ YD	39,601	39,601																		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8,246	8,246																		
44001980	CONCRETE BARRIER REMOVAL	FOOT	73	73																		
44004250	PAVED SHOULDER REMOVAL	SO YD	1,067	1,067																		
50102400	CONCRETE REMOVAL	CU YD	80			79	1															
50200100	STRUCTURE EXCAVATION	CU YD	204			93	111															
50300225	CONCRETE STRUCTURES	CU YD	1				1															
50300255	CONCRETE SUPERSTRUCTURE	CU YD	152.6			152.6																
50300300	PROTECTIVE COAT	SO YD	816			691	13	51	61													
50300510	RUSTICATION FINISH	SO FT	1315			1,315																
50800205	REINFORCEMENT BARS, EPOXY COATED	POLND	18160			18,160																
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2,474	2,474																		
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	996	996																		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	300	300																		
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	3	3																		
550A0660	STORM SEWERS, CLASS A, TYPE 3 15"	FOOT	353	353																		
550A0700	STORM SEWERS, CLASS A, TYPE 3 21"	FOOT	125	125																		
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	111	111																		
55100400	STORM SEWER REMOVAL 10"	FOOT	1,802	1,802																		
55100500	STORM SEWER REMOVAL 12"	FOOT	1,487	1,487																		
55100700	STORM SEWER REMOVAL 15"	FOOT	504	504																		
55101100	STORM SEWER REMOVAL 21"	FOOT	8	8																		
55101600	STORM SEWER REMOVAL 36"	FOOT	20	20																		
58500100	EPOXY MORTAR REPAIR	CU FT	15				15															
58600100	SAND BACKFILL	CU YD	172	172																		
59000100	EPOXY CRACK SEALING	FOOT	477				299	116	62													
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	28				28															
60107700	PIPE UNDERDRAINS 6"	FOOT	9,888	9,888																		
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	238	238																		

\* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH  
 DATE: June 9, 2006 CHECKED BY: RMC

CTE | AECOM

S00-2

9/30/06 9:38:39 AM