F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	247	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A63 * (1919.15, 2021-922 PT1 & PT2) R-2

SUMMARY OF QUANTITIES

					90% FEDERAL / 10% STATE								
						RETAINING WALL	BRIDGE						
				URBAN	URBAN ROADWAY	69TH STREET SOUTHWEST	STR NO 016-0142	STR NO 016-1148	SIGNING	LIGHTING	SURVEILLANCE	SAFETY	CDOT LIGHTING
	CODE NO.	ITEM	UNIT	QUANTITY	J000	Y007	SFTY-2A	SFTY-2A	Y002-1C	Y030-1E	Y032-1F	SFTY-3N	Y030-1E
	20101000	TEMPORARY FENCE	FOOT	1,092	1,092								
	20200100	EARTH EXCAVATION	CU YD	32,031	32,031	△1							
	20200410	EARTH EXCAVATION (SPECIAL)	CU YD	28	28								
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,033	2,033								
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	55		55							
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,500	1,500								
	20800150	TRENCH BACKFILL	CU YD	966.9	966.9								
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	35,907	35,907								
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,280	3,280								
*	21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	5,264	5,264								
*	21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	5,264	5,264								
*	25000210	SEEDING, CLASS 2A	ACRE	1.61	1.61								
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	149	149								
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	148	148								
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	147	147								
NP	25000750	MOWING	ACRE	2.68	2.68								
*	25100630	EROSION CONTROL BLANKET	SQ YD	8,544	8,544								
*	25200200	SUPPLEMENTAL WATERING	UNIT	205.2	205.2								
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5,487	5,487								
	28000510	INLET FILTERS	EACH	129	129								
	31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	4,421	4,421								
	31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	31,282	31,282								
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14.7	14.7								
	40600300	AGGREGATE (PRIME COAT)	TON	72.1	72.1								
	42001300	PROTECTIVE COAT	SQ YD	39,427	39,427								
	42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	27,335	27,335								
	44000100	PAVEMENT REMOVAL	SQ YD	30,474	30,474								
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,220	4,220								
	44001980	CONCRETE BARRIER REMOVAL	FOOT	358	358								
	44004250	PAVED SHOULDER REMOVAL	SQ YD	420	420								

NP = NON-PARTICIPATING

* DENOTES SPECIALTY ITEMS

CTE | AECOM

△1 Rev. 8-21-06 S00-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG

p:\p04685\civil\8-cntrs 18 & 19\stracfr 19\general\s0190012.dgn 6/6/2006 9:39:54 AM