

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94		COOK	247	11
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
60A63		• (1919.15, 2021-922 PT1 & PT2) R-2		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE																
				URBAN		URBAN ROADWAY	RETAINING WALL 69TH STREET SOUTHWEST	BRIDGE		SIGNING	LIGHTING	SURVEILLANCE	SAFETY	CCTV LIGHTING						
				J000	Y007			STR NO 016-0142	STR NO 016-1148						Y002-1C	Y030-1E	Y032-1F	SFTY-3N	Y030-1E	
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	258	258																
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	2,876	2,876																
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	721	721																
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SO FT	12,531	12,531																
X0324112	BARRIER BASE	FOOT	5,617	5,617																
X0324470	CONDUIT ENCASED, REINFORCED CONCRETE, 3-4" DIA., CNC	FOOT	48																	48
X0324697	SOIL STABILIZERS	POUND	206,725	206,725																
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	384	384																
X2020300	EXCAVATE AND PLACE EXISTING GRANULAR MATERIAL	CU YD	1,474	1,474																
X4210400	LUG SYSTEM REMOVAL	EACH	1	1																
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SO YD	6,520	6,520																
X6061003	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.48 (MODIFIED)	FOOT	289	289																
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	1,122	1,122																
X6065740	CONCRETE MEDIAN SURFACE, 5 INCH (MODIFIED)	SO FT	1,201	1,201																
X6370910	CONCRETE BARRIER, SINGLE FACE, 32" HEIGHT	FOOT	885	885																
X6370930	CONCRETE BARRIER, DOUBLE FACE, 32" HEIGHT	FOOT	4,159	4,159																
X6640050	CHAIN LINK FENCE 42", ATTACHED TO STRUCTURE (SPECIAL)	FOOT	549			549														
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	8	8																
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1																
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	240	240																
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	50	50																
X8100045	CONDUIT ENCASED, REINFORCED CONCRETE, 1-3" DIA., CNC	FOOT	235																	235
X8360105	LIGHT POLE FOUNDATION, INTEGRAL WITH BARRIER WALL, 24" DIAMETER	FOOT	13																	13
X0325567	STABILIZED SUB-BASE 4 1/2"	SO YD	35,907	35,907																
XX003988	TEMPORARY CONCRETE BARRIER REMOVAL	FOOT	5,112	5,112																
XX004201	PAVEMENT REINFORCEMENT 14"	SO YD	27,335	27,335																
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2																	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2																	2
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	846	846																

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: June 9, 2006
DRAWN BY: NJH
CHECKED BY: RMG

CTE | AECOM

Rev. B-21-06

S00-5

5/30/06 AM