

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE																	
				URBAN ROADWAY		RETAINING WALL	BRIDGE		SIGNING	LIGHTING	SURVEILLANCE	SAFETY	CDOT LIGHTING								
				J000	URBAN	69TH STREET SOUTHWEST	STR NO 016-0142	STR NO 016-1148	Y002-1C	Y030-1E	Y032-1F	SFTY-3N	Y030-1E								
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1																	
Z0076600	TRAINEES	HOUR	1,500	1,500																	
X0325491	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., SCH. 80 PVC	FOOT	351																		351
X0325492	CONVENTIONAL STREET LIGHTING UNIT WALL MOUNTED, INSTALL ONLY	EACH	5																		5
X0325494	GALVANIZED STEEL CONDUIT IN TRENCH, 2" DIA., SCH. 40	FOOT	70																		70
B0700110	GROUND ROD, 3/4" DIA. X 10 FT.	EACH	5																		5
TWY02040	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1																		1
X0945500	PAINT EXISTING POLE COMPLETE	EACH	5																		5
X0325495	REMOVE EXISTING STREET LIGHTING UNIT AND SALVAGE	EACH	5																		5
X0325496	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	70																		70
X0325493	CABLE IN CONDUIT, <sup>TRIPLEX,</sup> 2-1/C NO. 6 AND 1-1/C NO. 8 GND.	FOOT	501																		501
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	1,618				715	903													
X0325497	STRUCTURAL REPAIR OF CONCRETE (SPECIAL)	SQ FT	1,196				1,196														
X0325498	DUCTILE IRON PIPE	FOOT	134	134																	
W900200	NON-SPECIAL WASTE DISPOSAL	CU. YD.	2,000	2,000																	
W900450	SPECIAL WASTE PLANS AND REPORTS	L. SUM	1	1																	
W900530	SOIL DISPOSAL ANALYSIS	EACH	2	2																	

© Y080

• DENOTES SPECIALTY ITEMS

REVISIONS		NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
63RD STREET TO GARFIELD BLVD (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE      DRAWN BY: NJH  
DATE: June 9, 2006      CHECKED BY: RMC

CTE | AECOM

Rev. 8-21-06 S00-6

6/9/2006 5:39:37 AM