

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94		COOK	247	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
60A63		(1919.15, 2021-922 PT1 & PT2) R-2		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE										
				URBAN		URBAN ROADWAY	RETAINING WALL 69TH STREET SOUTHWEST	BRIDGE		SIGNING	LIGHTING	SURVEILLANCE	SAFETY	CDDT LIGHTING
				J000	Y007			STR NO 016-0142	STR NO 016-1148					
20101000	TEMPORARY FENCE	FOOT	1,092	1,092										
20200100	EARTH EXCAVATION	CU YD	34,401	34,401										
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	28	28										
20201200	REMOVAL AND DISPOSAL OF UNSPLITABLE MATERIAL	CU YD	2,033	2,033										
20700220	POROUS GRANULAR EMBANKMENT	CU YD	55			55								
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,500	1,500										
20800150	TRENCH BACKFILL	CU YD	966.9	966.9										
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	35,907	35,907										
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	3,280	3,280										
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SO YD	5,264	5,264										
* 21101825	COMPOST FURNISH AND PLACE, 6"	SO YD	5,264	5,264										
* 25000210	SEEDING, CLASS 2A	ACRE	1.61	1.61										
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	149	149										
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	148	148										
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	147	147										
NP 25000750	MOWING	ACRE	2.68	2.68										
* 25100630	EROSION CONTROL BLANKET	SQ YD	8,544	8,544										
* 25200200	SUPPLEMENTAL WATERING	UNIT	205.2	205.2										
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5,487	5,487										
28000510	INLET FILTERS	EACH	129	129										
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	4,421	4,421										
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	31,282	31,282										
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14.7	14.7										
40600300	AGGREGATE (PRIME COAT)	TON	72.1	72.1										
42001300	PROTECTIVE COAT	SQ YD	39,427	39,427										
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	27,335	27,335										
44000100	PAVEMENT REMOVAL	SQ YD	30,474	30,474										
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,220	4,220										
44001980	CONCRETE BARRIER REMOVAL	FOOT	358	358										
44004250	PAVED SHOULDER REMOVAL	SQ YD	420	420										

NP = NON-PARTICIPATING

\* DENOTES SPECIALTY ITEMS

CTE | AECOM

SQQ-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
63RD STREET TO GARFIELD BLVD (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: June 9, 2006  
DRAWN BY: NJH  
CHECKED BY: RMG

6/9/2006 9:39:54 AM