

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	2006-003 TS	COOK	63	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO. 60B13				

SUMMARY OF QUANTITIES		UNIT	URBAN TOTAL QUANT. 80% FED. 20% STATE	CONSTRUCTION TYPE CODE																				INTERCONNECT SCHEMATIC IL. 64 FROM RIDGELAND TO AUSTIN BLVD.		
CODE NO	ITEM			IL. RTE 64 AT CORNELL AVE.	IL. RTE 64 AT HAWTHORNE AVE.	IL. RTE 64 @ 30TH AVE/RUBY	IL. RTE 64 AT 25TH AVE.	IL. RTE 64 AT JEWEL DR.	IL. RTE 64 AT 19TH/BROADWAY	IL. RTE 64 AT 15TH AVE.	IL. RTE 64 AT 14TH AV/GEORGE	IL. RTE 64 AT WINTSTON PK PL	IL. RTE 64 AT 9TH AV	IL. RTE 64 AT 7TH AV	IL. RTE 64 AT 5TH AV	IL. RTE 64 AT 1ST AV	IL. RTE 64 AT FOLK PLAZA	IL. RTE 64 AT THATCHER RD.	IL. RTE 64 AT 76TH AV.	IL. RTE 64 AT IL. 43 (HARLEM)	IL. RTE 64 AT OAK PARK	IL. RTE 64 AT NATOMA	IL. RTE 64 AT NARRAGANSETT		IL. RTE 64 AT RIDGELAND	IL. RTE 64 AT AUSTIN BLVD.
				Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-IF		Y031-IF	Y031-IF
* 44000600	SIDEWALK REMOVAL	SQ. FT.	160																					80	80	
67100100	MOBILIZATION	LSUM	1	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.01	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LSUM	1	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.01	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.01	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	LSUM	1	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.045	.01	
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	2220																					450	1770	
81400100	HANDHOLE	EACH	4																					2	2	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	22	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
X032598	FULL-ACTUATED CONTROLLER	EACH	15	1		1	1	1	1	1	1	1			1	1	1			1	1					
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	6		1								1	1					1			1		1	1	
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1																1							
86000100	MASTER CONTROLLER	EACH	1																1							
86400100	TRANSCEIVER - FIBER OPTIC	EACH	22	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	810																					810		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	70																					70		
87900200	DRILL EXISTING HANDHOLE	EACH	4																							4
88500100	INDUCTIVE LOOP DETECTOR	EACH	63		11									8	15				9				7	13		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	36																8	8	4	8	8	8		
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	3																1	2						
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	8																2	3	2	1				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	6																2	1				3		
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED ALUMINUM	EACH	26																4	4	8	4		6		
88600100	DETECTOR LOOP, TYPE 1	FOOT	135																					135		
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	70																					70		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	22	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C	FOOT	2220																					70	2150	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. RTE. 64 FROM
CORNELL AV. TO AUSTIN BLVD.
PLOT DATE: 6/23/2006