

CONSTRUCTION NOTES:

	NEW FULL-ACTUATED CONTROLLER	NEW FULL-ACTUATED CONTROLLER ANDTYPE IV CABINET	NEW FULL-ACTUATED CONTROLLER ANDTYPE V CABINET		NEW INDUCTIVE LOOP DETECTOR
* IL. RTE 64 AT CORNELL AVE.	X			EXISTING 3 PAIR NO. 18 CABLE SHALL REMAIN IN PLACE AND ACT AS TRACER CABLE.	
** IL. RTE 64 AT HAWTHORNE AVE.		X			X
* IL. RTE 64 AT 30TH AVE./RUBY ST.	X				
* IL. RTE 64 AT 25TH AVE.	X				
* IL. RTE 64 AT JEWEL DR.	X				
* IL. RTE 64 AT 19TH/BROADWAY	X				
* IL. RTE 64 AT 15TH AVE.	X				
* IL. RTE 64 AT 14TH AV/GEORGE ST.	X				
* IL. RTE 64 AT WINTSTON PARK PLAZA	X				
* IL. RTE 64 AT 9TH AV	X				
* IL. RTE 64 AT 7TH AV	X				
** IL. RTE 64 AT 5TH AV		X			X
** IL. RTE 64 AT 1ST AV		X			X
* IL. RTE 64 AT POLK PLAZA	X				
* IL. RTE 64 AT THATCHER RD.	X				
* IL. RTE 64 AT 76TH AV.	X				
** IL. RTE 64 AT IL. 43 (HARLEM)			X		
** IL. RTE 64 AT OAK PARK AV.		X			X
* IL. RTE. 64 AT NATOMA	X				
* IL. RTE. 64 AT NARRAGANSETT	X				
** IL. RTE. 64 AT RIDGELAND		X		X	
** IL. RTE. 64 AT AUSTIN BLVD.		X		X	

PROPOSED TRACER CABLE TO BE INSTALL FROM RIDEGLAND TO AUSTIN BLVD.

* THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

15 EACH CONTROLLER

** THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

7 EACH CONTROLLER AND CABINET (COMPLETE)

RELOCATE EXISTING LIGHT DETECTOR AMPLIFIER TO NEW CONTROLLER AND NEW CONTROLLER AND CABINET. THIS ITEM SHALL BE INCLUDED IN PAY ITEM OF NEW CONTROLLER.