

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-031 BY	WILL	137	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

URBAN
100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	CSXRR	SUNNYLAND DRAIN	IL 59	SFTY-2A	SFTY-3N
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2					
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	1					
63200310	GUARDRAIL REMOVAL	FOOT	699	699					
63300800	GUARD RAIL POST VERTICAL ADJUSTMENT	EACH	5	5					
64200105	SHOULDER RUMBLE STRIP	FOOT	987	987					
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	12	12					
67001000	MOBILIZATION	L SUM	1	1					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	39998	39998					
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	4786	4786					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	15313	15313					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	7488	7488					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	467	467					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12921	12921					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1742	1742					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	466	466					
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	103	103					
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	1596	1596					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	14505	14505					
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	1803	1803					
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	583	583					
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6					
* 78100300	REPLACEMENT REFLECTOR	EACH	382	382					
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	1500	1500					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	27	27					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	4	4					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1					
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	12396	12396					
* 81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	453		406	47			
X0322066	PROTECTIVE SHIELD (PERMANENT)	SQ YD	527				527		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	340	340					
X0322323	WEED CONTROL, TEASEL	GALLON	2.5	2.5					
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	6	6					
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	475	475					
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	475	475					
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2251		1249	1002			
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3	3					
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	699	699					
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	699	699					
X3120700	STABILIZED SUB-BASE 4, SUPERPAVE	SQ YD	12035	12035					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	93	93					
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	93	93					
X4073161	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 14"	SQ YD	300	300					
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	23	23					
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	12	12					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	274	274					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (OVER CSX RR AND SUNNYLAND DRAIN)
BRIDGE WIDENING

SUMMARY OF QUANTITIES
III

SCALE: N.T.S.
DATE 07/21/06

DRAWN BY AG
CHECKED BY DDH

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

Rev. 9-1-06

DATE = 07/21/06
DRAWN BY = AG
CHECKED BY = DDH
PLOT DATE = 07/21/06
PLOT NAME = 7-19-2006-13-6082
USER NAME = JUSER18
S:\DOCUMENT\02\31815M\CT\VL\CON\G08P1\0203.SHT