

SUGGESTED STAGES OF CONSTRUCTION

PRE-STAGE

- INSTALL "CHANGEABLE MESSAGE BOARDS" PRIOR TO THE START OF CONSTRUCTION ON FAI-55.
- CONSTRUCT PROPOSED DETENTION BASINS IN THE N.W. AND S.E. QUADRANTS OF THE U.S. ROUTE 30 INTERCHANGE, CONSTRUCT PROPOSED PIPE CULVERT BENEATH FRONTAGE ROAD SOUTH OF U.S. ROUTE 30 AS SHOWN ON THE PLANS USING STANDARD 701201.
- CONSTRUCT PROPOSED STORM SEWER LATERALS BENEATH EXISTING I-55 PAVEMENT AS SHOWN ON THE PLANS USING STANDARDS 701400 AND 701401 (SEE SHEET MOT-TYP-03 FOR STAGING), LANE CLOSURES WILL ONLY BE ALLOWED DURING THE OFF PEAK HOURS AS DETAILED IN THE SPECIAL PROVISION FOR "KEEPING EXPRESSWAY OPEN TO TRAFFIC". ALL STORM SEWER LATERAL WORK SHALL BE COMPLETED EACH NIGHT BEFORE OPENING LANE TO THE TRAFFIC IN THE MORNING.
- 4. RELOCATE EXISTING LIGHTING UNITS AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER.
- ESTABLISH TRAFFIC CONTROL ON U.S. ROUTE 30 AS SHOWN ON THE PLANS, BEGIN SUBSTRUCTURE WIDENING FOR THE I-55 BRIDGES OVER U.S. ROUTE 30, EJ&R R.R., AND MS (ABANDONED) R.R.
- CONSTRUCT STABILIZED CONSTRUCTION ENTRANCES TO AND FROM WORK AREAS AS SHOWN ON THE DETAIL AND APPROVED BY THE ENGINEER.
- REMOVE EXISTING PAVEMENT MARKING AND RAISED REFLECTIVE PAVEMENT MARKERS THAT CONFLICT WITH TEMPORARY TRAFFIC LANES.
- ESTABLISH STAGE I TRAFFIC CONTROL, INSTALL TEMPORARY PAVEMENT MARKINGS, TEMPORARY CONCRETE BARRIER AND SHIFT TRAFFIC TO STAGE I TEMPORARY TRAFFIC LANES AS SHOWN ON THE STAGING PLANS AND AS DIRECTED BY THE ENGINEER.

STAGE I

- REMOVE BITUMINOUS SHOULDER AND EXISTING GUARDRAIL FROM THE MEDIAN AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- COMPLETE STAGE I STRUCTURAL WORK AT THE U.S. ROUTE 30, EJ&E RAILROAD, MINK CREEK, MS (ABANDONED) RAILROAD AND LILY CACHE SLOUGH STRUCTURES AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER.
- INSTALL PROPOSED MAIN DRAIN STORM SEWER SYSTEM AS SHOWN ON PLANS OR AS DIRECTED BY THE ENGINEER, EXCAVATE AND CONSTRUCT EMBANKMENT.
- CONSTRUCT AGGREGATE SUBGRADE, PROPOSED CONCRETE BASE, AND CONCRETE BARRIER AS SHOWN ON THE PLANS.
- CONSTRUCT PROPOSED POLYMERIZED BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH), SUPERPAVE 12-1/4" FOR NEW INSIDE LANES AND THE INSIDE SHOULDERS AS SHOWN ON THE PLANS.
- CONSTRUCT TEMPORARY DRAINAGE FROM STA. 762+94 TO STA. 782+06 AS SHOWN ON THE STAGE II PLANS AND MOT CROSS SECTIONS OR AS DIRECTED BY THE ENGINEER.
- CONSTRUCT TEMPORARY PAVEMENT BETWEEN SB AND NB EXISTING INSIDE LANES, AND INSTALL TEMPORARY CONCRETE BARRIER FROM STA, 762+94 TO STA, 782+06 AS SHOWN ON THE STAGE II PLANS AND MOT CROSS SECTIONS OR AS DIRECTED BY THE ENGINEER.
- ONCE CONSTRUCTION OF THE PROPOSED CONCRETE BARRIER AND POLYMERIZED BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) FOR THE NEW INSIDE LANES AND SHOULDERS IS COMPLETE, THE CONTRACTOR SHALL REMOVE CONSTRUCTION WORK ZONE DRIVEWAYS.
- REMOVE STAGE I TEMPORARY PAVEMENT MARKING AND INSTALL STAGE II TEMPORARY PAVEMENT MARKING AS SHOWN ON THE STAGING PLANS AND AS DIRECTED BY THE ENGINEER.
- 10. ESTABLISH STAGE II TRAFFIC CONTROL AND SHIFT TRAFFIC TO STAGE II TEMPORARY TRAFFIC LANES AS SHOWN ON THE STAGING PLANS AND AS DIRECTED BY THE ENGINEER.

STAGE II

- 1. REMOVE OUTSIDE BITUMINOUS SHOULDERS AND EXISTING GUARDRAIL AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- 2. COMPLETE STAGE II STRUCTURAL WORK AT THE U.S. ROUTE 30. EJ&E R.R., MS (ABANDONED) R.R. AND LILY CACHE SLOUGH STRUCTURES AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER
- 3. CONSTRUCT PROPOSED AUXILIARY LANES UP TO THE BOTTOM OF THE PROPOSED SURFACE COURSE AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER.
- 4. CONSTRUCT NEW OUTSIDE SHOULDERS AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER.
- 5. COMPLETE ALL GUARDRAIL WORK AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

STAGE II (CONT.)

6. COMPLETE ALL SIGN WORK AS SHOWN ON THE PAVEMENT MARKING AND SIGNING PLANS AND AS DIRECTED BY THE ENGINEER

F.A.P. SECTION COUNTY 55 2006-032 BY WILL 505 102 STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT MOT-TYP-01 OF 05

CONTRACT NO. 60B86

- 7. SHIFT SOUTHBOUND TRAFFIC FROM THE TEMPORARY PAVEMENT INTO EXISTING SOUTHBOUND PAVEMENT.
- 8. REMOVE STAGE II TEMPORARY PAVEMENT AND TEMPORARY CONCRETE BARRIER FROM STA. 762+94 TO STA. 782+06.
- 9. CONSTRUCT TEMPORARY DRAINAGE FROM STA. 761+75 TO STA. 782+25 AS SHOWN ON THE STAGE III PLANS AND MOT CROSS SECTIONS OR AS DIRECTED BY THE ENGINEER.
- 10. CONSTRUCT TEMPORARY PAVEMENT BETWEEN SB AND NB EXISTING INSIDE LANES, AND INSTALL TEMPORARY CONCRETE BARRIER FROM STA. 761+75 TO STA. 782+25 AS SHOWN ON THE STAGE III PLANS AND MOT CROSS SECTIONS OR AS DIRECTED BY THE ENGINEER.
- 11. REMOVE STAGE II TEMPORARY PAVEMENT MARKING AND INSTALL STAGE III TEMPORARY PAVEMENT MARKING AS SHOWN ON THE STAGING PLANS AND AS DIRECTED BY THE ENGINEER.
- 12. ESTABLISH STAGE III TRAFFIC CONTROL, AND SHIFT TRAFFIC TO STAGE III TEMPORARY TRAFFIC LANES AS SHOWN ON THE STAGING PLANS AND AS DIRECTED BY THE ENGINEER.

STAGE III (EJ&E R.R. AND LILY CACHE SLOUGH STRUCTURES)

- 1. COMPLETE ALL STRUCTURAL WORK AT THE FUSE RATEROAD STRUCTURE AS SHOWN ON THE PLANS AND DIRECTED BY THE ENGINEER.
- 2. COMPLETE ALL STRUCTURAL WORK AT THE LILY CACHE SLOUGH STRUCTURE AS SHOWN ON THE PLANS AND DIRECTED BY THE ENGINEER.
- 3. REMOVE STAGE III TEMPORARY PAVEMENT MARKING AND INSTALL STAGE IV TEMPORARY PAVEMENT MARKING AS SHOWN ON THE STAGING PLANS AND AS DIRECTED BY THE ENGINEER.
- 4. ESTABLISH STAGE IV TRAFFIC CONTROL, AND SHIFT TRAFFIC TO STAGE IV TEMPORARY TRAFFIC LANES AS SHOWN ON THE STAGING PLANS AND AS DIRECTED BY THE ENGINEER.

STAGE IV (LILY CACHE SLOUGH STRUCTURE)

- 1. REMOVE TEMPORARY PAVEMENT AND TEMPORARY CONCRETE BARRIER FROM STA. 761+75 TO STA. 782+25.
- INSTALL PROPOSED DRAINAGE WITHIN WORK ZONE AREA FROM STA. 761+75 TO STA. 782+25
- 2. AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- 3. CONSTRUCT AGGREGATE SUBGRADE, PROPOSED CONCRETE BASE AND CONCRETE BARRIER FROM STA. 761+75 TO STA. 782+25 AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER.
- 4. CONSTRUCT PROPOSED POLYMERIZED BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH), SUPERPAVE 12-1/4" FOR NEW INSIDE LANES AND THE INSIDE SHOULDERS FROM STA. 761+75 TO STA. 782+25 AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER.
- 5. REMOVE STAGE IV TEMPORARY PAVEMENT MARKING AND TRAFFIC CONTROL.

STAGE V

- 1. USING FREEWAY STANDARDS 701400, 701401 AND 701446 FOR ONE LANE AND TWO LANE CLOSURES DURING OFF PEAK HOURS AS DETAILED IN THE SPECIAL PROVISION FOR "KEEPING EXPRESSWAY OPEN TO TRAFFIC" THE CONTRACTOR SHALL PERFORM-THE FOLLOWING OPERATIONS:
 - A. MILL EXISTING LANES AND CONSTRUCT THE SURFACE COURSE IN THE FOLLOWING ORDER:
 - 1 CENTER LANES
 - 2 INSIDE LANES
 - 3 INSIDE SHOULDERS
 - 4 OUTSIDE LANES
- B. THE CONTRACTOR SHALL RESURFACE MILLED PAVEMENT WITHIN FOUR CALENDAR DAYS.
- C. CONSTRUCT RUMBLE STRIPS, INSTALL PERMANENT PAVEMENT MARKING AND RAISED REFLECTIVE PAVEMENT MARKERS AS SHOWN ON THE PAVEMENT MARKING AND SIGNING PLANS.
- D. OPEN LANES TO TRAFFIC AS SHOWN ON THE PAVEMENT MARKING PLANS.

	REVISIONS NAME	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 55 US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH
			SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL GENERAL NOTES
PARSONS BRINCKERHOFF			SCALE: NONE DRAWN BY: DM

DATE: 06-30-06

CHECKED BY: DVS

- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION STAGING AND TRAFFIC CONTROL OPERATIONS WITH ADJACENT CONTRACTS. THE COST OF ANY ADDITIONAL TRAFFIC CONTROL AND/OR TEMPORARY CONSTRUCTION ITEMS REQUIRED FOR SUCH COORDINATION WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR "TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)"
- 2. PRIOR TO REMOVING TRAFFIC CONTROL FOR LANE CLOSURES THE CONTRACTOR SHALL SWEEP THE PAVEMENT SURFACE CLEAN.
- THE CONTRACTOR SHALL INSTALL TEMPORARY W21-1108 SIGNS ON BOTH SIDES OF THE ROADWAY IN ADVANCE OF THE AREAS WITH A GRADE DIFFERENTIAL BETWEEN LANES AND AFTER EACH ENTRANCE RAMP, SIGN LOCATIONS SHALL BE APPROVED BY THE ENGINEER, THE COST OF THE SIGNS WILL NOT BE PAID SEPARATELY BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR "TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)". THESE SIGNS SHALL BE 48X48 INCHES.
- THE REGULATORY SPEED LIMIT SHALL BE REDUCED TO 55 MPH DURING STAGE I ADJACENT TO AND BEFORE THE WORK AREAS WHERE TEMPORARY CONCRETE BARRIER IS INSTALLED AND TO 45 MPH DURING STAGE I AND II ADJACENT TO WORK AREAS WHERE TEMPORARY CONCRETE BARRIER IS NOT INSTALLED AS FOLLOWS:
 - A. IN CONJUNCTION WITH IMPLEMENTING TRAFFIC CONTROL AS SHOWN ON THE PLANS FOR STAGES I AND II, THE CONTRACTOR SHALL:
 - SIMULTANEOUSLY COVER THE EXISTING REGULATORY SPEED LIMIT SIGNS AND ERECT 55 OR 45 MPH REGULATORY SPEED LIMIT SIGNS (R2-1, 48"X60") ADJACENT TO ALL EXISTING SPEED LIMIT SIGNS WITHIN THE WORK AREA LIMITS AS DIRECTED BY THE ENGINEER.
 - SIMULTANEOUSLY ERECT SIGNS AS SHOWN IN THE "SPEED LIMIT REDUCTION SIGNING" DIAGRAM ON BOTH SIDES OF THE TRAVELED WAY AND COVER THE EXISTING REGULATORY SPEED LIMIT SIGNS WITHIN THE LIMITS OF THE "SPEED LIMIT REDUCTION SIGNING."
 - B. THE EXISTING SPEED LIMIT SIGNING OUTSIDE THE WORK AREA LIMITS AND BEYOND THE "SPEED LIMIT REDUCTION SIGNING" SHALL BE MAINTAINED, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 - C. THE CONTRACTOR SHALL UNCOVER THE EXISTING SPEED LIMIT SIGNS AND REMOVE THE 55 OR 45 MPH REGULATORY SPEED LIMIT SIGNS SIMULTANEOUS WITH THE REMOVAL OF TRAFFIC CONTROL DEVICES IN ANY SEGMENT OF THE ROADWAY AS DIRECTED BY THE ENGINEER.
 - D. THE COST OF THIS WORK (NOTE 5) SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR "TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)."
- 5. THE PROJECT WORK AREA CONSISTS OF ROADWAY AND BRIDGE WORK WITHIN THE FOLLOWING THREE MAIN CONSTRUCTION SEGMENTS:
 - U.S. ROUTE 30, E.J. & E. RAILROAD, AND MINK CREEK
 - MATERIAL SERVICE RAILROAD (ABANDONED)
 - LILY CACHE SLOUGH

WORK ZONE TRAFFIC CONTROL DEVICES AND SIGNING SHALL BE PLACED WITHIN AND BETWEEN THESE CONSTRUCTION SEGMENTS AS SHOWN ON THE MOT PLANS OR AS DIRECTED BY THE

- 6. DURING STAGE I THE CONTRACTOR SHALL ERECT REGULATORY HIGHWAY SIGNS R4-5 (48"X60") "TRUCKS USE LEFT LANE" ON BOTH SIDES OF THE TRAVEL LANES AT 1/2 MILE AND 1 MILE IN ADVANCE OF THE WORK ZONE, AT 1/2 MILE INTERVALS ADJACENT TO THE WORK ZONE, AND AT EACH ENTRANCE RAMP OF THE PROJECT AS DIRECTED BY THE ENGINEER. THE SIGNS SHALL ONLY BE PLACED ADJACENT TO THE ROADWAY, WHICH IS LOCATED WITHIN THE WORK ZONE AREAS. THE SIGNS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR "TEMPORARY INFORMATION SIGNING".
- DRUMS SHALL NOT BE PLACED IN THE LANE WHICH IS OPEN TO TRAFFIC. DURING MILLING AND PAVING OPERATIONS. THE CONTRACTOR SHALL USE ONE FOOT VERTICAL BARRICADES WITH STEADY BURN LIGHTS ALONG THE MILLING AND PAVING OPERATIONS. THE TYPE OF VERTICAL BARRICADES SHALL BE APPROVED IN WRITING BY THE ENGINEER PRIOR TO BEING USED ON THE PROJECT. DRUMS OR TYPE II BARRICADES SHALL BE USED TO DELINEATE ALL OPEN RAMPS THROUGHOUT THE WORK ZONE.
- SINCE THIS IS AN EXPRESSWAY FACILITY, THE CONTRACTOR MAY HAVE CREWS WORKING IN BOTH DIRECTIONS AT THE SAME TIME.
- SEE GENERAL NOTES FOR TREATMENT OF RAISED REFLECTIVE PAVEMENT MARKERS THAT CONFLICT WITH THE TEMPORARY TRAFFIC LANES.

LIST OF TRAFFIC CONTROL STATE AND DISTRICT 1 STANDARDS

TOTAL SHEET SHEETS NO. SECTION COUNTY WILL 55 2006-032 BY 505 103 STA. TO STA. FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT MOT-TYP-02 OF 05

CONTRACT NO. 60B86

STATE

OFF-ROAD OPERATIONS, MULTILANE, 4.5 m (15') TO 600 mm (24") FROM EDGE OF PAVEMENT 701101

701106 OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 4.5 m (15') AWAY

APPROACH TO LANE CLOSURE FREEWAY/EXPRESSWAY 701201

LANE CLOSURE, 2L, 2W, DAY ONLY FOR SPEED > OR = 45 MPH 701400

LANE CLOSURE, FREEWAY/EXPRESSWAY 701401

701402 LANE CLOSURE, FREEWAY/EXPRESSWAY WITH BARRIER

LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > OR = 45 MPH 701411

TWO LANE CLOSURE FREEWAY/EXPRESSWAY 701446

URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN. 701601

TRAFFIC CONTROL DEVICES 702001

TEMPORARY CONCRETE BARRIER 704001

DISTRICT 1

TRAFFIC CONTROL DETAILS FRO FREEWAY SINGLE AND MULTI-LANE WEAVE TC09


TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) TC11

MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS TC12

TC13 DISTRICT ONE TYPICAL PAVEMENT MARKINGS

TRAFFIC CONTROL DETAILS FOR SHOULDER CLOSURES PARTIAL RAMP CLOSURES TC17


SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS




SPEED LIMIT REDUCTION SIGNING

* THE SIGNS AND SEGMENTS MARKED WITH AN ASTERISK ARE NOT REQUIRED WHEN THE SPEED LIMIT IS ONLY REDUCED TO 55 M.P.H.

	REVISIONS NAME	DATE	ILLINOIS DEPARTMENT OF T FAI ROUTE 5:	5	
			US 30 (PLAINFIELD ROAD) TO L	ILY CACHE SL.	.OUGH
			SUGGESTED STAGE	'S OF	
			CONSTRUCTION AND	TRAFFIC	
			CONTROL GENERAL	NOTES	
PARSONS					
BRINCKERHOFF			SCALE: NONE	DRAWN BY: D	М
VEARS			DATE: 07-21-06	CHECKED BY: [DVS



PRE-STAGE, PHASE I STORM SEWER LATERALS CONSTRUCTION




PRE-STAGE, PHASE II STORM SEWER LATERALS CONSTRUCTION


NOTE:
STORM SEWER LATERAL CONSTRUCTION SHALL BE COMPLETED
DURING OFF-PEAK HOURS AS APPROVED BY THE ENGINEER.
HIGHWAY STANDARDS 701400 AND 701404 SHALL APPLY.


LEGEND

- 1 PVMT MARKING TAPE, TYPE III 4" (WHITE)
- 2 PVMT MARKING TAPE, TYPE III 5" SKIP-DASH (30FT/10FT)
- 3 PVMT MARKING TAPE, TYPE III 4" (YELLOW)
- 4 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90, 1 3/4"
- (5) BITUMINOUS BASE COURSE, SUPERPAVE, N90, 10 1/4"
- 6 EXISTING AGGREGATE SHOULDER
- (7) AGGREGATE SHOULDER, TYPE B
- VERTICAL PANELS OR VERTICAL BARRICADES AT 100' IN CURVES AND 200' IN TANGENTS
- ☐ DRUMS W/ STEADY BURN LIGHTS AT 50' C-C IN TAPERS AND 100' C-C IN TANGENTS
- WORK ZONE
- TRAFFIC FLOW ARROW
- TEMPORARY CONCRETE BARRIER

PRF-STAGE








TEMPORARY CONCRETE BARRIER DETAIL

 TYPE C MONO-DIRECTIONAL REFLECTORS SHALL BE PLACED AT 10' C-C ALONG THE BARRIER WALL THROUGHOUT THE LIMITS OF THE PROJECT. THIS WORK WILL BE PAID AT AT THE CONTRACT UNIT COST FOR "MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR".



CONSTRUCTION TYPICAL SECTION STAGE I & II

STA. 762+94 TO STA. 782+06 STAGE I
STA. 761+75 TO STA. 782+25 STAGE II
SEE MOT CROSS SECTIONS FOR DETAILS
(TEMPORARY PAVEMENT CONSTRUCTION NEAR LILY CACHE SLOUGH)

NOTE:

DRUMS SHALL BE PLACED AT 100 FT INTERVALS ALONG THE INSIDE AND OUTSIDE LANES BETWEEN CONSTRUCTION SEGMENTS, OR AS DIRECTED BY THE ENGINEER.

LEGEND

- 1 PVMT MARKING TAPE, TYPE III 4" (WHITE)
- 2 PVMT MARKING TAPE, TYPE III 5" SKIP-DASH (30FT/10FT)
- 3 PVMT MARKING TAPE, TYPE III 4" (YELLOW)
- BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90, 1 3/4"
- (5) BITUMINOUS BASE COURSE, SUPERPAVE, N90, 10 1/4"
- 6 EXISTING AGGREGATE SHOULDER
- 7) AGGREGATE SHOULDER, TYPE B
- VERTICAL PANELS OR VERTICAL BARRICADES AT 100' IN CURVES AND 200' IN TANGENTS
- DRUMS W/ STEADY BURN LIGHTS AT 50' C-C IN TAPERS AND 100' C-C IN TANGENTS

WORK ZONE


TRAFFIC FLOW ARROW

TEMPORARY CONCRETE BARRIER

STAGE I

	REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION				
	NAME	DATE					
	D. MELNIK	08/01/06	FAI ROUTE 55				
			US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH	ı			
			SUGGESTED STAGES OF				
			CONSTRUCTION AND TRAFFIC				
			CONTROL GENERAL NOTES				
F		+	SCALE: NONE DRAWN BY: DM				
-		1	DATE: 06-30-06 CHECKED BY: DVS				

PARSONS BRINCKERHOFF



MIXTURE REQUIREMENTS

MIXTURE TYPE	AC TYPE	RAP %	AIR VOIDS
BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D" N90	PG 64-22	10	4% e 90
BITUMINOUS BASE COURSE, SUPERPAVE, IL-19, N90-MIN LIFT 2 1/4"	PG 64-22	10	4% @ 90
CLASS D PATCHES (BINDER IL-25, N105)	PG 64-22	10	4% @ 105
BITUMINOUS REPLACEMENT OVER PATCHES (BINDER IL-25, N105)	PG 64-22	10	4% @ 105

WEIGHT NOTE:

1) THE UNIT WEIGHT OF 112 LBS/SQ YD/ INCH THICKNESS WAS USED TO CALCULATE ALL OTHER BITUMINOUS SURFACE MIXTURES.

NOTE:

DRUMS SHALL BE PLACED AT 100 FT INTERVALS ALONG THE INSIDE AND OUTSIDE LANES BETWEEN CONSTRUCTION SEGMENTS, OR AS DIRECTED BY THE ENGINEER.

LEGEND


- PVMT MARKING TAPE, TYPE III 4" (WHITE)
- PVMT MARKING TAPE, TYPE III 5" SKIP-DASH (30FT/10FT)
- PVMT MARKING TAPE, TYPE III 4" (YELLOW)
- BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90, 1 3/4"
- BITUMINOUS BASE COURSE, SUPERPAVE, N90, 10 1/4"
- EXISTING AGGREGATE SHOULDER
- AGGREGATE SHOULDER, TYPE B
 - VERTICAL PANELS OR VERTICAL BARRICADES AT 100' IN CURVES AND 200' IN TANGENTS
- DRUMS W/ STEADY BURN LIGHTS AT 50' C-C IN TAPERS AND 100' C-C IN TANGENTS

WORK ZONE

TRAFFIC FLOW ARROW

TEMPORARY CONCRETE BARRIER

STAGE II




ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 55 US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH


SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL GENERAL NOTES


DATE: 07-21-06


DRAWN BY: DM CHECKED BY: DVS FINAL


CONTRACT NO. 60B86
















































































 CONTRACT
 NO.
 60B86

 COUNTY
 TOTAL SHEET NO.

 WILL
 505
 135
 F.A.P. SECTION COUNTY **LEGEND** 55 2006-032 BY (ABC) SEE IDOT STANDARD 701400 STA. 787+00 TO STA. 817+00 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT MOTIII-08 OF 08 W2O-1(0)-48 W16-3A(0)-3612 WORK ZONE SPEED LIMIT 55 ROAD CONSTRUCTION 2 MILES AHEAD W20-1(0)-48 W20-1(0)-48 ROAD CONSTRUCTION AHEAD WORK ZONE PUBLIC INFORMATION SIGN BEGINS SPEED LIMIT 55 \$375 FINE MINIMUM X MILES R2-1-3648 R2-5c-3648 FRONTAGE RD. └-¢ 1-55 PVMT MARKING TAPE, TYPE III 4" (WHITE) PVMT MARKING TAPE, TYPE III 5" SKIP-DASH (WHITE-30 FT/10 FT) PVMT MARKING TAPE, TYPE III 4" (YELLOW) PVMT MARKING TAPE, TYPE III 4" SKIP-DASH (WHITE-6 FT/2 FT) DRUMS W/ STEADY BURN LIGHTS *See Drawing For Spacing BARRICADE, TYPE III WITH TWO FLASHING LIGHTS

STAGE III

REVISIONS
NAME
DATE


SONS
CKERHOFF


REVISIONS


ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH
SUGGESTED STAGES OF CONSTRUCTION
AND TRAFFIC CONTROL

SCALE: 1" = 50'
DATE: 06-30-06
CHECKED BY: DM

PARSONS BRINCKERHOFF








FINAL

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT



"TRUCK LEAVING ON LEFT/RIGHT" AS APPLICABLE. REMOTE CONTROLLED 8" CAPS 48"×48" SIGN 8"CAPS FLASHING LIGHTS
REQUIRED FOR "TRUCKS
ENTERING ON LEFT/RIGHT" SIGN TRUCKS ENTERING FLAGGER WORK AREA ON LEFT DRIVEWAY AHEAD AHEAD PREPARE TO STOP MIN. SIGN TRAILER MEETING THE REQUIREMENTS OF ARTICLE 1106.04 OF THE STANDARD SPECIFICATIONS MAY BE USED TO SUPPORT THE SIGNS WARNING SIGNS SHALL HAVE BLACK LEGEND ON ORANGE BACKGROUND FLAGGER WITH TRAFF CONTROL SIGN WORK AREA 100'

* SIGNS ARE TO READ "TRUCKS ENTERING ON LEFT/RIGHT"

SEE STAGING AND TRAFFIC CONTROL PLANS FOR LOCATION OF TEMP CONC BARRIER

CONSTRUCTION TRAFFIC UTILIZING WORK AREA EXIT

600'


LEGEND:

150'

EXIST EP

EXIST E-SHLD-

FLAGGER WITH TRAFFIC CONTROL SIGN



SIGN ON SUPPORT

O DRUM W/ MONODIRECTIONAL STEADY BURN LIGHT

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

 \leq

CONSTRUCTION TRAFFIC UTILIZING WORK AREA ENTRANCE

WORK AREA

300'

SEDIMENT CONTROL, STABILIZED

CONSTRUCTION ENTRANCE

EXIST E-SHLD-

TBT = TRAFFIC BARRIER TERMINAL

TCB = TEMPORARY CONCRETE BARRIER

WORK AREA

IMPACT ATTENUATOR

NOTES

DRUMS PLACED WHEN WORK-

AREA OPENING IS CLOSED

. THE "FLAGGER AHEAD" AND "TRUCKS ENTERING OR TRUCKS LEAVING ON LEFT/RIGHT" SIGNS SHALL BE COVERED OR TURNED AWAY FROM TRAFFIC WHEN THE FLAGGING OPERATION CEASES.

75' MIN.

1501

FOR WORK AREA EXIT

PAVEMENT MARKING TAPE, TYPE III, 4" YELLOW

TABLE A
WORK AREA
OPENING LOCATION

1001 MAX

WORK AREA OPENING

HALF ROADWAY PLAN

- 2. THE FLASHING LIGHTS SHALL MEET THE REQUIREMENTS OF ARTICLE 702,05(o) AND BE OPERATED BY THE FLAGGER REMOTELY. THE LIGHTS SHALL BE FLASHING ONLY WHEN A VEHICLE IS ENTERING THE EXPRESSWAY.
- WORK AREA EXIT OPENINGS SHALL BE LOCATED A MINIMUM OF ONE HALF MILE APART.
 WORK AREA EXIT OPENINGS AND WORK AREA ENTRANCE OPENINGS SHALL BE LOCATED A MINIMUM OF 2,300' APART.
 WORK AREA OPENINGS INTO THE MEDIAN FROM BOTH DIRECTIONS OF TRAFFIC SHALL NOT BE PLACED DIRECTLY ACROSS FROM EACH OTHER.
 WORK AREA OPENINGS INSTALLED DURING STAGE I CONSTRUCTION MAY BE LOCATED AS SHOWN IN TABLE A.
 THE WORK AREA OPENING LOCATIONS SHALL BE APPROVED BY THE ENGINEER.
- ALL CONSTRUCTION VEHICLES SHALL EXIT THE WORK AREA AT A WORK AREA OPENING.
- . ALL CONSTRUCTION VEHICLES SHALL ENTER THE WORK AREA AT A WORK AREA ENTRANCE OPENING AND SHALL USE THEIR TURN SIGNALS TO WARN MOTORISTS.

THE CONTRACTOR SHALL PLACE DRUMS WITH STEADY BURNING MONODIRECTIONAL LIGHTS, SPACED AT 10' CENTERS, ACROSS THE WORK AREA OPENING WHEN THE WORK AREA OPENING IS CLOSED. THE COSTS OF INSTALLING, MAINTAINING AND REMOVING THESE DRUMS AND SIGNS SHALL BE INCLUDED IN THE UNIT PRICE BID FOR "TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)".

500'

500'

- WORK AREA OPENINGS SHALL NOT BE SIMULTANEOUSLY USED AS A WORK AREA ENTRANCE AND A WORK AREA EXIT.
- 8. THE CONTRACTOR SHALL CLOSE THE WORK AREA OPENING WHEN REVISING THE SIGNING FROM AN ENTRANCE TO AN EXIT AND FROM AN EXIT TO AN ENTRANCE.
- 9. A FLAGGER IS REQUIRED AT ALL TIMES UNLESS THE WORK AREA OPENING IS CLOSED. THE COST OF THE FLAGGER WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE BID FOR "TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)".
- O. SEE STAGING AND TRAFFIC CONTROL DETAIL FOR EMERGENCY PULLOUT AND EROSION AND SEDIMENT CONTROL DETAIL FOR STABILIZED CONSTRUCTION ENTRANCE.

P DADCONC	}	-
PARSONS	}	-
BRINCKERHOI	FF	-
100 YEARS	- h	-


ILLINOIS DEPARTMENT OF TRANSPORTATION


FAI ROUTE 55


US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH


STAGING AND TRAFFIC CONTROL DETAIL FOR WORK AREA DRIVEWAY ENTRANCE/EXIT


SCALE: NONE DATE: 06-30-06 CHECKED BY: DVS

































































F.A.P. RTE.	SECTION		COUN	TY	TOTAL SHEETS	SHEET NO.	
55	2006-032	BY	W	LL	505	162	
STA.	TO STA.						
ECD DO	AD DICT NO	IS I TAI	DIC CC	A TD	DDO ICCI	-	

EC - 01 OF 10

EROSION AND SEDIMENT CONTROL GENERAL NOTES

- THE WORK DESCRIBED ON THESE DRAWINGS ARE AN INTEGRAL PART OF THE STORM WATER POLLUTION PREVENTION PLAN USED TO OBTAIN A NPDES PERMIT FROM IEPA FOR THE CONSTRUCTION OF THIS PROJECT.
- THE PURPOSE OF THE EROSION AND SEDIMENT CONTROL MEASURES INCLUDED FOR THIS
 PROJECT IS TO LIMIT THE SEDIMENT POLLUTION IMPACT, OF ANY STORM WATER DISCHARGES
 THAT ORIGINATE ON THIS SITE OR OFF-SITE FLOWS THAT FLOW OVER THE DISTURBED AREAS,
 ON DOWNSTREAM AREAS.
- 3. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO INSURE THAT SEDIMENT TRANSPORT OFF THE SITE IS REDUCED BY A COMBINATION OF MINIMIZATION OF EROSION AT THE SOURCE AND INSTALLATION OF SPECIFIC MEASURES TO CONTROL OR REDUCE THE TRANSPORT OF SEDIMENT. A COPY OF THE EROSION AND SEDIMENT CONTROL SCHEDULE BEING IMPLEMENTED BY THE CONTRACTOR WILL BE ON THE CONSTRUCTION SITE AT ALL TIMES.
- 4. TO THE MAXIMUM EXTENT POSSIBLE, ALL FLOWS ORIGINATING OFF THE CONSTRUCTION SITE WILL BE DIVERTED AROUND DISTURBED AREAS OR WILL BE CONVEYED THROUGH THE SITE IN A MANNER THAT UNTREATED ON-SITE RUNOFF DOES NOT MIX WITH THE OFF-SITE RUNOFF.
- 5. ALL RUNOFF ORIGINATING ON DISTURBED AREAS ASSOCIATED WITH THIS PROJECT WILL PASS THROUGH ONE OR MORE MEASURES THAT WILL MINIMIZE THE OFF-SITE SEDIMENT IMPACTS OF THE CONSTRUCTION ACTIVITY.
- 6. ALL PERMANENT SEDIMENT BASINS, PERMANENT STORM WATER CONTROL MEASURES, AND RUNOFF CONTROL MEASURES REQUIRED TO KEEP OFF-SITE RUNOFF FROM FLOWING OVER THE CONSTRUCTION AREA WILL BE INSTALLED BEFORE CLEARING AND STRIPPING OF THE SITE PROCEEDS, PRIOR TO PROCEEDING WITH GENERAL EARTHWORK ON A PROJECT THE CONTRACTOR WILL OBTAIN APPROVAL OF HIS PROPOSED EARTHWORK AND STABILIZATION SCHEDULE.
- 7. A MAXIMUM OF 10 ACRES MAY BE IN SOME STAGE OF GRADING AT A SINGLE TIME.
 ADDITIONAL AREAS (UP TO 10 ACRES) MAY BE CLEARED BUT WILL NOT BE STRIPPED OF
 VEGETATION UNTIL THE GRADED AREAS HAVE BEEN PROTECTED FROM EROSION THROUGH
 INSTALLATION OF EITHER TEMPORARY OR PERMANENT MEASURES. WHENEVER POSSIBLE,
 THE GRADING WILL BE COMPLETED TO THE DESIGN GRADE AND THE PERMANENT VEGETATION
 PLAN IMPLEMENTED PRIOR TO STARTING GRADING ACTIVITIES ON THE NEXT SITE.

 (A) WHEN BALANCING FARTHWORK (BORROW FROM A CUIT USED AS FILL AT A LOCATION
 - A) WHEN BALANCING EARTHWORK (BORROW FROM A CUI USED AS FILL AT A LOCATION DISTANT FROM THE CUIT) THE ENGINEER WILL CONSIDER ALLOWING MORE THAN 10 ACRES OF GRADING AT A TIME. THE 10 ACRES LIMITATION DOES NOT INCLUDE HAUL ROADS, BRIDGE CONSTRUCTION WORK AREAS AND STORAGE AREAS.
- (B) VARIATIONS TO THE ABOVE MAY BE CONSIDERED BY THE ENGINEER UNDER ALL THE FOLLOWING CONDITIONS:
 - IF THE CONTRACTOR FALLS BEHIND SCHEDULE THROUGH NO FAULT OF HIS OWN.
 THE CONTRACTOR MUST PRESENT A SCHEDULE DEMONSTRATING THE NEED FOR SUCH VARIATION IN ORDER TO COMPLETE THE WORK ON TIME.
 - * THE CONTRACTOR MUST COMPLY WITH ALL OTHER CONTRACT REQUIREMENTS.
- 8. DISTURBED AREAS ARE TO BE PROTECTED FROM EROSION IN A TIMELY MANNER. UPON COMPLETION OF GRADING OR CONSTRUCTION, THE AREA WILL BE STABILIZED (USING PERMANENT MEASURES WHEN POSSIBLE) WITHIN 7 CALENDAR DAYS. TEMPORARY STABILIZATION THROUGH USE OF GROUND COVER, MULCHING, OR OTHER APPROVED MEASURES WILL BE INSTALLED WHENEVER SITE DEVELOPMENT WORK, GRADING OR OTHER EARTH DISTURBING ACTIVITIES CEASE TO BE CONTINUOUS FOR A PERIOD EXCEEDING 14 CALENDAR DAYS. THE 7/14 DAY REQUIREMENT IS TAKEN TO MEAN THAT THE STABILIZATION OPERATION IS COMPLETE OR NEARING COMPLETION IN THE DEFINED TIME.
- 9. STABILIZATION OF CUT OR FILL SLOPES WITH TEMPORARY OR PERMANENT EROSION CONTROL MEASURES IS REQUIRED WHENEVER THE CUT OR FILL ACTIVITY REACHES 10 FEET VERTICALLY OR THE FINISHED SLOPE EQUALS 30 FEET, WHICHEVER IS MORE RESTRICTIVE, ONCE THE STABILIZATION MEASURES ARE INSTALLED, THE PLACEMENT OF FILL EXCAVATION ACTIVITIES ARE ALLOWED TO PROCEED.

- 10. THE CONTRACTOR SHALL DESIGNATE ONE OF HIS EMPLOYEES AS RESPONSIBLE FOR IMPLEMENTATION OF THE EROSION AND SEDIMENT CONTROL PLAN ON ALL DISTURBED AREAS. THIS PERSON IS TO BE KNOWLEDGEABLE ABOUT INSTALLATION AND MAINTENANCE OF THE REQUIRED MEASURES. THIS EMPLOYEE IS TO HAVE THE AUTHORITY TO CARRY OUT THE IMPLEMENTATION OF ANY INSTRUCTIONS CONCERNING THE EROSION AND SEDIMENT CONTROL PLAN GIVEN BY THE ENGINEER. ALL MEASURES WILL BE INSPECTED BY THIS INDIVIDUAL AND THE ENGINEER ON A REGULAR BASIS (AT LEAST ONCE EVERY 7 DAYS) AND AFTER RAINFALL EVENTS GREATER THAN 1/2 INCH.
- II. SEDIMENT TRAPS, SEDIMENT BASINS, DITCHES, SEDIMENT CONTROL, SILT FENCE, STONE OUTLET STRUCTURES, EARTH BERMS, ETC. SHALL BE MAINTAINED DURING THE CONSTRUCTION SEASON AS WELL AS THE WINTER MONTHS AND OTHER TIMES WHEN THE PROJECT IS CLOSED DOWN. TRAPS WILL BE CLEANED WHEN THEY ARE 50% FILLED, SILT FENCE STONE OUTLET STRUCTURES SHALL HAVE SEDIMENT REMOVED WHEN IT REACHES 50% THE HEIGHT OF THE CONTROL DEVICE. THESE SPOILS WILL BE REMOVED TO AN APPROVED SITE.
- 12. SALVAGED TOPSOIL SHALL BE PLACED ON WELL DRAINED LAND AWAY FROM INTERMITTENT AND LIVE STREAMS OR WETLANDS WITH THE APPROPRIATE RUNOFF CONTROL AND SEDIMENT CONTROL MEASURES INSTALLED AROUND THE STORAGE SITE AND STABILIZED IMMEDIATELY AFTER FINAL SHAPING OF THE PILE IN ACCORDANCE WITH MULCH, METHOD 2. THE CONTRACTOR WILL PROVIDE AN ADEQUATE QUANTITY OF SILT FENCE TO CONTROL THE PERIMETER OF THE STOCKPILE.
- 13. MATERIALS EXCAVATED FOR THE CONSTRUCTION OR CLEANOUT OF SEDIMENT TRAPS OR SEDIMENT BASINS SHALL NOT BE STOCKPILED IN THE (VICINITY) OF THE TRAP OR BASIN. IT WILL EITHER BE PLACED IN AN EMBANKMENT OR WASTED AS DIRECTED BY THE FINGINFER.
- 14. EXCAVATION TO BE USED FOR EMBANKMENTS SHALL NOT BE STOCKPILED UNLESS PERIMETER CONTROLS ARE UTILIZED. WHEN THIS MATERIAL IS STOCKPILED FOR THE CONVENIENCE OF THE CONTRACTOR THE COST OF THE CONTROLS ARE BORNE BY THE CONTRACTOR, IF THE MATERIAL IS STOCKPILED AT THE DIRECTION OF THE ENGINEER THE DEPARTMENT WILL ASSUME THE COSTS OF THE CONTROLS.
- 15. SEDIMENT LADEN DEWATERING DISCHARGE MUST BE DIRECTED TO AN APPROVED SEDIMENT TRAPPING MEASURE PRIOR TO RELEASE FROM THE SITE.
- 6. WHEN THE CONTRACTOR REQUESTS A CHANGE TO POSTPONE COMPLETION OF THE EXCAVATION OF A SPECIFIC AREA AS A CONTINUOUS OPERATION AND PLACING THE TOPSOIL AS DEFINED IN THE STANDARD SPECIFICATIONS, THE ENGINEER MAY ALLOW THE CONTRACTOR TO STBILIZE THE AREA USING TEMPORARY STABILIZATION WITH STRAW MULCH PROVIDING THE FOLLOWING CONDITIONS ARE MET:

 (A) ALL AREAS BEING STABILIZED ARE 3:1 SLOPES OR FLATTER.

 (B) THE CONTRACTOR BEARS THE COST OF PREPARING THE SEED BED AND STABILIZING THE AREA WITH TEMPORARY STABILIZATION WITH STRAW MULCH.

 (C) ALL REQUIRED SEDIMENT CONTROL MEASURES FOR THE SECTION OF ROAD IN QUESTION HAVE BEEN INSTALLED ARE BEING MAINTAINED.
- SEEDING USAGE
 TEMPORARY EROSION CONTROL SEEDING USED ON SHORT TERM TEMPORARY SEEDING.
 CLASS 2A SALT TOLERANT ROADSIDE MIX USED FOR NEW CONSTRUCTION OF LIMITED
 ACCESS ROUTES INTENDED TO BE MOWED BY 100T.

CLASS 4 - USED IN PERMANENT 1:2 SLOPES AND 1:3 SLOPES HIGHER THAN 10 FEET.

18. TOP SOIL PLACEMENT
TOPSOIL WILL BE PLACED ON FINAL SLOPES WHICH WILL NOT BE DISTURBED BY
FUTURE CONSTRUCTION. TOPSOIL WILL NOT BE PLACED ON SURFACES WHICH WILL BE
PAVED IN THE FUTURE, NOR ON TEMPORARILY STEEP SLOPES.

- INLET FILTERS ARE REQUIRED FOR THE STRUCTURES SHOWN ON THE PLANS. STRUCTURE OPENINGS VARY SUCH THAT FIELD MEASUREMENT AND/OR CONTRACTOR DESIGN WILL BE REQUIRED. COST OF DESIGN, LABOR AND MATERIALS WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE CONTRACT UNIT PRICE PER EACH FOR "TINIFT FILTER".
- 20. THE CONSTRUCTION LIMITS WILL BE STAKED BY THE ENGINEER PRIOR TO COMMENCING CONSTRUCTION. THE CONSTRUCTION LIMITS MAY BE ADJUSTED BY THE ENGINEER TO PRESERVE TREES AND NO ADDITIONAL COMPENSATION WILL BE PAID TO THE CONTRACTOR FOR CHANGED CONSTRUCTION LIMITS.
- 21. THE RESIDENT ENGINEER SHALL HAVE FINAL DETERMINATION OF THE PLACEMENT AND LOCATION OF THE SEDIMENT CONTROL, SILT FENCE.
- 22. SEE EROSION AND SEDIMENT CONTROL PLANS FOR PLACEMENT OF ALL EROSION AND SEDIMENT CONTROL PAY ITEMS.
- 23. SEE PROPOSED DRAINAGE PLANS FOR FINAL DRAINAGE STRUCTURE, STORM SEWER AND PIPE CULVERT INFORMATION.
- 24. SEE EXISTING DRAINAGE AND UTILITY PLANS FOR INFORMATION CONCERNING THE REMOVAL, ADJUSTMENT, RECONSTRUCTION, ETC. OF EXISTING STRUCTURE AND PIPES.
- 25. THE ACTUAL NEED FOR TEMPORARY DRAINAGE FACILITIES, AS WELL AS THE STAGING OF THE PERMANENT DRAINAGE SYSTEM CONSTRUCTION, MAY BE MODIFIED BY THE RESIDENT ENGINEER, WHO SHALL BE CONSULTED BEFORE THE INSTALLATION, WHERE APPLICABLE, TEMPORARY STRUCTURE AND PIPE TABLES FOR THIS WORK ARE SHOWN ON THE FROSION CONTROL PLANS.
- 26. AS DETERMINED BY THE CONTRACTOR, SOME OF THE PROPOSED DRAINAGE STRUCTURES WILL BE STAGE CONSTRUCTED VERTICALLY TO FACILITATE CONSTRUCTION OPERATIONS. IF THE TOP SLAB OF THE STRUCTURE MUST BE PLACED AT AN INTERIM ELEVATION, THE TOP SLAB WILL THEN BE REMOVED AND THE REMAINING PORTION OF THE STRUCTURE ADDED AND THE TOP SLAB RE-INSTALLED IN A LATER STAGE. FOR DRAINAGE STRUCTURES COMPLETED TO FULL HEIGHT IN THIS CONTRACT, THE COST OF STAGE CONSTRUCTING THEM VERTICALLY WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE CONTRACT UNIT PRICE PER EACH FOR THE DRAINAGE STRUCTURE OF THE TYPE SPECIFIED IN THE PLANS.
- 27. EROSION CONTROL MEASURES SHALL BE REMOVED ONLY WHERE INDICATED ON THE PLANS. COST OF REMOVAL SHALL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE TYPE OF MEASURE INDICATED ON THE PLANS.
- 28. TEES REQUIRED TO MAKE TEMPORARY CONNECTIONS TO EXISTING SEWER SHALL BE INSTALLED ACCORDING TO IDOT DISTRICT 1 STANDARD BD-07 AND PAID FOR AT CONTRACT UNIT PRICE PER EACH FOR "REINFORCED CONCRETE PIPE TEE" OF THE SIZES REQUIRED TO MAKE THE CONNECTIONS. CONTRACTOR MAY AT HIS OPTION USE PRE-FABRICATED WYES INSTEAD OF TEES, AT HIS COST. ELBOWS AND OTHER FITTINGS REQUIRED TO MAKE TEMPORARY CONNECTIONS SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER METER FOR THE TYPE AND CLASS OF PROPOSED LATERAL PIPE SPECIFIED.

REVISIONS
NAME DATE


PARSONS
BRINCKERHOFF


SMITH ENGINEERING
CONSULTANTS, INC.
www.smithengineering.com


ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH


EROSION AND SEDIMENT CONTROL - GENERAL NOTES


SCALE: 1" = 50' DATE: 06/30/2006 DRAWN BY: JPA CHECKED BY: TEH


































CONTRACT NO. 60B86 F.A.I. SECTION 55 2006-032 BY COUNTY 505 175 WILL STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT -EXISTING GROUND -TOP OF BERM EL. 612.0 TOP OF BERM EL. 612.0 --EL. 607.0 INV. 607.6-WATER QUALITY VOLUME PROVIDED = 0.304 AC-F1 -12" RCP @ 0.5% STONE RIPRAP CL A3-ELEVATION SECTION A-A DETAIL OF EMERGENCY SPILLWAY NOT TO SCALE H.W.L. 610.5 -EMERGENCY SPILLWAY EL. 610.5 -WET BOTTOM PONE (WATER QUALITY) -STA. 584+52 OFFSET: 90.0' RT N.W.L. 607.6 (2899) (2899) (2900) H.W.L. = 610.5 N.W.L. = 607.6 -EXISTING GROUND SECTION B-B -STA. 584+52 OFFSET: 263' RT DETENTION BASIN - I INFORMATION STONE RIPRAP CL A3, 28 SY STONE RIPRAP CL A3 TEMPORARY FENCE DETENTION VOLUME REQUIRED = 1.444 AC-FT DETENTION VOLUME PROVIDED = 1.584 AC-FT -EXISTING 24" CULVERT HIGH WATER ELEVATION = 610.5 RELEASE RATE = 2.57 CFS WATER QUALITY VOLUME REQUIRED = 0.179 AC-FT WATER QUALITY VOLUME PROVIDED = 0.304 AC-FT -STA. 581+84 OFFSET: 378' RT NOTES 1. FOR STRUCTURE AND PIPE INFORMATION SEE DRAINAGE SCHEDULES. **DETENTION BASIN** BASIN CONTOUR OFFSET AT ELEVATION BASIN CONTOUR OFFSET AT ELEVATION 612.0 607.0 606.0 606.0 607.0 612.0 612.0 607.0 606.0 606.0 607.0 612.0 581+90 120.4 140.4 580+32 144.8 218.2 247.3 -- 167.8 -- 179.1 580+40 131.0 582+00 120.6 140.6 210.4 206.3 205.2 580+50 126.6 179.1 582+10 121.0 141.0 227.8 160.1 189.1 170.8 199.0 580+60 124.8 144.9 580+70 123.8 143.9 225.2 582+20 121.5 141.6 582+30 122.5 142.6 206.4 IABBI.DGN, .. GARCIAAZ 209.1 212.7 216.9 180.8 208.8 582+40 123.8 144.0 580+90 581+00 122.7 142.8 122.3 142.3 190.6 218.2 200.2 227.0 582+50 125.6 146.0 582+60 128.0 148.9 234.4 238.8 581+10 581+20 581+30 121.9 142.0 191.1 191.1 20.9.2 582+70 131.2 152.8 221.4 243.2 225.6 246.9 ..\LP1@1A@01.0GN, ..\Al. 6-28-2@@6, 15:@3:47 121.6 141.6 121.2 121.2 183.9 207.6 217.6 242.6 181.1 217.3 225.1 249.2 582+80 135.4 158.4 582+90 141.0 165.6 229.1 249.6 229.1 249.6 230.5 250.5 224.2 248.7 -- 242.7 -- 229.7 -- 204.9 ILLINOIS DEPARTMENT OF TRANSPORTATION 120.9 140.9 180.0 225.1 231.9 254.7 120.7 140.7 180.9 230.8 237.2 258.4 120.4 140.5 186.1 233.2 239.8 259.8 583+00 148.0 175.1 FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH 583+10 156.6 188.6 583+20 167.7 --583+30 183.7 --581+50 581+60 120.3 140.3 196.9 229.3 237.1 258.5 120.3 140.3 218.5 218.5 229.1 254.5 DRAINAGE DETAILS 583+35 204.9 DETENTION BASIN SCALE: DRAWN BY MRK DATE 07/05/06 CHECKED BY TKL


DATE NAME SCALE NAME PLOT FILE PLOT USER


TENC


TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS

































				CONTRAC	CT NO.	60B86
F.A.P. RTE.	SECTION		C	OUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032	ВΥ		WILL	505	188
STA.		,	ΤO	STA.		
FED. RO	AD DIST. NO.	HLLIN	OIS	FED. AID	PROJECT	
				DRUI)T 1 0F	3



<u>DETENTION BASIN</u> RESTRICTOR STRUCTURE #123

PARSONS BRINCKERHOFF

DATE ILLINOIS DEPARTMENT OF TRANSPORTATION US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE DETAILS DETENTION BASIN RESTRICTOR

SMITH ENGINEERING CONSULTANTS, INC. www.smithengineering.com

DATE: 07/21/2006

F.A.P. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032	BY	WILL	505	189
STA.		T	STA.		
FED. RO	AD DIST. NO.	ILLINO	IS FED. AID	PROJECT	
			DRUD	[2 OF	= 3

NOTES

- 1. IN STAGE 1, THE FRAMES AND GRATES SHALL BE SET FLUSH WITH THE LEVEL OF THE BINDER COURSE AND BE SECURED BY TACK WELDING, WEDGING WASHERS OR A COMBINATION THEREOF TO THE SATISFACTION OF THE ENGINEER, IMMEDIATELY PRIOR TO PLACING THE SURFACE COURSE OR AS DIRECTED BY THE ENGINEER, THE FRAMES AND GRATES SHALL BE UNSECURED AND ADJUSTED TO THE FINAL SURFACE ELEVATION IN ACCORDANCE WITH SECTION 603 " ADJUSTING FRAMES AND GRATES OF DRAINAGE AND UTILITY STRUCTURES." THE COST OF SECURING AND UNSECURING THE FRAMES AND GRATES SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE EACH FOR FRAMES AND GRATES TO BE ADJUSTED.
- 2. THE COST OF ADDITIONAL WIDTH OF CONCRETE GUTTER AS SHOWN AT THE DRAINAGE STRUCTURES SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER FOOT FOR CONCRETE

CONCRETE GUTTER DETAIL AT DRAINAGE STRUCTURE

-DRAINAGE STRUCTURE (AS SHOWN ON PLANS)

¢ DRAINAGE STRUCTURE

- CONCRETE GUTTER (SEE NOTE 1)

FRAME & GRATE (AS SHOWN ON PLANS,

1" THICK PREFORMED

EXPANSION JOINT FILLER

SEE NOTE 2

5'-0" (TYP)

SEE NOTE 1)

DOUBLE FACE, 42" HEIGHT

(TYP.)


CONCRETE BARRIER,

-EDGE OF CONCRETE GUTTER

-PR EDGE OF PAVEMENT

PR EDGE OF PAVEMENT

SIDE ELEVATION



1. THE COST OF SOLID CONCRETE BLOCK OR CONCRETE ADJUSTING RINGS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE OF DRAINAGE STRUCTURES OF TYPE OR SIZE

- 2. SEE STATE AND DISTRICT 1 STANDARDS FOR DRAINAGE STRUCTURE DETAILS.
- 3. FOR STRUCTURE AND PIPE INFORMATION SEE DRAINAGE SCHEDULES.

ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 55 PARSONS BRINCKERHOFF US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE DETAILS STRUCTURE ADJUSTMENT SMITH ENGINEERING


> CHECKED BY TL FINAL

DRAWN BY MRK


CONSULTANTS, INC. SCALE: N.T.S. DATE: 07/21/2006

CONCRETE ADJUSTING RINGS OR CONCRETE BLOCKS FOR TYPE 20 AND TYPE 21 F & G

F.A.P. RTE.	SECTION		COUN	TY	SHEE	AL TS	SHEET NO.
55	2006-032	BY	W	ILL	509	5	190
STA.		T	O STA				
FED. RO	AD DIST. NO.	ILLING	IS FE	. AID	PROJE	ECT	
				RUD	T 3	0	F 3



PROPOSED PLAN



SECTION A-A

PROPOSED STORM SEWER (AS SHOWN ON PLANS)

PROPOSED LATERAL CONNECTION (AS SHOWN ON PLANS)

FRAME & GRATE ---AS SHOWN ON PLANS


SEE DETAIL B

PIPE UNDERDRAINS 6" (SPECIAL) (TYP)


PROPOSED DRAINAGE STRUCTURE— (AS SHOWN ON PLANS) (TYP)

PR BIT PAVEMENT

AGGREGATE --SUBGRADE



DETAIL A



DETAIL B

NOTES 1. SEE STANDARD 601001 FOR DETAILS NOT SHOWN.

THE COST OF GEOTECHNICAL FABRIC FOR FRENCH DRAINS, FABRIC ENVELOPE FOR
PIPE UNDERDRAINS, CA-16 AGGREGATE FOR BEDDING AND TRENCH BACKFILL AND
OUTLET CONNECTION TO DRAINAGE STRUCTURES WILL NOT BE PAID SEPERATELY, BUT
SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR PIPE UNDERDRAINS 6".

GENERAL NOTES

THE 24" RADIUS ON THE DRAINAGE FITTING IS ONLY A MINIMUM. LARGER RADII MEETING THE APPROVAL OF THE ENGINEER MAYBE SUBSTITUED.

	REVISIONS		ILLINOI
	NAME	DATE	12211101
PARSONS			US 30 (PL
BRINCKERHOFF			
1828			
SMITH ENGINEERING			
CONSULTANTS, INC.			SCALE: N.T.S
www.smithengineering.com			DATE: 07/21/

OIS DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55 PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE DETAILS PIPE UNDERDRAIN

DATE: 07/21/2006

DRAWN BY MRK CHECKED BY TL

FINAL

..\DU!Ø!A!Ø!.DGN, ..\DUØ' 6-28-2ØØ6, 15iØ3i13

STRUCTURE

NO.

STRUCTURE DESCRIPTION

MAN TA 5 DIA TIF C

CB TA 5 DIA T2IF&G
MAN TA 7 DIA T24F&G
CB TA 4 DIA T20F&G

MAN TA 6 DIA TIF CL PRCF END S EL EORS 30 PRC FLAR END SEC 12 PRC FLAR END SEC 12

CB TA 4 DIA T21F&G
MAN TA 6 DIA T20F&G

CB TA 4 DIA T20F&G CB TA 4 DIA T20F&G

CB TA 4 DIA T20F&G
CB TA 4 DIA T20F&G
CB TA 4 DIA T20F&G
GRT-C FL END S EQV 30

CONCRETE BARRIER,-

DOUBLE FACE, 42" HEIGHT

LEGEND

DATE NAME SCALE NAME

ES - EXISTING STRUCTURE EP - EXISTING PIPE DRAINAGE STRUCTURE NOTATION AT CONCRETE BARRIER

1-55 CENTERLINE

220.6 245.6 50.5 49.9

146.0 RT

1.5 RT -1.5 RT -1.5 RT -1.5 RT -1.5 RT --

C DRAINAGE STRUCTURE

-STATION, OFFSET AND RIM

ELEVATION SET AT THE EDGE

OF THE CONCRETE BARRIER

STATION

574+40 574+60

581+50 584+00 586+45 577+60 580+48

581+91 582+19

588+76 589+07

574+20

574+40

574+60 577+50 579+50 581+50 584+00

586+45 580+48 INVERTS

620.54 624.48

OFFSET DIR. NORTH SOUTH EAST WEST

 OFFSET
 DIR
 NORTH
 SOUTH
 EAST
 WEST

 - RT
 609.62
 - - -

 1.5
 LT
 609.49
 609.50
 - -

 1.5
 LT
 609.12
 609.12
 609.66
 -

 1.5
 LT
 609.09
 609.09
 609.64
 -

 1.5
 LT
 609.06
 609.06
 609.61
 -

 1.5
 LT
 609.05
 608.55
 608.55
 -

 1.5
 LT
 612.75
 612.72
 612.75
 -

 1.5
 LT
 616.30
 616.18
 616.30
 -

 1.5
 LT
 620.50
 620.24
 620.50
 -

 1.5
 LT
 - 624.36
 624.44
 -

 72.0
 RT
 - - 608.34
 608.34

 146.0
 RT
 - - 607.60
 -

-- INVERT, STATION AND OFFSET HEADWALL OR END SECTION

DATE

FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE SCHEDULE PROPOSED STRUCTURES

SCALE:

DRAWN BY SN CHECKED BY TKL

-SIZE NOTATION

STORM SEWER OR PIPE CULVERT NOTATION

-CLASS SS 2 RCP CL 3 24

DATE 07/05/06 TENC

PIPE CONNECTIONS (Pipe No. - Pipe Size)
TH EAST

SOUTH

| 2707 - SPAN 30", RISE 19" | 2707 - SPAN 30", RISE 15" | 2708 - SPAN 30", RISE 19" | 4709 - DIA 15" | 2709 - SPAN 38", RISE 24" | 2708 - SPAN 38", RISE 24" | 4710 - SPAN 38", RISE 24" | 2711 - DIA 15" | 2710 - DIA 15" | 2710 - DIA 15" | 4711 - DIA 15" | 2712 - DIA 15" | 4712 - DIA 15" | 2713 - DIA 15" | 4713 - DIA 15" | 2713 - DIA 15" | 4714 - DIA 15" | 2713 - DIA 15" | 4714 - DIA 15" | 4714 - DIA 15" | 2713 -

07 - SPAN 30", RISE 19" 2706 - SPAN 30", RISE 19" 08 - SPAN 30", RISE 19" 2707 - SPAN 30", RISE 19"

NORTH

KIND OF SEWER PIPE ---

TYPE-

TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS

CONTRACT NO. 60B86 COUNTY TOTAL SHEET NO.

WILL 505 191

TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

F.A.I. SECTION BTE. SECTION 55 2006-032 BY

PROPOSED SHEET SC INLET UNDERDRAIN STRUCTURE RIM ELEVATION NO. FILTER CONNECTION TOP SLAB

YES YES YES

YES YES

YES

RIM ELEVATION NO.

626.66 628.86

614.99

629.79

629.88 613.04

613.04 613.05

628.95

WEST

4708 - DIA 15' 4709 - DIA 15'

4714 - DIA 13 2717 - SPAN 38", RISE 24" 2716 - SPAN 38", RISE 24" 2717 - SPAN 38", RISE 24"

2716 - SPAN 38", RISE 24" 4710 - SPAN 38", RISE

2899 - DIA 12"

EP - DIA 12

F.A.I. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
55	2006-032 BY	WILL	505	192
STA.		TO STA.		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

2706 SS RCP CL 4 24 G1A 24" 12 0.99 0.7 2708 2705 2706 2707 2708 285 RCP SO R19 594 M 207 315 50.30 3.7 2706 2707 2707 285 RCP SO R19 594 M 207 315 0.10 1.1 270 2700 2707 2707 285 RCP SO R19 2708 2709 27	PIPE NO.	PIPE DESCRIPTION	PIPE SIZE	LENGTH (FT)	SLOPE (%)	TRENCH BACKFILL (CUYD)	SHEET NO.	FROM STRUCTURE	TO STRUCTURE
2706 SS 1 RCEP S30 R19 SPAN 30", RISE 19" 125 0.30 9.7 2706 2707 2707 SS 2 RCEP S30 R19 SPAN 30", RISE 19" 15 0.18 1.1 2707 2708 2708 SS 2 RCEP S30 R19 SPAN 30", RISE 19" 15 0.18 1.2 2708 2709 2709 SS 2 RCEP S38 R24 SPAN 30", RISE 24" 284 0.18 7.2.7 2709 2710 2710 2710 2712 2710 2710 2712 2713 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2711 2711 2711 2711 2711 2711 2711 2711 2711	2705		DIA 24"	12	0.99	0.7		2705	2706
2707 SS 2 RCEP S30 R19 SPAN 30", RISE 19" 15 0,18 1.1 2707 2708 2708 SS 2 RCEP S30 R19 SPAN 30", RISE 19" 15 0,18 1.2 2708 2709 2709 2709 2710 2710 2710 2710 2711 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 2711 2710 2711 <t< td=""><td></td><td></td><td>SPAN 30", RISE 19"</td><td>125</td><td></td><td>9.7</td><td></td><td>2706</td><td>2707</td></t<>			SPAN 30", RISE 19"	125		9.7		2706	2707
2708 SS 2 RCEP S30 R19 SPAN 30", RISE 19" 15 0.18 1.2 2708 2709 2709 2709 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 284 0.18 72.7 2709 2710 2710 SS 2 RCP CL 3 15 DIA 15" 195 1.76 69.1 2711 2710 2711 SS 2 RCP CL 3 15 DIA 15" 196 1.75 76.4 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2713 2712 2711 2712 2714 2713 2712 2714 2713 2712 2714 2713 2712 2714 2714 2712		SS 2 RCFP S30 R19	SPAN 30", RISE 19"						
2709 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 284 0.18 72.7 2709 2710 2710 SS 2 RCP CL 3 15 DIA 15" 195 1.76 69.1 2711 2710 2711 SS 2 RCP CL 3 15 DIA 15" 196 1.75 76.4 2712 2713 2713 2713							**		
2710 SS 2 RCP CL 3 15 DIA 15" 195 1.76 69.1 2711 2710 2711 SS 2 RCP CL 3 15 DIA 15" 196 1.75 76.4 2712 2711 2711 2712 2711 2711 2711 2711 2712 2711 2711 2712 2711 2712 2711 2712 2711 2712 2713 2712 2713 2712 2714 2713 2714 2713 2714 2713 2714 2713 2714 2713 2714 2713 2714 2713 2714 2713 2716 282 RCEP S38 R24 SPAN 38", RISE 24" 62 0.30 26.8 4710 2716 2800 2899 P CUL 1 RCCP 12 DIA 12" 37 0.27 - 2899 2900 2899 P CUL 1 RCCP 12 DIA 15" 3 0.80 0.1 4707 2707 4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708		SS 2 RCEP S38 R24	SPAN 38", RISE 24"				·		
2711 SS 2 RCP CL 3 15 DIA 15" 196 1.75 76.4 2712 2711 2712 SS 2 RCP CL 3 15 DIA 15" 246 1.60 96.5 2713 2712 2713 SS 2 RCP CL 3 15 DIA 15" 241 1.60 96.5 2714 2713 2716 SS 2 RCP S38 R24 SPAN 38", RISE 24" 62 0.30 26.8 4710 2716 2717 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 62 0.30 26.8 4710 2716 2899 P CUL 1 RCCP 12 DIA 12" 37 0.25 - 2716 2800 4707 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4707 2707 4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4710 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 3 0.61 1			DIA 15"						
2712 SS 2 RCP CL 3 15 DIA 15" 246 1.60 96.5 2713 2712 2713 SS 2 RCP CL 3 15 DIA 15" 241 1.60 61.5 2714 2713 2716 SS 2 RCPP S38 R24 SPAN 38", RISE 24" 62 0.30 26.8 4710 2716 2717 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 94 0.25 - 2716 2800 2899 P CUL 1 RCCP 12 DIA 12" 37 0.27 - 2899 2900 4707 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4707 2707 4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4709 2709 4710 SS 2 RCP S38 R24 SPAN 38", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>									
2713 SS 2 RCP CL 3 15 DIA 15" 241 1.60 61.5 2714 2713 2716 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 62 0.30 26.8 4710 2716 2717 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 62 0.30 26.8 4710 2716 2899 P CUL 1 RCCP 12 DIA 12" 37 0.27 - 2899 2900 4707 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4707 2707 4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2709 4710 SS 2 RCP S38 R24 SPAN 38", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4712 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>									
2716 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 62 0.30 26.8 4710 2716 2717 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 294 0.25 - 2716 2800 2899 P CUL 1 RCCP 12 DIA 12" 37 0.27 - 2899 290C 4707 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4707 2707 4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4709 2709 4710 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4712 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6									
2717 SS 2 RCEP S38 R24 SPAN 38", RISE 24" 294 0.25 - 2716 2800 2899 P CUL 1 RCCP 12 DIA 12" 37 0.27 - 2899 2900 4707 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4707 2707 4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4709 2709 4710 SS 2 RCEP S38 R24 SPAN 36", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713		SS 2 RCEP S38 R24							
2899 P CUL 1 RCCP 12 DIA 12" 37 0.27 - 2899 290C 4707 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4707 2707 4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4709 2709 4710 SS 2 RCEP S38 R24 SPAN 36", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713		SS 2 RCEP S38 R24	SPAN 38", RISE 24"						
4707 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4707 2707 4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4709 2709 4710 SS 2 RCEP 538 R24 SPAN 38", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4712 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713		P CUL 1 RCCP 12	DIA 12"			-			
4708 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4708 2708 4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4709 2709 4710 SS 2 RCP S38 R24 SPAN 38", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4712 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713									
4709 SS 1 RCP CL 4 15 DIA 15" 3 0.80 0.1 4709 2709 4710 SS 2 RCEP S38 R24 SPAN 36", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4712 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713									
4710 SS 2 RCEP 538 R24 SPAN 38", RISE 24" 3 0.61 1.8 2710 4710 4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4712 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713									
4711 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4711 2711 4712 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713			SPAN 38", RISE 24"						
4712 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.6 4712 2712 4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713									
4713 SS 2 RCP CL 3 15 DIA 15" 3 1.00 1.4 4713 2713									
4714 S\$ 2 RCP CL 3 15 OIA 15" 3 1.00 O.6 4714 2714		SS 2 RCP CL 3 15							
		SS 2 RCP CL 3 15							
	4124	33 2 NCI CE 3 13	DIA IS		1.00	0.0		7127	2117
					 			 	
								1	
						 		 	
									
						 		 	
						 		 	
			 					 	1
								 	
						 		 	
								 	
						ļ			
						 			
								 	
						ļ		 	
								 	
						<u> </u>		 	
								-	
						_			
									ļ
									ļ
						ļ			
						 			
				·····		 			
						 			-
									ļ

					ļ	 		-	
					 	 		 	
						 		-	
						 		 	
		· · · · · · · · · · · · · · · · · · ·				 		-	
						 			
									
					ļ	 		+	
	<u> </u>				<u> </u>	 		-	
						 		-	
						<u> </u>			ļ
						+		ļ	
						 		-	
						ļ			
						ļ		ļ	ļ
						 		<u> </u>	ļ
					ļ	 			
									-
			ļ						ļ
						ļ			ļ
								L	
						ļ		 	ļ
									ļ
								1	
						<u> </u>		L	ļ
						ļ		L	<u> </u>
				<u> </u>		<u> </u>		1	<u> </u>

PIPE NO.	PIPE DESCRIPTION	PIPE SIZE	LENGTH (FT)	SLOPE (%)	TRENCH BACKFILL (CUYD)	SHEET NO.	FROM STRUCTURE	TO STRUCTURE
			-					

				<u> </u>				

REVISIONS NAME DATE	US 30 (PLAINFIELD DRAINA	MENT OF TRANSPORTATION AL ROUTE 55 ROAD) TO LILY CACHE SLOUGH GE SCHEDULE OSED PIPES
	SCALE:	DRAWN BY SN
	DATE 07/05/06	CHECKED BY TKL
	TENO	TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS

PLOT DATE = \$DATE\$
FILE NAME = \$FILEL\$
PLOT SCALE = \$SCALE\$
USER NAME = \$USER\$

F.A.P RTE.	SECTION		С	опитл	TOTAL	SHEET NO.
55	2006-032	BY		WILL	505	193
STA.			то	STA.		
FED. R	DAD DIST. NO.	IŁLIN	OIS	FED. AID	PROJECT	
	· · · · · · · · · · · · · · · · · · ·	***************************************		PSCH	01 OF	02

PIPE SCHEDULE

					***************************************	****							STORM SE	WER (FEET)								
8	NUMBER	w	س≨										CLAS	5S A							VII E.V. 1.		<u>س</u> ا
NUMBER	N N	1 K A	<u> </u>	호텔						TYPE 1									TYPE 2	···			SLOPE
PIPE N	SHEET N	UPSTREAM	DOWNSTREAM STRUCTURE	TRENCH BACKFILL (CU YD)	12 in	15 în	18 in	21 in	24 în	30 in	14×23 ELL	19×30 ELL	22×34 ELL	24×38 ELL	34×53 ELL	12 în	15 în	18 in	21 în	24 in	27 in	36 in	3d1d
1	DRU-1	2	1	0												3							0.33%
2	DRU-1	1	3	40												297							0.44%
3	DRU-2	4	3	1												3 297					-		0.33% 0.66%
5	DRU-2 DRU-2	6	5 5	67									-			3					 		0.33%
6	DRU-2	5	7	88		 										1		207					0.32%
7	DRU-2	8	7	1						<u> </u>						3							1.00%
8	DRU-2	9	7	20																65			0.22%
9	DRU-2	10	9	1												3							1.00%
10	DRU-2	11	9	247														ļ	322	-			0.50% 0.67%
11	DRU-2	12	11	0	3						ļ							297	-	 		-	0.50%
12 13	DRU-2 DRU-2	13	11 13	224 0	3											 		231			-		0.67%
14	DRU-2	15	13	68											†	247		1					0.75%
15	DRU-3	16	15	0	3																		0.67%
16	DRU-3	18	17	0												3							1.00%
17	DRU-3	17	19	71											ļ	297							0.44%
18	DRU-3	20	19	0												3 297							1.00% 0.75%
19	DRU-3	19	21	103										<u> </u>	ļ	3			<u> </u>				1.00%
20	DRU-3 DRU-3	22 21	21 23	0 224											ļ			297					0.50%
22	DRU-3	24	23	0					<u> </u>				 			3							1.00%
23	DRU-3	23	25	265					<u> </u>				1						297				0.50%
24	DRU-2	7	121	22																110			3.75%
25	DRU-4	26	25	1												3							1.00%
26	DRU-4	25	27	119								 				3				297			0.50%
27	DRU-4	28	27	0					 	ļ						3	ļ	-		 	272		0.20%
28	DRU-4 DRU-4	27 30	29 29	185 1					ļ		<u></u>					3				 	-16		1.00%
30	DRU-4	29	30a	17																	54		0.20%
31	DRU-4	31	31a	15	*************								İ							65			0.27%
32	DRU-4	32	31	1												3							0.33%
33	DRU-4	33	31	18					97		<u> </u>						<u> </u>	<u> </u>					0.33%
34	DRU-4	34	33	0	3			247	-	ļ	-			-			1						0.33%
35 36	DRU-4 DRU-4	35 36	33 35	31	3			247	 				-			 		 		-	 	 	0.33%
37	DRU-4	37	35	37	J	 									1	 		247	 				0.31%
38	DRU-4	38	37	0									 			3							0.33%
39	DRU-5	39	37	43													297						0.51%
40	DRU-5	40	39	0	3														ļ				0.33%
41	DRU-5	42	41								-		<u> </u>			1				11	 	 	0.33%
85	DRU-6	87	EXIST	74					ļ	ļ	ļ	-				3	1	45	 	1	 		1.00%
86 87	DRU-6 DRU-6	88 89	87 87	103							 			-		1 3	297	 	 	-	1		0.70%
88	DRU-6	90	89	0		-	 		 	 	 	 	 	 		3		 			 	 	0.33%
89	DRU-6	91	89	71							†	 		1		297	 			1			0.67%
90	DRU-6	92	91	1												3							0.33%
91	DRU-7	94	93	0												3							0.33%
92	DRU-7	93	95	68					-		<u> </u>		-	ļ		297	 	-					0.68%
93	DRU-7	96	95	0	L	L	L	L		L	L		<u> </u>			1 3	<u> </u>	l	ــــــــــــــــــــــــــــــــــــــ	L	L	1	0.33%

	REVISIO	NS
	NAME	DATE
PARSONS		
BRINCKERHOFF		
- 22		
SMITH ENGINEERING		
CONSULTANTS, INC.		
www.smithengineering.com		

ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 55 US 30 (PLAINFIELD ROAD) TO LÎLY CACHE SLOUGH

DRAINAGE SCHEDULE -PIPES

SCALE: 1" = 50' DATE: 07/21/2006

F.A.P. RTE.	SECTION		С	OUNT.	Y	TOTA	AL TS	SHEET NO.
55	2006-032	BY		WIL	L	505	5	194
STA.		7	ГО	STA.		•		
FED. RO	AD DIST. NO.	ILLIN	210	FED.	AID	PROJE	ECT	
				Р	SCH	02 ()F	02

PIPE SCHEDULE

													STORM SE	WER (FEET)								
8	NUMBER	- W	.≱ ա										CLA	SS A									뀙
NUMBER	UME	E A	35.25	TRENCH BACKFILL (CU YD)						TYPE 1						<u> </u>			TYPE 2				SLOPE
Z		STR	NST CC	₩ X X		Τ	Ι	Τ	1	1		Γ.	I		T			[T	I		
PIPE	SHEET	UPSTREAM	DOWNSTREAM STRUCTURE	+89 ⊃	12 in	15 in	18 in	21 in	24 in	30 în	14×23 ELL	19×30 ELL	22×34 ELL	24×38 ELL	34×53 ELL	12 in	15 in	18 in	21 in	24 în	27 in	36 in	3d1d
94	DRU-7	95	97	107		 											297						0.64%
95	DRU-7	98	97	0											ļ	3							0.33%
96	DRU-7	97	99	73														232					0.63%
96a	DRU-7	100	99	0							<u> </u>					3				ļ	-		0.33%
97	DRU-7	99	EXIST	27														20			-		0.36% 0.32%
113	DRU-12	123	124	0	63										-					21		1	3.79%
203	DRU-8	204	205	0		ļ			-	-	ļ	l			-	<u> </u>	33		 	21			0.49%
204	DRU-8	205	206	9 4				ļ	-						-		22					 	0.46%
206	DRU-8 DRU-8	205 206	207	84				<u> </u>	-	-							297		-				0.48%
207	DRU-8	207	209	109		 		-	1	 	 						297						0.49%
208	DRU-8	208	210	78				-	 	 	 							297					0.49%
209	DRU-8	209	211	97														297					0.39%
210	DRU-9	210	212	58				<u> </u>		· · · · · · · · · · · · · · · · · · ·								297					0.46%
211	DRU-9	211	213	84														297					0.51%
212	DRU-9	212	214	38															247				0.25%
213	DRU-9	213	215	49			***************************************												247				0.34%
214	DRU-9	214	216	24															197				0.20%
215	DRU-9	215	217	36															197				0.20%
216	DRU-9	216	218	10																102			0.22%
217	DRU-9	217	219	22																102			0.30%
218a	DRU-9	218	218a	6						65													0.20%
218	DRU-9	220	218	6							ļ							42					0.26%
219	DRU-9	221	219	9							-							42	ļ				0.26%
220	DRU-9	222	220	12		147				ļ	ļ	<u> </u>	L										0.32%
221	DRU-9	223	221	21	407	147	<u> </u>	ļ			-										ļ		0.32%
222	DRU-9	224	222	26 37	197 197		 			-	· 				 				l				0.44%
223	DRU-9 DRU-10	225	223	50	191	ļ				-	-	l			 		 	338					0.65%
224 224a	DRU-10 DRU-10	227 226a	226	0			-				 	-			<u> </u>	3		330	 		 		1.00%
225	DRU-10 DRU-10	2280	227	1	 			-	-							3	 			†			1.00%
226	DRU-10	226	BRIDGE	8	 		 	 	 	+	+	 	 			<u> </u>			20		<u> </u>		0.50%
227	DRU-10	230	229	0	 		-	-											T		†	160	0.22%
228	DRU-10	231	227	59	l	 	† · · · ·	1		†	——	<u> </u>	†		t	236		l					0.69%
229	DRU-10	232	231	0					 	<u> </u>	·	<u> </u>	 	-		3	1					İ	1.00%
230	DRU-10	233	FES	6					65								<u> </u>	1					0.17%
231	DRU-10	234	233	1	3	T				-	1												1.00%
232	DRU-10	235	233	51			197																0.38%
233	DRU-10	236	235	0	3																		1.00%
234	DRU-10	237	235	36												197					<u> </u>		1.15%
235	DRU-10	238	237	0												3							1.00%
236	DRU-9	219	218	1	3															ļ	<u> </u>	<u> </u>	0.33%
		TOTAL		3474	484	294	197	247	162	65	0	0	0	0	0	2537	1540	2955	1527	773	326	160	L

PARSONS
NAME DATE

PARSONS
BRINCKERHOFF

SMITH ENGINEERING
CONSULTANTS, INC.
www.smithengineering.com

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE SCHEDULE -

DRAINAGE SCHEDULE -PIPES

SCALE: 1" = 50' DATE: 07/21/2006

DRAINAGE STRUCTURE REMOVAL SCHEDULE

			CONCRETE		R	EMOVA	L (R)			ADJUS	T (ADJ)	FRAMES AND	DRAIN.	PIPES TO BE
SHEET	STATION	OFFSET (FT)	HEADWALL REMOVAL (EACH)	MANHOLE (EACH)	PRC FES (EACH)	,	STORM	SEWE	?	MEDIAN INLET BOX	MH (EACH)	RECON MH (EACH)	GRATES TO BE ADJUSTED (EACH)	STRUCTURES TO BE CLEANED (C) (EACH)	CLEANED (CLN) (FOOT)
			(EACH)			15"	18"	24"	30"						SIZE / LENGTH
DRU-02	598+60	3' L	1												
DRU-02	598+60	CL					110								
DRU-02	598+60	118' L	1												
DRU-04	629+30	CL		1											
DRU-04	629+30	CL					53								
DRU-04	631+50	53' L													30" / 115'
DRU-04	631+50	CL				1	100	ļ							
DRU-04	631+74	CL	1			l									
DRU-05	642+67	CL				1									30" / 146'
DRU-05	642+67	CL													30" / 50'
DRU-05	643+25	CL			1										
DRU-05	643+25	CL	1			20									
DRU-06	701+52	CL													30" / 151'
DRU-06	701+52	95′ R													30" / 37'
DRU-06	701+52	95' L													30" / 38"
DRU-06	701+54	CL				20									
DRU-06	701+75	CL		1											
DRU-07	721+55	CL													36" / 140'
DRU-07	721+55	95′ R													36" / 50'
DRU-07	721+55	95' L													36" / 43'
DRU-07	721+55	72′ L	1												
DRU-09	766+50	CL	1			63									
DRU-10	773+00	CL							82						
DRU-10	773+50	CL								1					
DRU-10	779+50	68' L	1												
DRU-10	780+00	65′ L						163							
DRU-10	781+00	62' L	1												
DRU-10	782+00	CL					60	1							
DRU-10	782+00	80' L	1					1							
DRU-10	782+50	64' R				1									24" / 130"
DRU-10	783+00	84' L	1					1							24" / 100'
DRU-10	783+95	77′ L				T								1	
		TOTALS	8	2	1	103	323	163	82	1				1	1000

PARSONS BRINCKERHOFF SMITH ENGINEERING CONSULTANTS, INC. www.smithengineering.com

ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 55 US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE SCHEDULE -REMOVALS

SCALE: 1" = 50' DATE: 07/21/2006

F.A.P. RTE.	SECTION		С	типо	Y	TOTAL SHEETS	SHEET NO.
55	2006-032	BY		WIL	L	505	196
STA.			TO	STA.			
FED. RO	AD DIST. NO.	ILLIN	OIS	FED.	AID	PROJECT	
				S	SCH	01 OF	02

DRAINAGE STRUCTURE SCHEDULE

						,								JNAINAGE			<u>,</u>													
					1 25	M	ANHOL	.ES						.		CATO	H BASIN	IS	- 1	씸	丑									
E.R.	œ	L	OCATION		542531		TYPE							RE T)			PE A		TY C	TE PI	CONCRETE PIPE " PIPE WITH " RISER									
NUMBER	NUMBER			T	STANDARD						PRECAS F.E.S.	Т		EUCTU TY 2(С	NCRE IPE W	NCRE IPE V ISER									
STRUCTURE	SHEET N	STATION	ET (FT)	SIDE	BOX STAP		CL CL	-						DRAINAGE STRUCTURE TY 8x3, W/TWO TY 20 F&G			E 20 & GRATE	Ξ	TY 8 F	REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 18" RISER	REINFORCED CO TEE, 36" P 18" R1	RIM				INVERT EL	EVATIONS.			
ls		rs.	OFFSET	"	INLET	4 FT	5 FT	6 FT	12"	24"	27"	30"	36"	DRAI 8x3,	4 FT	5 FT	6 FT	8 FT	 	REINF.	RE INF	EFEA	NORTH	SOUTH	EAST	WEST	SOUTH EAST	NORTH EAST	SOUTH WEST	NORTH WEST
1	DRU 1	590+50	1.5	LT	 	†	 	1		 	 	İ			1				t			629.59	625.34		625.34					
2	DRU 1	590+50	1.5	RT								ļ —			1							629.74				625.35				
3	DRU 2	593+50	1.5	LT											1							628.02	622.32	624.02	622.32					
4	DRU 2	593+50	1.5	RT	<u> </u>										1				\perp			628.04			017.10	622.33				
5	DRU 2	596+50	3	LT	 	ļ	ļ	ļ		ļ	ļ				1				11			624.73 624.29	616.68	620.35	617.18	617.19				
6	DRU 2	596+50	7	RT	↓			-				ļ			11				+			622.5	616.01	616.01	617.01	616.01				
7	DRU 2 DRU 2	598+60 598+60	3	LT RT	 		-	\vdash		-	ļ				1	1			! 			622.05	010.01	610.01	011.01	617.04				
9	DRU 2	599+25	3	LT	╁	 		\vdash		 	 	 	 			1			+			622.44	616.4	616.15	617.15	- GING !				
10	DRU 2	599+25		RT	 	 	1			 	 	 	-		1							622.1				617.18				
11	DRU 2	602+50	3	LT	1	1	\vdash	\vdash				<u> </u>			<u>-</u>	1			1 1			627.45	622.54	617.9	623.04					
12	DRU 2	602+50		RT	1	1				 					1							626.98				623.06				
13	DRU 2	605+50	3	LT		1									1							634.38	629.77	624.04	629.76					
14	DRU 2	605+50		RT											1							633.71				629.78				
15	DRU 3	608+00	3	LT		<u> </u>				<u> </u>					1				1_1			638.17		631.65	633.64					
16	DRU 3	608+00		RT		ļ				ļ	<u> </u>				1				11			637.59	671.05		677.07	633.66				
17	DRU 3	611+50	3	LT	 	-	 			ļ	ļ		ļ		1							638.32 638.14	631.95		633.87	633.9				
18	DRU 3	611+50	-	RT		 	₩			<u> </u>		<u> </u>			1				++			634.64	626.07	630.63	630.07	633.3			·····	
19	DRU 3	614+50	3	LT	 	├	 			 		-			1							634.52	626.01	630.63	630.01	630.1				
20	DRU 3 DRU 3	614+50	3	RT LT		┼		-		 		ļ			1							627.82	617.54	623,82	623.04	030.1				
21	DRU 3	617+50 617+50	J	RT		 		-		 					1				┼─┼			627.56	OI I I	023102	025,01	623.07				-
23	DRU 3	620+50	3	LT	+	+-	 	 			·	 				1			1			620.55	609.23	616.05	615.98					
24	DRU 3	620+50	- <u></u>	RT	†	 	 			 	 	 	 		1	1						620.39	***************************************			616.01				
25	DRU 4	623+50	3	LT	T	†	†			 	1					1						613.35	604.47	607.72	608.47					
26	DRU 4	623+50		RT	1										1							613.03				608.5				
27	DRU 4	626+50	1.5	LT												1						608.18	598.73	602.98	603.98					
28	DRU 4	626+50	1.5	RT	<u> </u>						<u> </u>				1				1_1			608.09				603.99				
29	DRU 4	629+25	1.5	LT	ļ	ļ					ļ	ļ	-			1			\perp			606.39	598.18	598.18	601.83	501.05				
30	DRU 4	629+25	1.5	RT	ļ	—	 	ļļ		ļ			1		1				-			606.26	597.81			601.86				
30a	DRU 4	629+85	5.5	LŢ	-			├		1	1								+				231.01	598.15	 					
31a 31	DRU 4 DRU 4	630+29 631+00	6.5 1.5	LT	 		+-			1 -	 	ļ			 	1	-		+			605.33	600.33	598.35	599.35					
32	DRU 4	631+00	1.5	RT	+	 	 	 		 	 	 	 		1				+			605.15		000.00	555.55	599.36				
33	DRU 4	632+00	1.5	LT	1	\vdash	\vdash	+-1		1	 	 			<u> </u>	1			+			605.66	600.91	600.66	601.66					
34	DRU 4	632+00	1.5	RT	1	1	1	\Box	l	 	1		1		1				1 1			605.52				601.67				
35	DRU 4	634+50	1.5	LT	1	T	1									1						606.31	601.79	601.54	602.29					
36	DRU 4	634+50	1.5	RT			1			1					1							606.33				602.3				
37	DRU 5	637+00	1.5	LT											1				\Box			607.43	602.81	602.56	603.06					
38	DRU 5	637+00	1.5	RT	1		L								1				1 1			607.3			<u> </u>	603.07				
39	DRU 5	640+00	1.5	LT		<u> </u>	_		ļ	 	<u> </u>	ļ			1				11			608.6		604.35	604.6	604.64				
40	DRU 5	640+00	1.5	RT	ļ	-	<u> </u>		ļ	 		ļ	 		1			ļ	+			608.56 610.16	602.64	-	602.64	604.61 602.57				
41	DRU 5	642+75	-	RT	+ .		1			 	 		-			-		ļ	+			610.16	602.64	602.68	602.64	602.51	ļ			
42	DRU 5	642+86	-	RT LT	1	╂		-	ļ	 	 	_	 			 			++	1			615.97	002,08	ME	ME				
86 87	DRU 6	701+53 702+00	1.5	LT	+			 		ļ	 	 	+		1			 	++		ļ	628.79	624.54	616.42	623.7	14/1-				
88	DRU 6	702+00	1.5	RT	+	+	+	\vdash		 	 	 	 		1	 	-	 	+			628.81	JE 70 1	010112	02081	623.71				
89	DRU 6	705+00	1.5	LT	+	1	+	$\vdash \vdash \vdash$		-	ļ	 	 		1	 		-	+			634.76	630.76	626.65	630.76					
90	DRU 6	705+00	1.5	RT	†	1	1	\vdash	l				†		1				+			634.96			T	630.77				
91	DRU 6	708+00	1.5	LT	1	1	1	\vdash	l	†	†	1			1	1			T			639.16		632.79	632.79					
92	DRU 6	708+00	1.5	RT	1		1		 	1	1				1							639.2				632.8				
93	DRU 7	713+00	1.5	LT						L					1							639.63	633.47		635.55					
94	DRU 7	713+00	1.5	RT											1				ΙĪ			639.59		L	l	635.56	l	<u> </u>		

Γ	REVIS10	NS	
	NAME	DATE	
PARSONS			
BRINCKERHOFF			
SMITH ENGINEERING			
CONSULTANTS, INC.			SC
www.smithengineering.com			n.

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE SCHEDULE -STRUCTURES

SCALE: 1" = 50'
DATE: 07/21/2006

CONTRACT NO. 60886

A.P. SECTION COUNTY TOTAL SHEET
SHEETS NO.
55 2006-032 BY WILL 505 197

STA. TO STA.

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

ROAD DIST. NO. | ILLINOIS FED. AID PROJECT | SSCH 02 OF 02

DRAINAGE STRUCTURE SCHEDULE

			· · · · · · · · · · · · · · · · · · ·		531	MA	ANHOLE	s						>		CATO	H BASI	NS.		뷥	핕		Journal	MPM MANAGEMENT 15 15 15 15 15 15 15 1						
85		L	OCATION		542531									7 F F F F F F F F F F F F F F F F F F F					ΤY	E PI	E E									
NUMBER	NUMBER				STANDARD		TYPE	<u> </u>			PRECAS	Т		AGE STRUCTURE TY W/TWO TY 20 F&G		TYF	PE A		c	REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 18" RISER	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 18" RISER									
뵕			p		TAN	ו	TY 1 F	•			F.E.S.			STRU 70 T		TVD	E 20			CON PIF	SIS PIS									
STRUCTURE	SHEET	STATION	T (FT)		Box s			\dashv						GE :		FRAME		E	8 F	30, EB	36, 36	RIM				INVERT EL	LEVATIONS	*		
STR	S	STA	OFF SET	SIDE	- B	F		ᇤ			1	Γ	 	DRAINAGE 8x3, W/TI		T			J≿	FOR TEE,	15 OF OR	ELEV		1	ı	1	COUTU	Luonzu	COUTU 1	NORTH
			Ö		INLET	4	5	٥	12"	24"	27"	30"	36"	₩ 6	14 F	5 FT	6 FT	8 FT		REI	REI	. .	NORTH	SOUTH	EAST	WEST	SOUTH EAST	NORTH EAST	SOUTH WEST	WEST
95	DRU 7 DRU 7	716+00 716+00	1.5	LT RT											1							635.44 635.61	626,88	631.44	631.44	631.45				
96 97	DRU 7	719+00	1.5	LT	+ -		-			<u> </u>	 		ļ		1 1	 	-		+		-	629.21	621.76	624.96	625.21	031.43				
98	DRU 7	719+00	1.5	RT											1							629.32				625.22				
99	DRU 7	721+35	1.5	LT			 			ļ	1				1	ļ	ļ		\perp			625.06	614.4	620.29	620,79	500.0				
100	DRU 7 DRU 7	721+35 721+55	1.5	RT LT	-								-		1		ļ		1		1	625.27	 		ME	620.8 ME				
118	DRU 7	721+56	76	LT	-		1						1		 	1	ļ		+		· ·		<u> </u>		1442	613.9				
121	DRU 2	598+70	128	LT						1												611				611.9				
123	DRU 12	889+36	125	LT															1			602.5							601	
124	DRU 12	889+04	72	LT	 	ļ			1	ļ	-					_			-				616.5		ļ	ļ		600.8		
204 205	DRU 8 DRU 8	751+20 751+65	1.5	RT LT	1	1			ļ	<u> </u>	 		 		 	 	<u> </u>		+		 	618.5	613.32	615.75						
206	DRU 8	752+00	1.5	LT							 		 		1	 			+			618.88	613.23	613.23	1					
207	DRU 8	752+00	1.5	RT											1							618.88	612.27	614.52						
208	DRU 8	755+00	1.5	LT											1							617.44	611.7	611.95						
209	DRU 8	755+00	1.5	RT	ļ						ļ		ļ		1	ļ	[\bot		ļ	617.59 615.98	611.47 610.91	611.47	<u> </u>			ļ		
210	DRU 9 DRU 9	758+00 758+00	1.5 1.5	LT.	 		1				1				1 1				+-			616.43	610.4	610.91 610.65	ļ					
212	DRU 9	761+00	1.5	LT	†					 	 	l	 		 	 1			1-1			614.59	609.74	609.99						
213	DRU 9	761+00	1.5	RT												1						614.9	609.77	609.77						
214	DRU 9	763+50	1.5	LT												1						613.59	609.22	609.22						
215	DRU 9	763+50	1.5	RT	-	ļ					ļ		ļ			1 1			\perp		ļ	614 . 06 613 . 19	609.25 608.81	609,25	1					
216 217	DRU 9 DRU 9	765+50 765+50	1.5 1.5	LT RT			-									1 1		ļ	+-			613.69	608.55	608.81 608.8						
218	DRU 9	766+55	1.5	LT			\vdash			 	 				1	1 1			+			613.16	608.83	608.58	608.33	607.83				
2180	DRU 9	766+55	66.5	LT						 		1													607.7					
219	DRU 9	766+55	1.5	RT												1						613.66	608.34	608.34		608.34				
220	DRU 9	767+00	1.5	LT		ļ					ļ		ļ		1		ļ		\perp			613.16	609.21	608.76						
221 222	DRU 9 DRU 9	767+00 768+50	1.5 1.5	RT LT			\vdash	_			-		 		1				+-			613.66 613.24	609.22 609.94	608.97 609.69				 		
223	DRU 9	768+50	1.5	RT	 	 	 -				 				1			 	+			613.8	609.95	609.7				-		
224	DRU 9	770+50	1.5	LT							†				i							613.72		610.82	1					
225 226	DRU 9	770+50	1.5	RT											1							614.3		610.83						
226	DRU 10	773+20	1.5	LT	ļ	ļ			ļ	ļ	1	ļ	 		 _	1			\perp		-	614.92	608.85	608.6	610.91	610.04		<u> </u>		
226c	DRU 10 DRU 10	773+20 776+61	1.5	RT LT	 		+-+					ļ			1 1	 	 		+		-	615.27 615.95	611.3	611.05	611.95	610.94	-			
228	DRU 10	776+61	1.5	RT	+		+			 	+	 			1 1	 	 		+-		 	618.08	1	0.1100	0.11.00	611.98		 		
229	DRU 10	779+25	70	LT						†	1	İ	1		† -														618	
230	DRU 10	781+00	70	LT									1															618.35		
231	DRU 10	779+00	1.5	LT	 	 					1				1	ļ	ļ		\perp			619.81		613.22	615.81	C1E 04				
232 233	DRU 10 DRU 10	779+00 782+00	1.5 0.34	RT LT	 					 	-				1	1	-		+-		 	620.28 623.33				615.84	619,86	619.86		
234	DRU 10	782+00	2,69	RT	+		\vdash			 	 		 		+ 1	+			+		 	623.59	<u> </u>				013:00	013.00		
235	DRU 10	784+00	1.5	LT	1		1			 	1	 	1		†	ı						626.38					622.38	621.63	621.13	
236	DRU 10	784+00	1.5	RT											1							625.92		•						
237	DRU 10	786+00	1.5	LT	<u> </u>						 	ļ			1 1	ļ			1-1		-	628.6	-		ļ		624.6		623.34	
238 239	DRU 10 DRU 10	786+00 782+00	1.5	RT LT	-	ļ	\vdash		ļ	1	 		-		1	 			-			629,04			ļ		619.75			
539	סז העת	102700	102		1	 	$\vdash \vdash$			- ' -						 	<u> </u>	<u></u>	+				<u> </u>	<u> </u>	<u> </u>		013113			
		 	1	l	1		+			 	 				1	t			+		 	ļ			1					
<u></u>		TOTALO	1		 _	.	├ —┼		<u> </u>				L			 			1.1		↓_				<u> </u>					
L		TOTALS			12	1	1		1	1 5	1	1	3	l	1 65	21	L	L	1	1	1	1	<u> </u>	I	1	L	L	L	L	



ILLINOIS DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE SCHEDULE -STRUCTURES

SCALE: 1" = 50' DATE: 07/21/2006

PIPE UNDERDRAIN SCHEDULE

STATION	TO STATION	OFFSET (FT)	PIPE UNDERDRAINS 6" (FT)	PIPE UNDERDRAINS (SPECIAL) 6" (FT)
589+16	590+44	RT	128	
589+12	590+44	LT	128	
590+44	590+48	RT	120	4
590+44	590+48	LT		4
590+58	593+44	RT RT	286	
590+58	593+44	LT	286	
593+44	593+48	RT ·		4
593+44	593+48	LT		4
593+58	596+42	RT	284	
593+58	596+42	LT	284	
596+42	596+46	RT		4
596+42	596+46	LT		4
596+56	598+54	RT	198	
596+56	598+54	LT	198	
598+54	598+58	RT		4
598+54	598+58	LT		4
598+61	598+65	RT		4
598+61	598+65	LT		4
598+65	599+20	RT	55	
598+65	599+20	LT	55	
599+26	599+30	RT		4
599+26	599+30	LT	740	4
599+30	602+42	RT	312	
599+30	602+42	LT	312	ļ
602+52	602+56	RT		4
602+52	602+56	LT	200	4
602+56	605+45	RT	289	
602+56	605+45	LT RT	289	4
605+52	605+56			4
605+52	605+56	LT	236	7
605+56	607+92 607+92	RT LT	236	
605+56	611+42	RT	126	
610+16 610+10	611+42	LT	132	
611+42	611+46	RT	132	4
611+42	611+46	LT		1 4
611+58	614+44	RT	286	
611+58	614+44	LT	286	
614+44	614+48	RT	200	4
614+44	614+48	LT		4
614+58	617+44	RT	286	<u> </u>
614+58	617+44	LT	286	
617+44	617+48	RT		4
617+44	617+48	LT		4
617+58	620+44	RT	286	
617+58	620+44	LT	286	
620+44	620+48	RT		4
620+44	620+48	LT		4
620+58	623+44	RT	286	
620+58	623+44	LT	286	
623+44	623+48	RT		4
623+44	623+48	LT		4
623+58	626+44	RT	286	
623+58	626+44	LT	286	
626+44	626+48	RT		4
626+44	626+48	LT		4
626+58	629+19	RT	261	ļ
626+58	629+19	LT	261	
629+19	629+23	RT		4
629+19	629+23	LT		4
631+02	631+06	RT		4
631+02	631+06	LT	1 00	4
631+06	631+92	RT	86	
631+06	631+92	LT	86	4
632+02	632+06	RT		
632+02	632+06	LT	270	4
632+06	634+42	RT LT	236	
632+06	634+42		236	4
634+52	634+56 634+56	RT LT		4
634+52 634+56	636+92	RT	236	-
634+56	636+92	LT	236	
		**************	ا مر	4
637+02 637+02	637+06 637+06	RT LT		4
637+06	639+92	RT	286	T
	639+92	LT	286	
637+06				

PIPE UNDERDRAIN SCHEDULE

STATION	TO STATION	OFFSET (FT)	PIPE UNDERDRAINS 6" (FT)	PIPE UNDERDRAINS (SPECIAL) 6" (FT)
640+02	640+06	RT		4
640+02	640+06	LT		4
640+06 640+06	641+00 641+00	RT LT	94	
699+30	699+40	RT	34	10
699+30	699+40	LT		10
699+40	702+02	RT	262	
699+40	702+02	LT	262	
702+02	702+06 702+06	RT LT		4
702+02 702+06	704+92	RT	286	4
702+06	704+92	LT	286	
705+02	705+06	RT		4
705+02	705+06	LT		4
705+06	707+92	RT	286	
705+06 711+35	707+92 712+94	LT RT	286 159	
711+35	712+94	LT	159	
712+94	712+98	RT		4
712+94	712+98	LT		4
713+08	715+94	RT	286	
713+08 715+94	715+94 715+98	LT RT	286	4
715+94	715+98	LT		4
716+08	718+94	RT	286	
716+08	718+94	LT	286	
718+94	718+98	RT		4
718+94	718+98	LT		4
719+08	721+27	RT	219	
719+08 721+54	721+54 721+58	LT LT	246	4
751+75	751+94	LT	19	T
751+75	751+94	RT	19	
751+94	751+98	LT		4
751+94	751+98	RT		4
752+08	754+94	LT	286	
752+08 754+94	754+94 754+98	RT LT	286	4
754+94	754+98	RT	1	4
755+08	757+94	LT	286	
755+08	757+94	RT	286	
757+94	757+98	LT		4
757+94	757+98	RT	2000	4
758+08 758+08	760+94 760+94	LT RT	286	l
760+94	760+98	LT	200	4
760+94	760+98	RT		4
761+08	763+44	LT	236	
761+08	763+44	RT	236	
763+44	763+48	LT		4 4
763+44 763+58	763+48 765+44	RT LT	186	-
763+58	765+44	RT	186	
765+44	765+48	LT		4
765+44	765+48	RT		4
765+58	766+44	LT	86	ļl
765+58 766+44	766+44 766+48	RT LT	86	4
766+44	766+48	RT		4
766+52	766+56	LT		4
766+52	766+56	RT		4
766+56	766+92	LT	36	ļ
766+56 767+02	766+92 767+06	RT LT	36	4
767+02	767+06	RT	1	1 4 1
767+06	768+42	LT	136	
767+06	768+42	RT	136	
768+52	768+56	LT		4
768+52	768+56	RT	100	4
768+56 768+56	770+42 770+42	LT RT	186 186	
770+52	770+56	LT	100	4
770+52	770+56	RT		4
770+56	771+70	LT	114	
770+56	771+80	RT	124	<u> </u>
773+22	773+26	LT	1	4

PIPE UNDERDRAIN SCHEDULE

			PIPE	PIPE
STATION	то	OFFSET	UNDERDRAINS	UNDERDRAINS
31711011	STATION	(FT)	6"	(SPECIAL) 6"
			(FT)	(FT)
773+22	773+26	RT		4
773+26	776+40	LT	314	
773+26	776+40	RT	314	
776+65	778+82	LT	217	
776+65	778+82	RT	217	
779+02	779+06	LT		4
779+02	779+06	RT		4
779+06	781+86	LT	280	
779+06	781+86	RT	280	
781+94	781+98	LT		4
781+94	781+98	RT		4
781+98	783+92	LT	194	
781+98	783+92	RT	194	
784+02	784+06	LT		4
784+02	784+06	RT		4
784+06	785+92	LT	186	
784+06	785+92	RT	186	
786+02	786+06	LT		4
786+02	786+06	RT		4
		TOTALS	18793	352

	REVISIONS	
	NAME	DATE
PD PARSONS BRINCKERHOFF		
SMITH ENGINEERING CONSULTANTS, INC. www.smithengineering.com		


ILLINOIS DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE SCHEDULE -PIPE UNDERDRAIN

SCALE: 1" = 50'
DATE: 07/21/2006







TBE GROUP, INC.

CIVIL ENGINEERING * TRANSPORTATION * ENVIRONMENTAL

* PLANNING * UTILITY ENGINEERING/LOCATING

GROUF

IL09500132, 142, 158, 229, 245 TBE SUE PAGE NO: 25 of 29 Checked by: ______

Utility Quality Level "A" : Test Holes Utility Quality Level "B" : Designating

The SBC locations depicted have been obtained through the application of geophysical methods to determine the existence and approximate horizontal position of these facilities. However, SBC will not provide TBE Group, Inc. with utility records nor allow access to their field closures (pedestals/manholes etc.), to help verify the locations of their existing underground facilities. Therefore, TBE is unable to verify the completeness of the SBC locations depicted in accordance with the CI/ASCE Standard 38-02.

Utilities shown on these plans as depicted in the legend have been investigated by TBE Group, Inc in accordance with SUE Industry Standards. All other information shown has been provided to TBE Group, Inc by others. Changes to utilities after dates shown may have been made and therefore may result in variances from this plan. Consideration should be given to updating this plan if deemed advisable prior to final design and construction.

205 W. WACKER DRIVE SUITE 1020 CHICAGO, IL 60606 (312) 704-1970

REVISIONS	5	
NAME	DATE	ILL
A	i	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUE Investigation of Underground Utilities
I-55/I-80 from US RT. 30 to Weber Road
Section No. 99 (1&2) WRS-1
Contract No. 62895 and 62896
Will County

SQL "B" DATE : 1/17/06

DRAWN BY : KLC SCALE : 1" = 50'

