

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE															
				URBAN ROADWAY	RETAINING WALL		MWRD BOX CULVERT	SIGNING	SAFETY	LIGHTING	SURVEILLANCE								
					016-W977	43rd-31st						Y000	Y007	Y007	X02B-2A	Y002-1C	SFTY-3N	Y030-1E	Y032-1F
40600300	AGGREGATE (PRIME COAT)	TON	87.8	87.8															
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	6,214	6,214															
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	430						430										
42001300	PROTECTIVE COAT	SQ YD	137,134	137,134															
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	83,902	83,902															
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	2,371	2,371															
44000009	BITUMINOUS SURFACE REMOVAL 3"	SQ YD	267	267															
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1,664	1,626					38										
44000100	PAVEMENT REMOVAL	SQ YD	114,998	114,998															
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	36,897	36,897															
44000700	APPROACH SLAB REMOVAL	SQ YD	164						164										
44001980	CONCRETE BARRIER REMOVAL	FOOT	419	419															
44003100	MEDIAN REMOVAL	SQ FT	10,297	10,297															
44004250	PAVED SHOULDER REMOVAL	SQ YD	5,297	5,297															
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	616	616															
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1													
50102400	CONCRETE REMOVAL	CU YD	18			18													
50200100	STRUCTURE EXCAVATION	CU YD	583			101			108									298	
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	269.4	269.4															
50300225	CONCRETE STRUCTURES	CU YD	400.3			29.8			197.7									143.5	29.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	205.1			88.1			86.6									97.1	10.8 2.5
50300260	BRIDGE DECK GROOVING	SQ YD	153															153	
50300300	PROTECTIVE COAT	SQ YD	1729			686			456									263	34 290
50300510	RUSTICATION FINISH	SQ FT	8403			4352			3507									61	483
50500505	STUD SHEAR CONNECTORS	EACH	1734			1034			700										
50700209	UNTREATED TIMBER LAGGING	SQ FT	6677			3837			2840										
50700211	FURNISHING SOLDIER PILES (W SECTION)	FOOT	874																
50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	4339			2,150			2,189										
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	102,110			5240			41,160									32,360	17,690 1120 4540
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	8785			8785													
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	558			558													

• DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 GARFIELD BLVD TO 31ST STREET (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: June 9, 2006

DRAWN BY: PHP
 CHECKED BY: RMG



Rev. 8-22-06 Rev.

S00-2

6/8/2006 4:03:31 PM P:\040658\civil\B-civil\18 & 19\311\cvt\18general\900220a.dwg