

SAFETY ITEMS SCHEDULE

STATION TO STATION	STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	CONCRETE BARRIER TRANSITION	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER, DIRECT APPLIED	BARRIER BASE	CONCRETE BARRIER SINGLE FACE, 32" HEIGHT	CONCRETE BARRIER DOUBLE FACE, 32" HEIGHT	CONCRETE BARRIER, SINGLE FACE, 32" HEIGHT (MODIFIED)	IMPACT ATTENUATOR (SEVERE USE, NARROW) TEST LEVEL 3	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 2
	FOOT	EACH	EACH	EACH	EACH	FOOT	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	EACH	EACH
4474+50.00 TO 4480+00.00	-	-	-	-	-	79	-	12	-	465	0	386	0	-	-
4480+00.00 TO 4492+00.00	-	-	-	-	-	0	-	29	-	1,148	0	1,148	0	-	-
4492+00.00 TO 4504+00.00	150.0	-	1	1	-	111	3	29	1	1,166	63	992	0	-	-
4504+00.00 TO 4516+00.00	-	-	-	-	-	66	-	30	-	1,192	0	1,126	0	1	-
4516+00.00 TO 4529+00.00	25.0	-	1	1	-	81	1	6	1	296	182	33	0	2	-
4529+00.00 TO 4541+00.00	-	-	-	0	0	-	-	9	0	711	610	0	101	-	-
4541+00.00 TO 4533+00.00	125	-	1	1	0	32	3	23	1	1,799	774	993	0	2	-
4533+00.00 TO 4565+00.00	225	-	1	2	0	77	5	16	2	1,200	0	1,050	73	1	-
4565+00.00 TO 4577+00.00	212.5	1	1	1	0	466	5	18	1	1,377	38	804	69	2	-
4577+00.00 TO 4589+00.00	100	-	1	1	0	138	2	20	1	1,537	374	939	86	-	-
4589+00.00 TO 4601+00.00	-	-	-	0	0	70	-	15	0	1,176	0	1,106	0	-	1
4601+00.00 TO 4613+00.00	175	-	1	1	0	56	4	15	1	1,200	0	1,068	76	-	-
4613+00.00 TO 4625+00.00	-	-	-	0	0	72	-	26	0	2,074	802	1,086	114	-	-
4625+00.00 TO 4637+00.00	-	-	-	0	0	-	-	29	0	2,263	959	1,200	104	1	-
4637+00.00 TO 4638+05.00	-	-	-	0	0	-	-	6	0	456	0	456	0	-	-
TOTALS	1,012.5	1	7	8	0	1,248	23	283	8	18,059	3,801	12,386	624	7	1

PAVEMENT MARKING SCHEDULE

STATION TO STATION	POLYUREA PAVEMENT MARKING TYPE 1- LETTERS AND SYMBOLS	POLYUREA PAVEMENT MARKING, TYPE I-LINE 4"	POLYUREA PAVEMENT MARKING, TYPE I-LINE 5"	POLYUREA PAVEMENT MARKING, TYPE I-LINE 8"	POLYUREA PAVEMENT MARKING, TYPE I-LINE 12"	POLYUREA PAVEMENT MARKING TYPE I-LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
	SO FT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH
4474+50.00 TO 4482+00.00	-	3,002	940	-	82	-	95	-
4482+00.00 TO 4506+00.00	-	7,599	2,821	3,918	290	-	319	-
4506+00.00 TO 4529+00.00	-	6,896	2,420	7,036	1,535	-	322	-
4529+00.00 TO 4553+00.00	-	8,908	2,570	7,540	1,786	12	321	-
4553+00.00 TO 4577+00.00	-	10,220	3,000	3,033	467	12	330	-
4577+00.00 TO 4601+00.00	127.4	9,765	3,000	1,585	344	0	316	4
4601+00.00 TO 4625+00.00	36.4	8,313	3,106	3,223	397	51	311	-
4625+00.00 TO 4638+05.00	72.8	5,774	1,881	4,637	1,225	0	363	-
TOTALS	236.6	60,477	19,738	30,972	6,126	75	2,377	4


REVISIONS	
NAME	DATE
ADDENDUM 2	8/07/06

SCH-3

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
GARFIELD BLVD TO 31ST STREET (NB LOCAL LANES)

SCHEDULE OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG



D:\040465\CHIN\IB-contrs 18 & 19\SH\CONT IB\Schedules\62301\032a.sft 8/8/2006 3:44:13 PM