

SCHEDULE OF STORM SEWERS

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 2, 12	SS CL A 2, 15	SS WMQP, 12	TRENCH BACKFILL (CU. YD.)	ROCK EXCAVATION
29-04	14-29-09	63.7	12	1.00%	63.7			72.9	
29-03	29-04	121.0	12	1.00%	121.0			84.2	
29-07	29-03	4.5	12	1.00%	4.5			2.2	
29-05	14-28-14	73.7	12	1.00%	73.7			17.3	
29-02	29-01	10.5	12	1.00%	10.5			1.3	
29-01	29-05	131.6	12	1.00%	131.6			14.6	
29-06	29-05	4.3	12	1.00%	4.3			0.4	
30-01	14-29-14	64.0	12	1.00%	64.0			11.0	
30-04	14-30-01	68.6	12	1.00%	68.6			29.1	
30-03	30-04	6.0	12	2.50%	6.0			1.5	
30-02	30-03	18.0	12	1.00%	18.0			1.4	
30-07	14-30-05	73.5	12	1.00%	73.5			52.5	
30-06	30-07	6.7	12	2.50%	6.7			5.2	
30-05	30-06	18.0	12	1.00%	18.0			15.6	
30-08	14-30-05	24.5	12	1.00%	24.5			3.2	
30-18	14-30-09	25.3	12	1.00%	25.3			9.9	
30-17	30-18	48.8	12	1.00%	48.8			7.5	
30-14	30-17	47.0	12	1.00%	47.0			7.2	
30-10	30-12	17.3	12	1.00%	17.3			1.4	
30-12	30-14	11.2	12	1.00%	11.2			1.1	
30-11	30-12	18.0	12	1.00%	18.0			2.1	
30-09	30-11	17.6	12	1.00%	17.6			2.2	
30-13	30-11	11.5	12	1.00%	11.5			1.4	
30-16	30-17	2.6	12	1.00%	2.6			0.1	
30-15	30-16	18.0	12	1.00%	18.0			1.8	
30-19	30-15	16.0	12	1.00%	16.0			1.8	
31-03	14-30-14	27.7	12	1.00%	27.7			8.0	
31-02	31-03	47.7	12	1.00%	47.7			7.6	
31-01	31-02	22.0	12	1.00%	22.0			2.2	
31-04	31-01	11.0	12	1.00%	11.0			0.8	
31-07	14-30-17	30.6	12	1.00%	30.6			25.1	
31-06	31-07	47.5	12	1.00%	47.5			7.6	
31-05	31-06	19.9	12	1.00%	19.9			1.9	
31-08	31-05	51.1	12	1.00%	51.1			4.9	
31-09	14-30-22	70.1	12	1.00%	70.1			13.6	
31-10	31-09	27.2	12	1.00%	27.2			2.7	
31-11	14-31-01	60.6	12	1.00%	60.6			11.1	
31-12	14-31-04	58.2	12	1.00%	58.2			8.6	
32-01	14-31-06	57.5	12	1.00%	57.5			6.2	
32-02	14-31-11	57.9	12	1.00%	57.9			9.9	
32-04	14-31-16	71.3	12	1.00%	71.3			9.3	
32-03	32-04	11.0	12	1.00%	11.0			0.8	
32-09	32-04	4.5	12	1.00%	4.5			0.5	
32-08	14-32-01	66.0	15	0.35%		66.0		29.1	
32-07	32-08	18.0	15	1.00%		18.0		3.3	

SCHEDULE OF STORM SEWERS

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 2, 12	SS CL A 2, 15	SS WMQP, 12	TRENCH BACKFILL (CU. YD.)	ROCK EXCAVATION
32-06	32-07	16.9	12	1.00%	16.9			2.4	
32-05	32-06	31.0	12	1.00%	31.0			3.8	
32-10	32-07	4.8	12	1.00%	4.8			0.6	
33-01	32-07	10.1	12	1.00%	10.1			1.3	
33-02	33-01	46.0	12	1.00%	46.0			5.9	
33-04	14-32-05	56.9	12	1.00%	56.9			18.5	
33-06	33-04	43.0	12	1.00%	43.0			7.3	
33-03	33-06	39.7	12	2.50%	39.7			15.3	
33-08	33-03	4.5	12	1.00%	4.5			0.2	
33-05	14-32-09	55.3	12	1.00%	55.3			11.5	
34-02	34-01	11.0	12	1.00%	11.0			0.9	
34-01	14-32-13	51.5	12	1.00%	51.5			7.0	
34-04	14-33-07	52.8	15	1.00%		52.8		12.9	
34-03	34-04	11.0	12	1.00%	11.0			1.9	
34-05	34-04	10.9	12	1.00%	10.9			1.9	
34-06	34-05	18.9	12	1.00%	18.9			3.1	
34-07	14-33-14	51.4	12	1.00%	51.4			6.6	
34-08	14-33-18	52.2	12	1.00%	52.2			7.6	
34-09	34-10	47.6	12	1.00%	47.6			4.7	
35-02	14-34-01	51.6	12	1.00%	51.6			6.9	
35-01	35-02	55.9	12	2.50%	55.9			40.3	
35-06	14-34-05	51.5	12	1.00%	51.5			38.5	
35-05	35-06	3.5	12	1.00%	3.5			1.3	
35-04	35-05	18.0	12	1.00%	18.0			6.9	
35-03	35-04	36.0	12	1.00%	36.0			13.5	
35-07	35-04	70.9	12	1.00%	70.9			21.0	
36-02	14-34-10	65.8	12	1.00%	65.8			13.9	
36-01	36-02	26.0	12	1.00%	26.0			3.9	
36-04	14-35-01	63.3	12	1.00%	63.3			8.2	
36-03	36-04	22.0	12	1.00%	22.0			1.6	
36-06	14-35-08	60.6	12	1.00%	60.6			10.1	
36-05	36-06	12.7	12	1.00%	12.7			1.3	
36-07	36-06	11.1	12	1.00%	11.1			1.1	
36-08	14-35-15	59.6	12	1.00%	59.6			10.3	18.54
37-02	14-35-20	61.6	12	1.00%	61.6			24.5	25.96
37-01	37-02	86.1	12	1.00%	86.1			21.0	29.91
37-03	37-02	96.0	12	1.00%	96.0			37.3	38.12
37-04	14-36-01	74.0	12	1.00%	74.0			20.3	
37-05	37-04	11.0	12	1.00%	11.0			2.1	
38-02	EX P	49.8	12	1.00%	49.8			19.0	
37-09	38-02	66.0	12	1.00%	66.0			20.2	
37-06	37-09	56.1	12	1.00%	56.1			11.0	
37-08	37-09	5.0	12	1.00%	5.0			0.9	
37-07	37-08	18.0	12	1.00%	18.0			3.4	
38-01	38-02	29.4	12	2.50%	29.4			8.5	

SCHEDULE OF STORM SEWERS

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 2, 12	SS CL A 2, 15	SS WMQP, 12	TRENCH BACKFILL (CU. YD.)	ROCK EXCAVATION
38-03	38-01	76.0	12	1.00%	76.0			15.8	
38-04	38-03	18.0	12	1.00%	18.0			3.0	
38-06	14-36-08	49.4	12	1.00%	49.4			20.0	
38-05	38-06	43.5	12	2.50%	43.5			15.6	
38-07	38-05	11.0	12	1.00%	11.0			3.2	
38-09	14-36-09	49.4	12	1.00%	49.4			42.1	
38-08	38-09	54.1	12	2.50%	54.1			49.7	
38-10	38-08	11.0	12	1.00%	11.0			9.7	
38-11	38-10	18.0	12	1.00%	18.0			16.9	
38-13	38-09	4.5	12	1.00%	4.5			0.2	
39-01	14-37-01	51.6	12	1.00%	51.6			15.8	
39-02	14-37-06	51.6	12	1.00%	51.6			5.5	
39-03	14-37-10	51.2	15	1.00%		51.2		17.5	
39-04	39-03	8.5	12	1.00%	8.5			2.0	
39-05	39-04	13.5	12	1.00%	13.5			3.1	
39-06	14-37-20	52.7	12	1.00%	52.7			5.5	
39-07	39-06	4.8	12	1.00%	4.8			0.5	
40-01	14-38-01	60.4	12	1.00%	60.4			14.2	
40-02	40-01	87.0	12	1.00%	87.0			21.6	
40-03	40-02	20.0	12	1.00%	20.0			5.4	
40-05	14-38-05	49.7	12	1.00%	49.7			8.1	
40-04	40-05	22.7	12	1.00%	22.7			2.4	
40-06	40-04	32.0	12	1.00%	32.0			3.1	
40-07	40-06	18.0	12	1.00%	18.0			2.1	
40-08	40-07	3.9	12	1.00%	3.9			0.2	
40-09	14-38-09	51.6	12	1.00%	51.6			5.0	
41-02	14-39-01	51.6	12	1.00%	51.6			16.0	
41-01	41-02	64.0	12	1.00%	64.0			12.3	
41-03	14-39-05	51.6	12	1.00%	51.6			6.0	
41-04	14-39-09	51.6	12	1.00%	51.6			4.9	
42-01	14-39-13	51.6	12	1.00%	51.6			7.6	
42-02	14-40-01	51.6	12	1.00%	51.6			6.9	
42-03	14-40-05	50.7	12	1.00%	50.7			5.2	
43-01	14-40-09	51.6	12	1.00%	51.6			12.2	
43-03	43-01	38.0	12	1.00%	38.0			6.1	
43-02	43-03	1.7	12	1.00%	1.7			0.0	
43-04	14-41-01	67.6	12	1.00%	67.6			8.6	
44-01	14-41-05	62.7	12	1.00%	62.7			26.5	
44-02	44-01	96.0	12	1.00%	96.0			22.2	
44-03	14-41-09	57.7	12	1.00%	57.7			6.0	
44-05	14-41-13	54.5	12	1.00%	54.5			6.3	
44-04	44-05	11.0	12	1.00%	11.0			0.8	
44-06	14-42-01	52.8	12	1.00%	52.8			5.7	
44-08	14-42-10	51.8	12	1.00%	51.8			5.9	
44-07	44-08	12.0	12	1.00%	12.0			0.8	

BOWMAN, BARRETT & ASSOCIATES INC  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com

CONTINUED ON NEXT SHEET

REVISIONS	
NAME	DATE
REVISED	6/22/06
ADDENDUM 2	8/04/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
GARFIELD BLVD TO 31ST STREET (NB LOCAL LANES)  
DRAINAGE SCHEDULES  
PROPOSED STORM SEWER PIPES  
SCALE: 1"=N.T.S.  
DATE: 06/09/06  
DRAWN BY: JAM  
CHECKED BY: DDM