

September 15, 2006

SUBJECT: FAI Route 94/90 Project ACIM-000S (519) Section (2021-922 PT2 ETC 2324.6-1P) R-10 Cook County Contract No. 62301 Item No. 3X, September 22, 2006 Letting Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised pages 1, 3 & 8 of the Schedule of Prices.
- 2. Revised page 49 of the Special Provisions.
- 3. Revised sheets 7 & 15 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine Engineer of Design and Environment

Jerger abechlyne A.E.

By: Ted B. Walschleger, P. E. Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; N. R. Stoner; Roger Driskell; R. E. Anderson; Estimates; Design & Environment File

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 62301 NUMBER -

C-91-418-01 State Job # -PPS NBR -1-74823-0513 County Name -COOK--Code -31 - -District -1 - -

Project Number ACIM-000S/519/ Route FAI 94 FAI 90

Section Number -(2021-922PT2ETC2324.6-1P)R-10

ltem Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	I	Total Price
E20200G1	V-PARTHEN QUINQ 1G	EACH	931.000				
E20220G1	V-PARTHEN TRICUSP 1G	EACH	201.000				
K0030400	PERENNIAL PLANT DAYLI	UNIT	8.360				
* DELETED							
XX002957	REM & RE-E EXIST SIGN	EACH	13.000				
XX003988	TEMP CONC BARRIER REM	FOOT	14,466.000				
XX004046	AERIAL CABLE REMOVAL	FOOT	670.000				
* XX004201	PAVT REINFORCEMENT 14	SQ YD	83,902.000				
** XX004210	DI PIPE STORM SEW 12	FOOT	200.000				
X0320333	ROADWAY CLEANING SPL	EACH	19.000				
X0321720	WATER MAIN REMOVAL	FOOT	1,075.000				
X0321905	SS1 WAT MN 12	FOOT	49.000				
X0322256	TEMP INFO SIGNING	SQ FT	2,143.000				
X0322400	PILE EXTRACTION	EACH	20.000				
X0322859	WEED CONTR PRE-EM GRN	POUND	16.000				
X0323221	PLUG & ABAND EX PIPE	CU YD	8.000				
		* REVISED : AUGUST 22, 2006					
		** REVISED : SEPTEMBER 14, 2006			<u> </u>		

Page 1 9/18/2006 ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 62301 NUMBER -

C-91-418-01 State Job # -1-74823-0513 PPS NBR -County Name -COOK--Code -31 - -1 - -District -

Project Number ACIM-000S/519/ Route FAI 94 FAI 90

Section Number -(2021-922PT2ETC2324.6-1P)R-10

ltem Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0324697	SOIL STABILIZERS	POUND	1,669,253.000				
X0324698	APPLY DUST SUP AGENTS	UNIT	1,331.000				
X0324793	LT TOWER SERV PAD SPL	SQ FT	1,496.000				
X0325080	VIDEO TAPING MWRD CUL	FOOT	245.000				
X0325081	CONC SLAB HY DEM	SQ YD	165.000				
X0325085	TEMP PAVT INTERSTATE	SQ YD	3,162.000				
X0325314	LUG SYSTEM COMPL 38	EACH	2.000				
** DELETED							
* X0325502	MEDIAN BAR GATE SYS	EACH	2.000				
X0325504	CLEAN PIPE UNDERDRAIN	FOOT	4,230.000				
X0325505	CON EN RC 1-2 CNC	FOOT	67.000				
X0325506	CON EN RC 2-2 CNC	FOOT	115.000				
X0325507	LUG SYSTEM COMPL 59	EACH	1.000				
* DELETED							
X0325510	VIDEOTAPE PIPE UDRAIN	FOOT	8,456.000				
X0325511	CON ENCAS RC 5-4 CNC	FOOT	110.000				
		* RE	* REVISED : AUGUST 22, 2006				
** REVISED : SEPTEMBER 14, 2006							

Page 3 9/18/2006 ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 62301 NUMBER -

C-91-418-01 State Job # -1-74823-0513 PPS NBR -County Name -COOK--Code -31 - -District -1 - -

Project Number ACIM-000S/519/ Route FAI 94 FAI 90

Section Number -(2021-922PT2ETC2324.6-1P)R-10

ltem Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25100630	EROSION CONTR BLANKET	SQ YD	63,713.000				
25200200	SUPPLE WATERING	UNIT	1,531.400				
28000250	TEMP EROS CONTR SEED	POUND	30,641.000				
28000300	TEMP DITCH CHECKS	EACH	8.000				
28000510	INLET FILTERS	EACH	415.000				
* 31101810	SUB GRAN MAT B 12	SQ YD	83,920.000				
* 31101860	SUB GRAN MAT B 24	SQ YD	41,324.000				
* DELETED							
** 35300410	PCC BSE CSE 9 1/2	SQ YD	2,355.000				
* 40600200	BIT MATLS PR CT	TON	205.600				
40600300	AGG PR CT	TON	87.800				
42000521	PCC PVT 11 JOINTED	SQ YD	6,214.000				
42001165	BR APPR PAVT	SQ YD	430.000				
42001300	PROTECTIVE COAT	SQ YD	137,134.000				
42100380	CONT REINF PCC PVT 14	SQ YD	83,582.000				
		* REVISED : AUGUST 22, 2006					
		** REVISED : SEPTEMBER 14, 2006					

Page 8 9/18/2006

RECLAIMED GRANULAR MATERIAL

An existing granular sub-base/subgrade of variable thickness is present beneath the Dan Ryan Expressway. The contractor shall reclaim the clean, existing aggregate material from beneath the existing pavement and reuse that material as the 12 inches layer of aggregate below the Aggregate Sub-base, Type B, 12" inches specified in the Special Provision for Extended Life Concrete Pavement (30 Year). The existing granular material is to be removed down to the top of the earthen subgrade or to depth of 42.5 inches below the proposed top of pavement, which ever depth is reached first. Any surplus materials not needed for the 12 inch layer or not meeting the gradation requirements shall be disposed of by the contractor according to Article 202.03 of Standard Specifications.

To be used in reconstruction, the reclaimed aggregate shall meet the minimum gradation requirements as follows:

<u>Sieve Size</u>	Percent Passing
3 inch	100
1 inch	60 - 100
1/2 inch	50 - 90
# 4 sieve	10 - 60
#16 sieve	10 - 50
#200 sieve	0 - 15

The reclaimed aggregate is to be placed below bottom of sub-base granular material type B-12" and compacted in accordance with applicable portions of Section 311 of the Standard Speculations. The reclaimed aggregate shall only be placed under mainline pavement consisting of continuously reinforced portland cement concrete pavement. No reclaimed aggregate shall be placed under portland cement concrete shoulder. Reclaimed aggregate may also be substituted for Porous Granular Embankment Subgrade. Use of this material will not be permitted in the Sub-base Granular Material Type B 12". The contractor is responsible to prevent contamination during excavation and handling and is responsible for proper stockpiling procedures. In areas where the granular material does not extend down to a depth of 42.5 inches below the proposed top of pavement, the remaining earthen subgrade should be excavated to the grades shown in the plans in accordance with the applicable portions of Section 202 of Standard Specifications.

The Contractor shall submit to the Engineer a status report of existing granular material that has been excavated and planned to be re-used on a weekly basis to help in determining material quantity, availability, and assist in forecast production for the following week.

<u>Method of Measurement</u>. This work will be measured for payment in their final positions, as EXCAVATE AND PLACE EXISTING GRANULAR MATERIAL and the volumes computed in cubic yards by the method of average end areas.

EARTH EXCAVATION shall be measured for payment in accordance with Section 202 of the Standard Specifications.

Revised 09-15-2006