

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE															
				J000	RETAINING WALL		MWRD BOX CULVERT	SIGNING	SAFETY	LIGHTING	SURVEILLANCE								
					016-W977	43rd-31st						Y007	Y007						
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	858	858															
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	701	701															
20200100	EARTH EXCAVATION	CU YD	94,292	94,292															
20200200	ROCK EXCAVATION	CU YD	217	217															
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	763	763															
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9709	9709															
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	401			267	134												
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,500	1,500															
20800150	TRENCH BACKFILL	CU YD	3,902	3,902															
20900110	POROUS GRANULAR BACKFILL	CU YD	1,967.9	1,967.9															
* 21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	125,226	125,226															
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	30,724	30,724															
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	32,989	32,989															
* 21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	32,989	32,989															
* 25000210	SEEDING, CLASS 2A	ACRE	10.30	10.30															
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,188	1,188															
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,185	1,185															
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,183	1,183															
NP * 25000750	MOWING	ACRE	12.85	12.85															
* 25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	2.84	2.84															
* 25100630	EROSION CONTROL BLANKET	SQ YD	63,713	63,713															
* 25200200	SUPPLEMENTAL WATERING	UNIT	1,531.4	1,531.4															
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30,641	30,641															
28000300	TEMPORARY DITCH CHECKS	EACH	8	8															
28000510	INLET FILTERS	EACH	415	415															
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	83,920	83,920															
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	41,324	41,324															
<del>31200100</del>	<del>STABILIZED SUB-BASE 4"</del>	<del>SQ YD</del>	<del>8,924</del>	<del>8,924</del>															
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SQ YD	2,355	2,355															
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	205.6	205.6															

NP = NON-PARTICIPATING

• DENOTES SPECIALTY ITEMS



△ Rev. 9-13-06  
 △ Rev. 8-22-06

Rev.

500-1

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 GARFIELD BLVD TO 31ST STREET (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE  
 DATE: June 9, 2006

DRAWN BY: PHP  
 CHECKED BY: RMG

6/8/2006 4:08:30 PM