

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94		COOK	565	12
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
62301 • (2021-922 PT2 ETC 2324.6-1P) R-10				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE							
				URBAN ROADWAY	RETAINING WALL		MWRD BOX CULVERT	SIGNING	SAFETY	LIGHTING	SURVEILLANCE
					016-W977	43rd-31st					
				J000	Y007	Y007	X028-2A	Y002-1C	SFTY-3N	Y030-1E	Y032-1F
• 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	3,026								3,026
• 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	301							51	250
• 81016700	CONDUIT IN TRENCH, 2 1/2" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	38								38
• 81016800	CONDUIT IN TRENCH, 3" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	75								75
• 81017000	CONDUIT IN TRENCH, 4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	8								8
• 81023750	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	472	327							145
• 81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA. PVC	FOOT	510							510	
• 81302630	JUNCTION BOX, NON METALLIC, EMBEDDED IN STRUCTURE, 21"X11"X8"	EACH	1							1	
• 81400200	HEAVY-DUTY HANDHOLE	EACH	11								11
• 81400205	HEAVY-DUTY HANDHOLE (SPECIAL)	EACH	6								6
• 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4,127							206	3,921
• 82106300	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT (INSTALL ONLY)	EACH	6							6	
• 83050870	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-6 FT. MAST ARMS, INSTALL ONLY	EACH	3							3	
• 83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	20							20	
• 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12								12
• 87900200	DRILL EXISTING HANDHOLE	EACH	1								1
• 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	6								6
* E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	931	931							
* E20220G1	VINE-PARTHENOCISSUS TRICUSPIDATA (BOSTON IVY), 1-GALLON POT	EACH	201	201							
* K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	8.36	8.36							
X0320333	ROADWAY CLEANING (SPECIAL)	EACH	19	19							
X0321720	WATER MAIN REMOVAL	FOOT	1,075	1,075							
X0321905	STORM SEWERS, TYPE 1, WATERMAIN QUALITY PIPE, 12"	FOOT	49	49							
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	2,143	2,143							
X0322400	PILE EXTRACTION	EACH	20	20							
X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	16.0	16.0							
X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	8	8							
• X0323360	WOODEN POLE REMOVAL	EACH	2							2	
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	830	830							
• X0323907	COMMUNICATIONS VAULT	EACH	4								4

\* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
GARFIELD BLVD TO 31ST STREET (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: PHP  
DATE: June 9, 2006 CHECKED BY: RMG

CTE | AECOM

S00-6

4/18/06 PM 6/18/2006