

MEDIAN SCHEDULE

STATION	TO	STATION	SAND BACKFILL CU YD	CONCRETE MEDIAN SURFACE 6 INCH (SPECIAL) SQ FT	CONCRETE MEDIAN SURFACE 5 INCH (MODIFIED) SQ FT
3475+50.00	TO	3479+00.00	39	475	0
3479+00.00	TO	3491+00.00	0	415	0
3491+00.00	TO	3503+00.00	0	0	0
3503+00.00	TO	3515+00.00	617	7,781	0
3515+00.00	TO	3526+00.00	214	2,975	0
3526+00.00	TO	3529+00.00	0	0	0
3529+00.00	TO	3541+00.00	0	2,040	3,166
3541+00.00	TO	3533+00.00	0	335	808
3533+00.00	TO	3565+00.00	0	1,256	1,308
3565+00.00	TO	3577+00.00	0	1,294	1,392
3577+00.00	TO	3589+00.00	0	1,022	1,887
3589+00.00	TO	3601+00.00	0	103	0
3601+00.00	TO	3613+00.00	0	75	0
3613+00.00	TO	3625+00.00	0	675	0
3625+00.00	TO	3637+00.00	0	359	0
3637+00.00	TO	3638+05.00	0	0	0
TOTALS			870	18,805	8,561

PAVEMET MARKING SCHEDULE

STATION	TO	STATION	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
			SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH
3475+50.00	TO	3482+00.00	0	2,612	818	0	83	0	85	0
3482+00.00	TO	3506+00.00	0	8,782	3,003	1,628	376	0	323	0
3506+00.00	TO	3529+00.00	0	7,515	2,475	5,488	717	0	295	0
3529+00.00	TO	3553+00.00	127	6,945	2,951	9,481	1,897	36	360	0
3553+00.00	TO	3577+00.00	0	8,181	3,178	3,150	380	23	280	0
3577+00.00	TO	3601+00.00	55	8,453	2,400	2,749	1,158	0	244	4
3601+00.00	TO	3625+00.00	0	8,525	3,538	2,388	298	0	374	0
3625+00.00	TO	3638+05.00	0	5,671	2,310	1,958	451	0	232	0
FRANKLIN CONNECTOR			0	0	1361	27	380	0	0	0
TOTALS			182	56,684	22,034	26,869	5,739	59	2,193	4

SCH-04

REVISIONS	
NAME	DATE
REVISED SHEET	6/23/06
ADDENDUM 2	8/04/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
 GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)

ROADWAY SCHEDULES

SCALE: NTS  
 DATE: 06/09/06  
 DRAWN BY: RA  
 CHECKED BY: RS

BOWMAN, BARRETT & ASSOCIATES INC.  
 CONSULTING ENGINEERS  
 Chicago, Illinois  
 312.228.0100  
 www.bbainc.com



8/7/2006 5:56:26 PM