

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	115BR-1	WINNEBAGO	35	6
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

TEMPORARY FENCE *	
LOCATION	FOOT
AS DIRECTED BY ENGINEER	360
TOTAL	360

\* SEE COMMITMENTS ON SHEET 2 OF 35

PAVEMENT REMOVAL	
LOCATION	SQ YD
STA 62+50 TO STA 63+09.94 (STAGE I)	92
STA 63+42.19 TO STA 64+00 (STAGE I)	88
STA 62+50 TO STA 63+02.44 (STAGE II)	72
STA 63+36.35 TO STA 64+00 (STAGE II)	92
TOTAL	344

EARTHWORK QUANTITIES				
LOCATION	THEORETICAL		SHORTAGE (-) OR EXCESS (+)	REMARKS
	CUT	FILL		
	CU YD	CU YD	CU YD	
			[(A)0.75]-(B)	
	(A)	(B)	(C)	
IL 75				
STAGE I	121	7	84	--
STAGE II	128	39	57	--
TOTAL	249	46	141	
	PAY ITEM	FOR INFO ONLY		
	20200100			

PAVEMENT SCHEDULE								
LOCATION (STA. TO STA.)	31100910 SUB-BASE MATERIAL, TYPE A 12"	35101400 AGGREGATE BASE COURSE, TYPE B	35600300 BASE COURSE WIDENING, 8"	40600900 TEMPORARY RAMP	48101200 AGGREGATE SHOULDERS, TYPE B	48202400 BITUMINOUS SHOULDERS SUPERPAVE 6"	X4073146 BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH), SUPERPAVE, 13 1/4"	X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX 'C', NSO
	SQ YD	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON
STA 60+60 TO STA 62+77.58 (STAGE 1)		24	80					
STA 63+54 TO STA 65+90 (STAGE 1)		24	77					
STA 60+60 TO STA 62+50 (STAGE 2)		18	59					
STA 64+00 TO STA 65+90 (STAGE 2)		19	64					
STA 62+50 TO STA 64+00 (STAGE 1)	292			22	18	58	250	1
STA 62+50 TO STA 64+00 (STAGE 2)	292			25	18	169	283	10
TOTAL	584	85	280	47	36	227	533	11

CHANNEL EXCAVATION	
LOCATION	CU YD
AS DIRECTED BY ENGINEER	37
TOTAL	37

PERIMETER EROSION BARRIER	
LOCATION	FOOT
LT, STA 62+50 TO STA 62+80	30
LT, STA 63+50 TO STA 64+75	125
TOTAL	155

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF  
 QUANTITIES  
 FAP 505 (IL 75)  
 SECTION 115BR-1  
 WINNEBAGO COUNTY

VERT. SCALE: \_\_\_\_\_  
 HORIZ. SCALE: \_\_\_\_\_  
 DATE: 12/05

DRAWN BY NOE  
 CHECKED BY JKC