

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	115BR-1	WINNEBAGO	35	7
STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		

STEEL PLATE BEAM GUARD RAIL, TY. A	
LOCATION	FOOT
STA 60+56.00 TO STA 62+81.00 (STAGE 1)	225
STA 63+68.50 TO STA 64+81.00 (STAGE 1)	112.5
STA 61+64.50 TO STA 62+77.00 (STAGE 2)	112.5
STA 63+64.50 TO STA 64+52.00 (STAGE 2)	87.5
TOTAL	537.50

DELINEATORS	
LOCATION	EACH
AT EACH TYPE 1 TERMINAL END	4
TOTAL	4

TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STA 60+88 TO STA 62+00	112.5
STA 62+00 TO STA 64+50	250
STA 64+50 TO STA 65+62	112.5
TOTAL	475

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
STA. 59+55 TO STA. 67+02	63
STA. 60+60 TO STA. 65+90, LT.	177
STA. 60+60 TO STA. 65+90, RT.	177
TOTAL	417

STEEL PLATE BEAM GUARD RAIL, TYPE B	
LOCATION	FOOT
STA 62+81.00 TO STA 63+06.00 (STAGE 1)	25
STA 63+43.50 TO STA 63+68.50 (STAGE 1)	25
STA 62+77.00 TO STA 63+02.00 (STAGE 2)	25
STA 63+39.50 TO STA 63+64.50 (STAGE 2)	25
TOTAL	100

TEMPORARY BRIDGE TRAFFIC SIGNAL	
LOCATION	EACH
STA 59+95 RT	.25
STA 60+20 LT	.25
STA 66+27 RT	.25
STA 66+52 LT	.25
TOTAL	1

RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STA 60+88 TO STA 62+00	112.5
STA 62+00 TO STA 64+50	250
STA 64+50 TO STA 65+62	112.5
TOTAL	475

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STAGE I	2
TOTAL	2

STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	
LOCATION	FOOT
STA 63+06 TO STA 63+43.5 (STAGE 1)	37.5
STA 63+02 TO STA 63+39.5 (STAGE 2)	37.5
TOTAL	75

SHORT-TERM PAVEMENT MARKING	
LOCATION	FOOT
STA. 59+55 TO STA. 67+02	76
STA. 60+60 TO STA. 65+90, LT.	24
STA. 60+60 TO STA. 65+90, RT.	24
TOTAL	124

THERMOPLASTIC PAVEMENT MARKING		
LOCATION	78000200 4" YELLOW FOOT	78000200 4" WHITE FOOT
STA 59+55 TO STA 67+02	190	
STA 60+60 TO STA 65+90		1060
TOTAL	1250	

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STAGE II	2
TOTAL	2

TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	
LOCATION	EACH
STA 60+56.00	1
STA 61+64.50	1
STA 64+52.00	1
STA 64+81.00	1
TOTAL	4

TEMPORARY PAVEMENT MARKING		
LOCATION	70300220 4" FOOT	70300280 24" FOOT
STAGE I	1003	24
STAGE II	990	---
TOTAL	1993	24

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
STA 62+50 TO STA 64+00	2
TOTAL	2

GUARDRAIL MARKER, TYPE A	
LOCATION	EACH
LT. STA 61+14.5 TO STA 65+02	4
RT. STA 60+06 TO STA 65+31	6
TOTAL	10

GUARDRAIL REMOVAL	
LOCATION	FOOT
STA 61+91.15 TO STA 62+92.81 (STAGE 1)	102
STA 63+70.54 TO STA 64+66.67 (STAGE 1)	96
STA 61+79.43 TO STA 62+75.89 (STAGE 2)	97
STA 63+53.89 TO STA 64+52.32 (STAGE 2)	98
TOTAL	393

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
SHORT TERM PAVEMENT MARKING	41
TEMPORARY PAVEMENT MARKING	713
TOTAL	754

TERMINAL MARKER - DIRECT APPLIED	
LOCATION	EACH
STA 60+06.00	1
STA 61+14.50	1
STA 65+02.00	1
STA 65+31.00	1
TOTAL	4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 505 (IL 75)
 SECTION 115BR-1
 WINNEBAGO COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE: 12/05
 DRAWN BY NOE
 CHECKED BY JKC