

F.A.S. RYS.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1671		DOUGLAS	181	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• 1445BR-2 & 22VBR-1

SUMMARY OF QUANTITIES

SHEET 4 OF 4

X 181-5B X 171-5B

LOCATION OF WORK:
FUNDING BREAKOUT
CONSTRUCTION TYPE CODE:

FAS 1671 RURAL 2L2W FED 80% STATE 20% 1000-2A 1124+40 - 1130+20.93 1131+24.93 - 1139+69.33 1139+69.33 - 1150+67.00 1155+98.5 - 1165+50.00	FAS 1671 BRIDGE SN 021-0062 FED 80% STATE 20% X280-2A 1130+20.93 TO 1131+24.93	FAS 1671 BRIDGE SN 021-0061 FED 80% STATE 20% X181-2A 1150+67.00 TO 1152+69.00	FAS 1671 BRIDGE SN 021-0060 FED 80% STATE 20% X171-2A 1154+06.5 TO 1155+98.50
--	--	--	---

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12.0	12.0			
67100100	MOBILIZATION	L SUM	1.0	1.0			
70100450	TRAFFIC CONT. AND PROTECTION STANDARD 701201	L SUM	1.0		1.0		
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1.0	.2		.3	.3
*70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	78.0	78.0			
*70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17,430.0	17,430.0			
*70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	360.0	360.0			
*70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	93.0	93.0			
*70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	710.0	710.0			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	78.0	78.0			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,914.0	4,914.0			
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	155.0	155.0			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	62.0	62.0			
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	8,403.0	8,403.0			
*78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	2,904.0	2,904.0			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	54.0	54.0			
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	9.0		3.0	3.0	3.0
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	31.0	31.0			
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	11.0	11.0			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	52.0	52.0			
X0322379	CONCRETE SEALER	SO YD	39.3	39.3			
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SO YD	2,520.2	241.0	606.2	852.0	821.0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	536.0	536.0			
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	1,229.0	1,229.0			
X4073146	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/4"	SO YD	4,607.0	4,607.0			
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1.0		1.0		
X0304084	CONCRETE SLOPEWALL	SO FT	4,227.0		7,227.0		
Z0002600	BAR SPLICERS	EACH	200.0		72.0	64.0	64.0
Z0038700	PERMANENT BENCH MARKS	EACH	2.0		1.0		1.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0			.5	.5

• SPECIALTY ITEMS

△ REVISED 9-12-06

SUMMARY OF QUANTITIES

Sheet 4 of 4

PLOT DATE = 7/10/2006
FILE NAME = c:\p02\proj\14505202\081\70258\text.dgn
PLOT SCALE = 42.3528 / IN.
USER NAME = dier-sombir