

F.A.S. RYE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1671	*	DOUGLAS	181	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* 1445BR-2 & 22VBR-1

SUMMARY OF QUANTITIES

SHEET 3 OF 4

X181-5B

X171-5B

LOCATION OF WORK:	FAS 1671 RURAL	FAS 1671 BRIDGE	FAS 1671 BRIDGE	FAS 1671 BRIDGE
FUNDING BREAKOUT	2L2W FED 80% STATE 20%	SN 021-0062 FED 80% STATE 20%	SN 021-0061 FED 80% STATE 20%	SN 021-0060 FED 80% STATE 20%
CONSTRUCTION TYPE CODE:	1000-2A 1124+40 - 1130+20.93 1131+24.93 - 1139+69.33 1139+69.33 - 1150+67.00 1155+98.5 - 1165+50.00	X280-2A 1130+20.93 TO 1131+24.93	X181-2A 1150+67.00 TO 1152+69.00	X171-2A 1154+06.5 TO 1155+98.50

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
51203700	TEST PILE STEEL HP12X74	EACH	2.0				2.0
51205200	TEMPORARY SHEET PILING	SQ FT	416.0			86.0	330.0
51500100	NAME PLATES	EACH	3.0		1.0	1.0	1.0
54001000	BOX CULVERT END SECTIONS	EACH	2.0	2.0			
54002020	EXPANSION BOLTS 3/4 INCH	EACH	4.0	4.0			
54010503	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	156.0	156.0			
54213447	END SECTIONS 12"	EACH	11.0	11.0			
54215415	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 15"	EACH	3.0	3.0			
54248510	CONCRETE COLLAR	CU YD	0.8	0.8			
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	217.0	217.0			
55100500	STORM SEWER REMOVAL 12"	FOOT	90.0	90.0			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	195.0		47.0	86.0	62.0
60100945	PIPE DRAINS 12"	FOOT	675.0	675.0			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	412.0		126.0	154.0	132.0
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	15.0	15.0			
60404400	FRAMES AND GRATES, TYPE 4	EACH	1.0	1.0			
60500060	REMOVING INLETS	EACH	4.0	4.0			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	21.3	21.3			
60602800	CONCRETE GUTTER, TYPE B	FOOT	131.0	131.0			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	265.0	265.0			
60622354	CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)	SO FT	153.0	153.0			
60900515	CONCRETE THRUST BLOCKS	EACH	11.0	11.0			
• 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2,575.0	2,575.0			
• 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.0	1.0			
• 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8.0	8.0			
• 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4.0	4.0			
• 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1.0	1.0			
• 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	10.0	10.0			
• 63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	3,025.0	3,025.0			
66101120	BITUMINOUS SHOULDER CURB	FOOT	1,868.0	1,868.0			
66201120	CONCRETE SHOULDER CURB	FOOT	155.0	155.0			
•	SPECIALTY ITEMS						

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

- F.A.S. ROUTE 1671 (I.L.S. ROUTE 45)
SECTION 1445BR-2 & 22VBR-1
DOUGLAS COUNTY
Sheet 3 of 4

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
DATE: 06/20/06 CHECKED BY: C.R.G.

PLOT DATE = 7/10/2006
FILE NAME = c:\p\projects\0505202 (v01)\70258-ext.dgn
PLOT SCALE = 42.3529 / IN.
USER NAME = plersomb