

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	47BR-2	VERMILION	68	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SHEET 1 OF 3

LOCATION OF WORK:

VERMILION COUNTY

ROADWAY / STRUCTURE
IMPROVEMENTS
FAP 332 (US 150 / IL 1)
STA. 2520+50
STA. 2524+77
80% FEDERAL
20% STATE
X081-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	0.8	0.8
20200100	EARTH EXCAVATION	CU YD	340.0	340.0
20400800	FURNISHED EXCAVATION	CU YD	5120.0	5120.0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	181.0	181.0
* 25000300	SEEDING, CLASS 3	ACRE	0.5	0.5
* 25000314	SEEDING, CLASS 4B	ACRE	0.3	0.3
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	80.0	80.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	80.0	80.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	80.0	80.0
* 25100115	MULCH, METHOD 2	ACRE	0.8	0.8
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80.0	80.0
28000300	TEMPORARY DITCH CHECKS	EACH	12.0	12.0
28000400	PERIMETER EROSION BARRIER	FOOT	796.0	796.0
28000500	INLET AND PIPE PROTECTION	EACH	1.0	1.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	1260.0	1260.0
28200200	FILTER FABRIC	SQ YD	1260.0	1260.0
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	651.0	651.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	18.0	18.0
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	579.0	579.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	267.0	267.0
44000100	PAVEMENT REMOVAL	SQ YD	717.0	717.0
44004000	PAVED DITCH REMOVAL	FOOT	19.0	19.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	73.0	73.0
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SQ YD	386.0	386.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0	1.0
50104650	SLOPE WALL REMOVAL	SQ YD	421.0	421.0
50105220	PIPE CULVERT REMOVAL	FOOT	72.0	72.0
50200100	STRUCTURE EXCAVATION	CU YD	5.7	5.7
50300225	CONCRETE STRUCTURES	CU YD	103.8	103.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	244.2	244.2
50300260	BRIDGE DECK GROOVING	SQ YD	633.0	633.0
50300300	PROTECTIVE COAT	SQ YD	792.0	792.0
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16.0	16.0

* SPECIALTY ITEM

PLOT DATE = 6/28/2006
 FILE NAME = c:\projects\48060004\48104020\text.dgn
 USER NAME = jperkins

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. 332 (U.S. ROUTE 150/IL 1)

SECTION 47BR-2

VERMILION COUNTY

Sheet 1 of 3

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
DATE: 06/16/06 CHECKED BY: R.M.N.