

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	47BR-2	VERMILION	68	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

## SUMMARY OF QUANTITIES

SHEET 2 OF 3

LOCATION OF WORK:

VERMILION COUNTY

ROADWAY / STRUCTURE  
IMPROVEMENTS  
FAP 332 (US 150 / IL 1)  
STA. 2520+50  
STA. 2524+77  
80% FEDERAL  
20% STATE  
X081-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48 IN.	FOOT	1185.0	1185.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	73,110.0	73,110.0
51201600	FURNISHING STEEL PILES HP12X53	FOOT	385.0	385.0
<b>X0325278</b>	<b>DRIVING PILES</b>	FOOT	<b>385.0</b>	<b>385.0</b>
51203600	TEST PILE STEEL HP12X53	EACH	2.0	2.0
<b>X0325277</b>	<b>PILE SHOES</b>	EACH	<b>16.0</b>	<b>16.0</b>
51500100	NAME PLATES	EACH	1.0	1.0
54213453	END SECTIONS 18"	EACH	2.0	2.0
54215547	METAL END SECTIONS 12"	EACH	2.0	2.0
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	41.0	41.0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	106.5	106.5
60100945	PIPE DRAINS 12"	FOOT	80.0	80.0
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	140.0	140.0
60900515	CONCRETE THRUST BLOCKS	EACH	2.0	2.0
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	2.0	2.0
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	250.0	250.0
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.0	1.0
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4.0	4.0
*63200310	GUARDRAIL REMOVAL	FOOT	623.0	623.0
66201120	CONCRETE SHOULDER CURB	FOOT	29.0	29.0
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	2.0	2.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8.0	8.0
67100100	MOBILIZATION	L SUM	1.0	1.0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1.0	1.0
*70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0	1.0
70106700	TEMPORARY RUMBLE STRIP	EACH	6.0	6.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1388.0	1388.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	567.0	567.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	715.0	715.0

PLOT DATE = 6/25/2005  
 PLOT SCALE = 20.000000  
 PLOT USER = p1arsonb

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 F.A.P. 332 (U.S. ROUTE 150/IL 1)  
 SECTION 47BR-2  
 VERMILION COUNTY  
 Sheet 2 of 3  
 SCALE: NOT TO SCALE  
 DATE: 06/16/06  
 DRAWN BY: B.B.P.  
 CHECKED BY: R.M.N.