

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
817	8BR-2, 8BR-3	WASHINGTON	52	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			80% FED 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		SN 095-0010 SEC 8BR-2		SN 095-0011 SEC 8BR-3	
				X080-2A	SFTY-3N	X080-2A	SFTY-3N
20200100	EARTH EXCAVATION	CU YD	35	35			
20200500	EARTH EXCAVATION (WIDENING)	CU YD	70	40		30	
20400800	FURNISHED EXCAVATION	CU YD	290	55		235	
25000200	SEEDING, CLASS 2	ACRE	0.5	0.25		0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	46	23		23	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	46	23		23	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	46	23		23	
25100115	MULCH, METHOD 2	ACRE	0.5	0.25		0.25	
25100630	EROSION CONTROL BLANKET	SQ YD	807	240		567	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	75		75	
28000300	TEMPORARY DITCH CHECKS	EACH	2	2			
28000400	PERIMETER EROSION BARRIER	FOOT	1090	255		835	
28100105	STONE RIPRAP, CLASS A3	SQ YD	129	84		45	
28200200	FILTER FABRIC	SQ YD	129	84		45	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	37	37			
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	80	80			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.7	0.4		0.3	
40600300	AGGREGATE (PRIME COAT)	TON	4	2		2	
40600990	TEMPORARY RAMP	SQ YD	72	36		36	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	6	6			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	132	66		66	
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	1926	1038		888	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	99	99			
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2	1		1	
50102400	CONCRETE REMOVAL	CU YD	19.3	10.1		9.2	
50105220	PIPE CULVERT REMOVAL	FOOT	43	43			
50300225	CONCRETE STRUCTURES	CU YD	0.9	0.9			
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2465	1414		1051	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	40	40			
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	252	126		126	
51500100	NAME PLATES	EACH	2	1		1	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	224	112		112	
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	41	41			
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	275	158		117	
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	746	428		318	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	487.5	125		362.5	

PLOT DATE = 8/27/82
 PLOT NAME = #11111
 PLOT SCALE = #SCALE
 REFERENCE = #REF

* SPECIALTY ITEMS