

SCHEDULE OF QUANTITIES


85392

Item No.	Description	Unit	Quantity
A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	
	85TH AVENUE WEST		
	145' LT. STA. 11+90	1	
	105' LT. STA. 12+34	1	
	145' LT. STA. 12+72	1	
	36' LT. STA. 13+00	1	
	36' LT. STA. 15+00	1	
	36' LT. STA. 17+00	1	
	36' LT. STA. 19+00	1	
	52' LT. STA. 21+00	1	
	65' LT. STA. 23+00	1	
	49' LT. STA. 28+00	1	
	49' LT. STA. 30+00	1	
	49' LT. STA. 32+00	1	
	49' LT. STA. 34+00	1	
	49' LT. STA. 36+00	1	
	49' LT. STA. 38+00	1	
	43' LT. STA. 68+00	1	
	43' LT. STA. 70+00	1	
	43' LT. STA. 73+00	1	
	51st ST.		
	76' LT. STA. 102+50	1	
	78' RT. STA. 102+50	1	
	46' LT. STA. 104+50	1	
	TOTAL	21	
B2004120	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	
	85TH AVENUE WEST		
	PER LANDSCAPE PLANS	3	
	TOTAL	3	
	SHRUB, RHUS TYPHINA BAILTIGER (TIGER EYE SUMAC) CONTAINER GROWN, 5-GALLON	EACH	
	85TH AVENUE WEST		
	PER LANDSCAPE PLANS	2	
	TOTAL	2	
K0030412	PERENNIAL PLANTS, STELLA DE ORO DAYLILIES, 1 GALLON POTS	UNIT	
	85TH AVENUE WEST (PER LANDSCAPE PLANS)	50	
	TOTAL	50	
XX003239	CALAMAGROSTIS ACUTIFLORA 'KARL FOERSTER' 2 GAL	EACH	
	85TH AVENUE WEST (PER LANDSCAPE PLANS)	14	
	TOTAL	14	
XX004465	ANNUAL PLANTS	EACH	
	85TH AVENUE WEST (PER LANDSCAPE PLANS)	100	
	TOTAL	100	

Item No.	Description	Unit	Quantity
XX005307	TREE QUERCUS BICOLOR (SWAMP WHITE OAK), 3" CALIPER, BALLED & BURLAPPED	EACH	
	85TH AVENUE WEST		
	166' LT. STA. 10+85	1	
	195' LT. STA. 11+10	1	
	159' LT. STA. 11+20	1	
	40' LT. STA. 12+00	1	
	74' LT. STA. 12+10	1	
	47' LT. STA. 12+40	1	
	36' LT. STA. 14+00	1	
	36' LT. STA. 16+00	1	
	36' LT. STA. 18+00	1	
	36' LT. STA. 20+00	1	
	65' LT. STA. 22+00	1	
	65' LT. STA. 24+00	1	
	49' LT. STA. 27+00	1	
	49' LT. STA. 28+00	1	
	49' LT. STA. 31+00	1	
	49' LT. STA. 33+00	1	
	49' LT. STA. 35+00	1	
	49' LT. STA. 37+00	1	
	49' LT. STA. 39+00	1	
	43' LT. STA. 69+00	1	
	43' LT. STA. 71+00	1	
	51st ST.		
	69' LT. STA. 103+50	1	
	48' RT. STA. 103+50	1	
	TOTAL	23	

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 4"
	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
STAGE 1					
85TH AVENUE					
LT & RT STA. 10+77.81 - 26+00	931	698	9,694	-8,996	6,837
TURKEY HOLLOW TURN LANE					
RT 200+00 - 205+00	275	206	165	41	728
SUB TOTAL:	1,206	905	9,859	-8,955	7,564
STAGE 1					
OLD 85TH AVENUE Removal					
LT & RT STA. 0+25 - 2+75	585	439	1	438	1,414
SUB TOTAL:	585	439	1	438 *	1,414
STAGE 2					
Stage 1 waste.				438	
51st STREET					
LT & RT STA. 100+00 - 100+75	158	104	37	67	225
LT & RT STA. 101+25 - 104+89.26	2,199	1,649	5,418	-3,769	3,756
SUB TOTAL:	2,337	1,753	5,455	-3,264	3,981
STAGE 3					
85TH AVENUE					
LT & RT STA. 26+00 - 47+64	3,173	2,380	5,504	-3,124	9,813
LT & RT STA. 48+26 - 75+50	11,004	8,253	2,994	5,259	8,867
42nd STREET					
LT & RT STA. 2+50 - 3+05.50	243	182	0	182	99
SUB TOTAL:	14,420	10,815	8,498	2,317 **	18,779
GRAND TOTAL:	18,548	13,911	23,813	-12,219 ***	31,739
CODE NUMBER	PAY ITEM	UNIT	TOTAL		
20200100	EARTH EXCAVATION	C.Y.	18,548		
20400800	FURNISHED EXCAVATION	C.Y.	12,219		
21101615	TOPSOIL FURNISH AND PLACE, 4"	S.Y.	31,739		
* STAGE 1 WASTE, STORE AND USE IN STAGE 2.					
** WASTE AT END OF STAGE 3.					
*** TOTAL IS FURNISHED EXCAVATION NEEDS FOR STAGES 1 AND 2.					

Revised 9-11-06

 <p style="font-size: small;">Missman STANLEY & ASSOCIATES, P.C. Civil Engineering-Environmental Services-DE Landscaping Architecture-Drafting 1011 27th Avenue Rock Island, Illinois 61201-0040 Phone: (309) 782-0644 Fax: (309) 782-7891</p>	<p>85th Ave. West ROCK ISLAND, ILLINOIS</p> <p style="font-weight: bold;">SCHEDULE OF QUANTITIES</p>
<p>Missman Project No: A04T023</p> <p>File Name: 2037A_SUMMARY.dwg</p> <p>© COPYRIGHT 2003 ALL RIGHTS RESERVED</p> <p>Drawn By: WEF</p> <p>Checked By: DRM</p> <p>Date: MAY, 2006</p> <p style="font-size: large; font-weight: bold;">20</p> <p>Sheet 20 of 94</p>	