

SCHEDULE OF QUANTITIES

20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT
	85TH AVENUE WEST	
	32' RT. STA. 29+57	8
	32' RT. STA. 29+64	8
	36' RT. STA. 30+17	9
	36' RT. STA. 30+27	9
	34' RT. STA. 30+38	9
	46' RT. STA. 31+78	9
	44' RT. STA. 38+86	8
	44' RT. STA. 38+94	8
	43' RT. STA. 39+06	12
	43' RT. STA. 41+67	14
	42' LT. STA. 39+20	8
	34' LT. STA. 39+50	12
	31' LT. STA. 40+38	10
	31' LT. STA. 40+76	10
	30' LT. STA. 41+77	8
	23' LT. STA. 44+13	8
	30' RT. STA. 51+00	8
	32' LT. STA. 51+62	12
	38' LT. STA. 62+79	10
	37' LT. STA. 63+05	10
	37' LT. STA. 63+30	10
	36' LT. STA. 63+54	10
	35' LT. STA. 63+80	10
	34' LT. STA. 64+05	10
	34' LT. STA. 64+31	10
	34' LT. STA. 64+81	8
	37' RT. STA. 66+37	6
	39' RT. STA. 66+50	12
	32' RT. STA. 68+59	8
	39' RT. STA. 68+56	8
	34' RT. STA. 68+79	9
	TOTAL	291
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT
	85TH AVENUE WEST	
	38' RT. STA. 32+60	30
	34' RT. STA. 34+41	22
	45' RT. STA. 44+62	16
	33' LT. STA. 50+18	36
	51' LT. STA. 50+29	24
	33' LT. STA. 50+51	16
	53' LT. STA. 50+64	24
	32' RT. STA. 64+87	26
	31' RT. STA. 65+11	20
	35' RT. STA. 65+37	34
	31' RT. STA. 66+23	30
	33' RT. STA. 68+04	28
	43' RT. STA. 68+07	28
	40' RT. STA. 68+91	32
	36' RT. STA. 69+24	20
	29' RT. STA. 70+33	26
	TOTAL	412

20100500	TREE REMOVAL	ACRE
	85TH AVENUE WEST	
	RT. STA. 52+80-64+40	0.53
	TOTAL	0.53
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	C.Y.
	ESTIMATED QUANTITY ENTIRE PROJECT	200
	TOTAL	200
20800150	TRENCH BACKFILL	C.Y.
	LT. & RT. STA. 10+82	8
	LT. & RT. STA. 20+38	41.3
	RT. STA. 25+02-25+94	7.4
	LT. & RT. STA. 26+19	30
	LT. & RT. STA. 30+84	55.8
	RT. STA. 54+32-55+76	27.6
	LT. & RT. STA. 55+78	6.8
	RT. STA. 55+82-57+27	14.5
	RT. STA. 57+33-58+75	14.2
	LT & RT. STA. 58+78	3.6
	RT. STA. 58+81-60+31	10.3
	RT. STA. 60+41-62+44	31.2
	LT. & RT. STA. 62+50	3.6
	RT. STA. 62+54-64+46	15.4
	LT. & RT. STA. 72+00	28.8
	RT. STA. 72+04-73+03	20.8
	RT. STA. 73+09-73+44	2.8
	TOTAL	322.1
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	S.Y.
	ESTIMATED QUANTITY ENTIRE PROJECT	330
	TOTAL	330
25000300	SEEDING, CLASS 3	ACRE
	85TH AVENUE WEST	
	RT. STA. 25+75-31+82	0.3
	LT. STA. 47+50-48+10	0.01
	RT. STA. 64+00	0.3
	RT. STA. 66+50-67.50	0.04
	TOTAL	0.7
25000400	NITROGEN FERTILIZER NUTRIENT	POUND
	85TH AVENUE WEST	
	CLASS 1 SEEDING AREAS	243
	CLASS 3 SEEDING AREAS	63
	SODDED AREAS	102
	OLD 85TH AVENUE WEST	
	CLASS 1 SEEDING AREA	27
	TURKEY HOLLOW ROAD	
	CLASS 1 SEEDING AREA	13
	51ST STREET	
	CLASS 1 SEEDING AREAS	74
	42ND AVENUE	
	SODDED AREAS	1
	TOTAL	523

REVISONS	DESCRIPTION	DATE



85th Ave. West
ROCK ISLAND, ILLINOIS

SCHEDULE OF QUANTITIES

Missman Project No: A04T023	
File Name: 2037A_SUM&SCH.dwg	
© COPYRIGHT 2003 ALL RIGHTS RESERVED	
Drawn By: WEF	
Checked By: DRM	
Date: MAY, 2006	
12	
Sheet 12 of 94	

G:\RA\200A\A04T023-85AVE WEST.dwg 2037A_SUM&SCH.dwg 6/6/2006 8:46:44 AM