



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 19, 2006

SUBJECT: FAU 8075 (Cardinal Hill Road)
Project HS-RS-167(46)
Section 03-00167-04-FP
Sangamon County
Contract No. 93423
Item 37
September 22, 2006 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Revised Special Provision “Construction Sequence”

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by the initials "A.E." to the right.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

STATE OF ILLINOIS
CONTRACT SPECIFICATIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1, 2002, the latest editions of the "Manual of Uniform Traffic Control Devices for Streets and Highways", and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the "Supplemental Specifications and Recurring Special Provisions," indicated on the Check Sheet included herein, which apply to and govern the construction of Cardinal Hill Road, Section 03-00167-04-FP, Project HS-RS-167 (46), in Sangamon County. In case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

DESCRIPTION OF WORK

This section consists of furnishing all equipment, labor, and material necessary to construct a 0.43 mile three-lane urban highway and a 1.15 mile two-lane rural highway from Cardinal Hill Road to Buckhart Road (East Main Street) in Rochester. Construction of intersections with Oak Hills Road, Illinois Route 29, and Buckhart Road is included. In addition a 0.21 mile section of Walnut Street (Triangle Road) and a 0.34 mile section of Oak Hill Road will be reconstructed, and 0.37 mile of Cardinal Hill Road will be removed. All earthwork, drainage structures, and other incidental items are also included.

SALVABLE MATERIALS

All existing material not used in the improvement shall become the property of the Contractor and shall be removed from the job site in accordance with the Standard Specifications.

PRECAUTION FOR UTILITIES

The Contractor shall take whatever precautions which may be necessary to protect the property of the various public utilities which may be located underground or above ground, at or adjacent to the site of this improvement. S/he will be required to repair or replace at his/her own expense, or bear the cost, to repair or replace, any public utility property which has been damaged through his/her negligence. The procedure and specifications of repair will be in accordance with the regulations and/or policy of the utility.

SHOP DRAWINGS REVIEW

The contractor shall submit shop drawings to Hanson Professional Services Inc., 1525 South Sixth Street, Springfield, IL 62703, for review and approval.

CONSTRUCTION SEQUENCE

Revised 9-19-06

The Contractor shall submit a proposed construction sequence at the pre-construction conference for approval by the County.