

SCHEDULE OF QUANTITIES

F.A.U. 7700/LOGAN AVE.

CITY OF MATTOON

SECTION 05-00143-00-RS

ROUTE: F.A.U. 7700

LOGAN AVE.

JOB#: C-97-060-06 CONTRACT#: 95479

PROJ#: M5042(14)

COLES COUNTY

SHEET 17 OF 43

X4066424 BIT. CONC. SFE. CSE. SP D N50

Lt. ~ Rt., 120+74 ~ 147+63 = 590 TON
 TOTAL = 590 TON

40600100 BIT. MATERIALS (PRIME COAT)

Lt. ~ Rt., 120+74 ~ 147+63 = 845 GALLON
 TOTAL = 845 GALLON

40600300 AGGREGATE (PRIME COAT)

Lt. ~ Rt., 120+74 ~ 147+63 = 9.0 TON
 TOTAL = 9.0 TON

40600980 BIT. SURF. REMOVAL BUTT JT.

Lt. ~ Rt., 120+74 ~ 120+99 = 134.0 SQ.YDs.
 20' Lt. ~ Rt., 147+38-46' Lt. ~ 55' Rt., 147+63 = 224.0 SQ.YDs.
 TOTAL = 358.0 SQ.YDs.

40800400 INCIDENTAL BIT. SURFACING

PRAIRIE St. 14'~16' Lt., C~L 128+07 = 0.7 TON
 RICHMOND AVE., 14'~16' Lt., C~L 132+07 = 0.8 TON
 RICHMOND AVE., 14'~16' Rt., C~L 132+07 = 1.5 TON
 MOULTRIE AVE., 14'~16' Lt., C~L 143+59 = 0.8 TON
 TOTAL = 3.8 TON

60300350 MANHOLE FRAMES ADJUST

10' Rt., 124+50 = 1.0 EACH
 5' Lt., 131+85 = 1.0 EACH
 TOTAL = 2.0 EACH

78000200 THERMOPLASTIC PVT MK LINE 4"

C~L, 121+70 ~ 147+20 = 600.0 FOOT
 DASHED 10' YELLOW 4" = 180.0 FOOT
 C~L, 120+50 ~ 121+40 = 175.0 FOOT
 DOUBLE SOLID YELLOW LINE 4" = 2,650.0 FOOT
 SOLID WHITE LINE 4" = 2,580.0 FOOT
 Lt. 120+70 ~ 12' Lt. 147+20 = 2,650.0 FOOT
 Rt. 121+40 ~ 12' Rt. 147+20 = 2,580.0 FOOT
 SOLID WHITE EDGE LINE 4" = 6,185.0 FOOT
 TOTAL = 6,185.0 FOOT

78000100 THERMOPLASTIC PVT MK LTR & SYM

6.0' Lt., 120+70 = 26.0 SQ.FT.
 6.0' Lt., 121+00 = 26.0 SQ.FT.
 18.0' Lt., 120+70 = 15.6 SQ.FT.
 18.0' Lt., 121+00 = 15.6 SQ.FT.
 TOTAL = 83.2 SQ.FT.

78000400 THERMOPLASTIC PVT MK LINE 6"

14.1' Lt. ~ Rt., 124+46 = 28.2 FOOT
 14.1' Lt. ~ Rt., 124+52 = 28.2 FOOT
 14.1' Lt. ~ Rt., 131+55 = 28.2 FOOT
 14.1' Lt. ~ Rt., 131+61 = 28.2 FOOT
 SOLID WHITE CROSSWALK 6" = 112.8 FOOT
 TOTAL = 112.8 FOOT

78000650 THERMOPLASTIC PVT MK LINE 24"

C~L ~ 35' Lt., 120+48 = 35.0 FOOT
 C~L ~ 20' Rt., 123+51 = 20.0 FOOT
 C~L ~ 14.1' Lt., 124+58 = 14.1 FOOT
 C~L ~ 14.1' Rt., 131+49 = 14.1 FOOT
 C~L ~ 14.1' Lt., 132+48 = 14.1 FOOT
 C~L ~ 15' Rt., 147+24 = 15.0 FOOT
 SOLID WHITE 24" STOP BAR = 112.3 FOOT
 TOTAL = 112.3 FOOT