

# SCHEDULE OF QUANTITIES

## F.A.U. 7670/WESTERN AVE.

**CITY OF MATTOON**

SECTION 05-00143-00-RS

ROUTE: F.A.U. 7670

WESTERN AVE.

JOB#: C-97-060-06

PROJ#:M-5042(14)

CONTRACT#: 95479

COLES COUNTY

SHEET 36 OF 43

X4066424 BIT. CONC. SFE. CSE. SP D N50

14' Lt. ~ Rt., 45+69 ~ 81+62 = 763.0 TON  
 14' ~ 29' Rt., S. 32<sup>nd</sup> ST. = 10.0 TON  
 14' ~ 50' Rt., LYTLE PARK, C~L 51+45 = 12.0 TON  
**TOTAL = 785.0 TON**

40600980 BIT. SURF. REMOVAL BUTT JT.

14' Lt. ~ Rt., 45+69 ~ 45+94 = 78.0 SQ.YDs.  
 20'~29' Rt., 32<sup>nd</sup> ST., C~L 58+30 = 65.0 SQ.YDs.  
 14' Lt. ~ Rt., 81+37 ~ 81+62 = 78.0 SQ.YDs.  
**TOTAL = 221.0 SQ.YDs.**

78000200 THERMOPLASTIC PVT MK LINE 4"

C~L, 45+70 ~ 81+62 = 890.0 FOOT  
 DASHED 10' YELLOW 4"  
 12' Lt.&Rt., 45+69 ~ 81+62 = 7,186.0 FOOT  
 SOLID WHITE EDGE LINE 4"  
**TOTAL = 8,076.0 FOOT**

40600100 BIT. MATERIALS (PRIME COAT)

Lt. ~ Rt., 45+69 ~ 81+62 = 1,200.0 GALLON  
**TOTAL = 1,200.0 GALLON**

56109210 WATER VALVES ADJUST

24' Rt., 57+96 = 1.0 EACH  
**TOTAL = 1.0 EACH**

78000400 THERMOPLASTIC PVT MK LINE 6"

14' Lt. ~ Rt., 57+89.5 = 28.0 FOOT  
 14' Lt. ~ Rt., 57+95.5 = 28.0 FOOT  
 SOLID WHITE CROSS WALK 6"  
**TOTAL = 56.0 FOOT**

40600300 AGGREGATE (PRIME COAT)

Lt. ~ Rt., 45+69 ~ 81+62 = 12.0 TON  
**TOTAL = 12.0 TON**

60300350 MANHOLE FRAMES ADJUST

10' Lt., 78+64 = 1.0 EACH  
 8' Lt., 81+27 = 1.0 EACH  
**TOTAL = 2.0 EACH**

78000650 THERMOPLASTIC PVT MK LINE 24"

C~L ~ 12' Rt., 57+81.5 = 12.0 FOOT  
 C~L ~ 12' Lt., 58+65 = 12.0 FOOT  
 SOLID WHITE 24" STOP BAR  
**TOTAL = 24.0 FOOT**