



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

August 24, 2017

SUBJECT: FAP Route 855 (IL 14)  
Project STP-0885 (053)  
Section 10B-1; 10B-2  
Hamilton County  
Contract No. 78498  
Item No. 39, September 22, 2017 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Special Provisions.
2. Revised sheet 1 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Maureen M. Addis, P.E.  
Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Jeffrey Keirn, Region 5, District 9; Tim Kell; D. Carl Puzey; Estimates

CWR/cr

## STATE OF ILLINOIS

---

### SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted April 1, 2016, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of FAP Route 855 (IL 14), Project STP-0885(053), Section 10B-1, 10B-2, Hamilton County, Contract No. 78498 and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

### LOCATION OF PROJECT

The improvement consists of single-barrel box culvert replacements in Hamilton County. SN 033-7009 (E), 033-7036 (P) carries IL 14 over a Ditch, 3.5 miles west of the White County Line in Hamilton County and SN 033-7012 (E), 033-7037 (P) carries IL 14 over Ditch, 1.9 miles west of the White county line in Hamilton County.

### DESCRIPTION OF PROJECT

The work included in this contract consists of furnishing labor, equipment and material necessary to complete the improvements included in the project according to the plans and as specified herein.

The proposed improvement will consist of the removal and replacement of a 12' X 7' single-barrel box culvert with a new 12' X 8' precast box culvert in Hamilton County, as well as, the removal and replacement of a 12' X 5' box culvert with a new 12' X 6' precast box culvert in Hamilton County. Both culverts will be closed to traffic according to TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21-9 and the special provision BOX CULVERT REMOVAL AND REPLACEMENT in order to complete the majority of this work.

**\*NOTE: All references to FAP Route 885 within this contract shall be understood to mean FAP Route 855.**