

F.A.I. SHEETS	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-067L	COOK	35	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

62806

SUMMARY OF QUANTITIES

URBAN
100% STATE

CODE NO.	ITEM	UNIT	QUANTITY	DOT WORK	
				LIGHTING	
				Y030-1E	
67100100	MOBILIZATION	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0076600	TRAINEES	HOUR			
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1	1	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8	
80700110	GROUND ROD, 3/4" DIA. X 10'-0" LENGTH	EACH	73	73	
X0324667	CONCRETE FOUNDATION, 20" DIAMETER, 1" ANCHOR RODS, 10" BOLT CIRCLE	FOOT	365	365	
X0323768	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID	EACH	11	11	
Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	1	1	
X0324436	CLEAN EXISTING MANHOLE OR HANDHOLE	EACH	1	1	
X0324662	CONDUIT, POLYETHYLENE, DIRECTIONAL BORING, 1.25"	FOOT	6936	6936	
X0324934	CONDUIT, POLYETHYLENE, DIRECTIONAL BORING, 2"	FOOT	133	133	
X0320901	PVC CONDUIT IN TRENCH, 2" DIA. (SCHEDULE 40)	FOOT	105	105	
81000600	CONDUIT IN TRENCH, 2" DIA. GALVANIZED STEEL	FOOT	10	10	
X0324354	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	115	115	
X0950075	REMOVE EXISTING LIGHTING CONTROLLER AND SALVAGE	EACH	1	1	
84200500	REMOVE EXISTING LIGHTING UNIT AND SALVAGE	EACH	72	72	
X0324434	REMOVE EXISTING STREET LIGHTING UNIT FOUNDATION	EACH	72	72	

△



⊕ Y080
-NON-PARTICIPATING-

△ Rev. 9-9-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
59th ST TO 47th ST (FRONTAGE ROAD)
CITY OF CHICAGO LIGHTING CONDUIT & FOUNDATIONS
WELLS STREET

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: February 11, 2005

DRAWN BY: CJM
CHECKED BY: WDS

02/02/2005 09:01:44 AM \\netc11\1\p40468\p40468\elec\14\citr\Sas\contract\902\sq02001\ra.sty