



COMPLETE COMMODITY CODE NO. 05-6610-5310M

CODE NO.	MATERIALS	SIZE	QUAN.
(1) 05-6610-5310	PRE-CAST HANDHOLE	30"X36"	1
(2) 05-9075-5470	STONE 3/4" CRUSHED	BAG	5
(2) 05-5082-5330	SONO TUBE	30"	1
(2) 05-5082-5342	SONO TUBE	42"	1
(2) 05-3267-2940	CONC. REDI-MIX	CU. YD.	1/2
(2) 57-0770-0000	6" X 6" MESH	36"X10'	1
05-1452-9720	BRICK		24
02-4299-5524	FRAME MANHOLE	24"	1
02-4574-5040	COVER, MANHOLE	24"	1
09-7796-9312	GROUND ROD	3/4"X12'	1
09-2630-3240	GROUND CLAMP		1

- (1) PRE-CAST HANDHOLE SHALL INCLUDE CABLE HOOKS AND CONDUIT KNOCKOUTS.
 (2) THESE ITEMS ARE FOR POURED-IN-PLACE HANDHOLES ONLY.

CONSTRUCTION NOTES:

- 8" BED OF STONE FOR DRAINAGE.
- ALL METALLIC CONDUITS ENTERING HANDHOLE SHALL EXTEND MINIMUM 1" & MAXIMUM 3" INSIDE INNER WALL AND BE EQUIPPED WITH AN APPROVED TYPE OF THREADED GROUNDING BUSHING.

B	01-23-00	ADDED CABLE HOOKS PER COMMISSIONER HURRY	ERC/RJD
A	12-8-95	REDRAW (CAD)	MP
	DATE	REVISION	
30" DIA. CONCRETE HANDHOLE			
CITY OF CHICAGO			
DEPT. OF PUBLIC WORKS DIVISION OF ELECTRICITY DIVISION OF UTILITIES - TRANSMISSION			
DRAFTSMAN	ENGINEER	INSPECTOR	TESTER
M. PATTON	B. CARTER		DEBARTOLO
SUPERVISING ENGINEER	ETPC APPROVED		
ENGINEER OF ELECTRICITY			UWE. NO.
GEN'L. SUPT. OF ELECTRICITY			867
DEPT. COMMISSIONER			
SIZE: 11"	SCALE: NONE	DATE: 12-8-95	

REVISIONS	
NAME	DATE