

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-068L	COOK	37	8
STA.	TO STA.			
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

62807

SUMMARY OF QUANTITIES

URBAN

100% STATE

CODE NO.	ITEM	UNIT	QUANTITY	DOT WORK LIGHTING	
				Y030-1E	
67100100	MOBILIZATION	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOUR</del>			
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1	1	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8	
80700110	GROUND ROD, 3/4" DIA. X 10'-0" LENGTH	EACH	72	72	
X0324667	CONCRETE FOUNDATION, 20" DIAMETER, 1" ANCHOR RODS, 10" BOLT CIRCLE	FOOT	245	245	
X0324668	CONCRETE FOUNDATION, 20" DIAMETER, 1" ANCHOR RODS, 10" BOLT CIRCLE, OFFSET	FOOT	373.75	373.75	
X0323768	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID	EACH	6	6	
<del>Z0018940</del>	<del>DRILL EXISTING MANHOLE OR HANDHOLE</del>	<del>EACH</del>	<del>6</del>	<del>6</del>	
<del>X0324435</del>	<del>CLEAN EXISTING MANHOLE OR HANDHOLE</del>	<del>EACH</del>	<del>6</del>	<del>6</del>	
<del>X0324662</del>	<del>CONDUIT, POLYETHYLENE, DIRECTIONAL BORING, 1.25"</del>	<del>FOOT</del>	<del>7884</del>	<del>7884</del>	
<del>84200500</del>	<del>REMOVE EXISTING LIGHTING UNIT AND SALVAGE</del>	<del>EACH</del>	<del>86</del>	<del>86</del>	

~~NON PARTICIPATING~~

**CTE ENGINEERS**  
 CONSER TOWNSEND ENGINEERS, INC.  
 303 EAST WACKER DRIVE, SUITE 600  
 CHICAGO, ILLINOIS 60601-9022, PHONE: (312) 938-0300

Rev. 9-9-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 59th ST TO 47th ST (FRONTAGE ROAD)  
 CITY OF CHICAGO LIGHTING CONDUIT & FOUNDATIONS  
 WENTWORTH AVENUE

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: CJM  
 DATE: February 11, 2005 CHECKED BY: WDS

V:\tech\nt\40468\p-0468\elec\4-nt\p\sum\contract\9013\c0908\001\2.ctb 05/09/05 09:09:40 AM