



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 7, 2005

SUBJECT: FAP Route 305
Section 2004 – 108BR
Cook County
Contract No. 62853
Item No. 075, 9/23/2005 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages i and iii of the Table of Contents.
2. Revised pages 2-4 of the Special Provisions.
3. Added pages 142-143 to the Special Provisions.
4. Revised sheets 2 and 6 of the Plans.
5. Added sheet 2A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" followed by "P.E." in smaller letters.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Roger Driskell; R. E. Anderson;
Estimates; Design & Environment File

TK/sar

TABLE OF CONTENTS

STATE OF ILLINOIS.....	1
SPECIAL PROVISIONS.....	1
LOCATION OF PROJECT.....	1
DESCRIPTION OF PROJECT.....	1
MAINTENANCE OF ROADWAYS.....	1
STATUS OF UTILITIES TO BE ADJUSTED.....	2
COMPLETION DATE PLUS GUARANTEED WORKING DAYS.....	2
RESTRICTION ON GUARANTEED WORKING DAYS.....	3
WORK ZONE TRAFFIC CONTROL (LUMP SUM PAYMENT).....	3
TRAFFIC CONTROL PLAN.....	4
KEEPING THE EXPRESS LANES OPEN TO TRAFFIC:.....	5
TRAFFIC CONTROL REQUIREMENTS FOR REMOVING AND ERECTING P P C DECK BEAMS.....	6
BEARING PAD ADJUSTMENT.....	7
BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE.....	7
BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH).....	8
BRIDGE HANDRAIL REMOVAL.....	8
BRIDGE SIDEWALK REPAIR (FULL DEPTH).....	9
CHANGEABLE MESSAGE SIGNS.....	9
CLEANING AND PAINTING EXPOSED REBAR.....	9
CONCRETE WEARING SURFACE.....	15
DECK SLAB REPAIR.....	16
FORMED CONCRETE REPAIR (GBSP1).....	22
EMERGENCY VEHICLE PRIORITY SYSTEM LEAD-IN CABLE.....	23
FRAMES AND GRATES TO BE REMOVED.....	24
KEYWAY REPAIR.....	24
PAVEMENT MARKING TAPE, TYPE III 4", SPECIAL.....	25
PEDESTRIAN RAILING.....	26
REBUILD EXISTING HANDHOLE.....	26
REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS.....	27
STRUCTURAL STEEL REPAIR.....	28
TEMPORARY INFORMATION SIGNING.....	28
TEMPORARY PAVEMENT.....	29
TRAFFIC SIGNAL SPECIFICATIONS.....	30

Revised 9/7/2005

WORK ZONE SPEED LIMIT SIGNS (BDE) 135
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 136
STEEL COST ADJUSTMENT (BDE)..... 138
PAYROLLS AND PAYROLL RECORDS (BDE)..... 142

Revised 9/7/2005

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

STATUS OF UTILITIES TO BE ADJUSTED

Effective: January 30, 1987 Revised: July 1, 1994

Utility companies involved in this project have provided the following estimated dates:

<u>Name of Utility</u>	<u>Type</u>	<u>Location</u>	<u>Estimated Dates for Start and Completion of Relocation or Adjustments</u>
Fiber Optic	Buried Cable	West of and parallel to Wolf Road.	No conflict
Commonwealth Edison	Aerial Line	East of and parallel to Wolf Road.	No conflict
MWRDGC	Buried Sewer	East of and parallel to Wolf Road.	No conflict
Telephone	Buried Cable	West of and parallel to Wolf Road.	Conduits in Sidewalk of Wolf Road Bridge are abandoned by the owner and may be removed.

The above represents the best information available to the Department and is included for the convenience of the bidder. The applicable portions of Articles 105.07 and 107.31 of the Standard Specifications shall apply.

COMPLETION DATE PLUS GUARANTEED WORKING DAYS

The Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on, August 15, 2006 except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within 10 guaranteed working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the guaranteed working days allowed for clean up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

Article 108.09 of the Standard Specifications or the Special Provision for Failure to Complete the Work on Time, if included in this contract, shall apply to both the completion date and the number of working days.

Revised 9/7/2005

RESTRICTION ON GUARANTEED WORKING DAYS

Effective: January 21, 2003

All temporary lane closures during the period governed by guaranteed working days will not be permitted during the hours of 6:00 a.m. to 9:00 a.m. and 3:00 p.m. to 6:00 p.m. Monday through Friday.

All lane closure signs shall not be erected any earlier than one-half (1/2) hour before the starting hours listed above. Also, these signs should be taken down within one-half (1/2) hour after the closure is removed.

Failure to Open Traffic Lanes to Traffic: Should the Contractor fail to completely open and keep open all the traffic lanes to traffic in accordance with the limitations specified above, the Contractor shall be liable and shall pay to the Department the amount of \$250 per lane blocked, not as a penalty but as liquidated and ascertained damages, for each and every 15 minute interval or a portion thereof that a lane is blocked outside the allowable time limitations. The Department may deduct such damages from any monies due the Contractor. These damages shall apply during the period governed by guaranteed working days and any extensions of that contract time.

WORK ZONE TRAFFIC CONTROL (LUMP SUM PAYMENT)

Effective: February 1, 1996 Revised: November 1, 1996

Specific traffic control plan details and Special Provisions have been prepared for this contract.

Method of Measurement: All traffic control (except traffic control pavement marking) indicated on the traffic control plan details and specified in the Special Provisions will be measured for payment on a lump sum basis. Traffic control pavement markings will be measured per meter (foot).

Basis of Payment: All traffic control and protection will be paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION (SPECIAL). This price shall be payment in full for all labor, materials, transportation, handling and incidental work necessary to furnish, install, maintain and remove all traffic control devices required as indicated in the plans and as approved by the Engineer.

SHORT TERM PAVEMENT MARKING, TEMPORARY PAVEMENT MARKING and PAVEMENT MARKING TAPE TYPE III will be paid for separately.

Revised 9/7/2005

TRAFFIC CONTROL PLAN

Effective: September 30, 1985

Revised: October 1, 1995

Traffic Control shall be in accordance with the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS:

701301, 701421, 701422, 701501, 701602, 701606, 701701, 701801, 702001 and 704001

DETAILS:

MAINTENANCE OF TRAFFIC PLANS
TEMPORARY INFORMATION SIGNING
MOT DETAILS, TEMPORARY RAMPS & WOLF ROAD INTERSECTION
WORK ZONE PUBLIC INFORMATION SIGNS

SPECIAL PROVISIONS:

MAINTENANCE OF ROADWAYS
WORK ZONE TRAFFIC CONTROL (LUMP SUM PAYMENT)
TRAFFIC CONTROL PLAN

Revised 9/7/2005

PAYROLLS AND PAYROLL RECORDS (BDE)

Effective: August 10, 2005

FEDERAL AID CONTRACTS. Add the following State of Illinois requirements to the Federal requirements contained in Section V of Form FHWA-1273:

“The payroll records shall include each worker’s name, address, telephone number, social security number, classification, rate of pay, number of hours worked each day, starting and ending times of work each day, total hours worked each week, itemized deductions made, and actual wages paid.

The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work. The submittals shall be on the Department’s form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box (“No Work”, “Suspended”, or “Complete”) checked on the form.”

STATE CONTRACTS. Revise Section IV of Check Sheet #5 of the Recurring Special Provisions to read:

“IV. COMPLIANCE WITH THE PREVAILING WAGE ACT

1. **Prevailing Wages.** All wages paid by the Contractor and each subcontractor shall be in compliance with The Prevailing Wage Act (820 ILCS 130), as amended, except where a prevailing wage violates a federal law, order, or ruling, the rate conforming to the federal law, order, or ruling shall govern. The Contractor shall be responsible to notify each subcontractor of the wage rates set forth in this contract and any revisions thereto. If the Department of Labor revises the wage rates, the Contractor will not be allowed additional compensation on account of said revisions.
2. **Payroll Records.** The Contractor and each subcontractor shall make and keep, for a period of three years from the date of completion of this contract, records of the wages paid to his/her workers. The payroll records shall include each worker’s name, address, telephone number, social security number, classification, rate of pay, number of hours worked each day, starting and ending times of work each day, total hours worked each week, itemized deductions made, and actual wages paid. Upon two business days’ notice, these records shall be available, at all reasonable hours at a location within the State, for inspection by the Department or the Department of Labor.
3. **Submission of Payroll Records.** The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work. The submittals shall be on the Department’s form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box (“No Work”, “Suspended”, or “Complete”) checked on the form.

Added 9/7/2005

Each submittal shall be accompanied by a statement signed by the Contractor or subcontractor which avers that: (i) such records are true and accurate; (ii) the hourly rate paid to each worker is not less than the general prevailing rate of hourly wages required by the Act; and (iii) the Contractor or subcontractor is aware that filing a payroll record that he/she knows to be false is a Class B misdemeanor.

4. Employee Interviews. The Contractor and each subcontractor shall permit his/her employees to be interviewed on the job, during working hours, by compliance investigators of the Department or the Department of Labor.”

80155

Added 9/7/2005