

|         |           |        |              |              |
|---------|-----------|--------|--------------|--------------|
| ROUTE   | SECTION   | COUNTY | TOTAL SHEETS | SHEET NUMBER |
| FAP 330 | 2004-130I | WILL   | 14           | 3            |

CONTRACT: 62900

LOCATION OF WORK: 1) US 45 OVER NORTH BRANCH PRAIRIE CREEK, SN 099-0118  
2) US 45 OVER PRAIRIE CREEK, SN 099-0119

| SUMMARY OF QUANTITIES |   |        | CONSTRUCTION TYPE CODE |                     |                     |
|-----------------------|---|--------|------------------------|---------------------|---------------------|
| CODE NO.              | DESCRIPTION   | UNIT   | TOTAL QUANTITIES       | SFTY -2A            |                     |
|                       |   |        |                        | Loc. 1: SN 099-0118 | Loc. 2: SN 099-0119 |
| 44001000              | BITUMINOUS CONCRETE SURFACE REMOVAL                 | SQ YD  | 91.9                   | 83.6                | 8.3                 |
| 50102400              | CONCRETE REMOVAL                                    | CU YD  | 13.7                   | 5.2                 | 8.5                 |
| 50300100              | FLOOR DRAINS  | EACH   | 6                      | 6                   | 6                   |
| 50300255              | CONCRETE SUPERSTRUCTURE                             | CU YD  | 13.7                   | 5.2                 | 8.5                 |
| 50300300              | PROTECTIVE COAT                                     | SQ YD  | 33.7                   | 19.5                | 14.2                |
| 50400405              | PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH) | SQ FT  | 2070                   | 1065                | 1005                |
| 50800205              | REINFORCEMENT BARS, EPOXY COATED                    | POUND  | 2190                   | 830                 | 1360                |
| 58100200              | WATERPROOFING MEMBRANE SYSTEM                       | SQ YD  | 303.5                  | 193.5               | 110                 |
| 58300100              | PORTLAND CEMENT MORTAR FAIRING COURSE               | FOOT   | 867                    | 494                 | 373                 |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A                     | CAL MO | 4                      | 2                   | 2                   |
| 67100100              | MOBILIZATION  | L SUM  | 1                      | 0.5                 | 0.5                 |
| 70100405              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321     | EACH   | 2                      | 1                   | 1                   |
| 70400100              | TEMPORARY CONCRETE BARRIER                          | FOOT   | 360                    | 180                 | 180                 |
| 70400200              | RELOCATE TEMPORARY CONCRETE BARRIER                 | FOOT   | 360                    | 180                 | 180                 |
| 89000100              | TEMPORARY TRAFFIC SIGNAL INSTALLATION               | EACH   | 2                      | 1                   | 1                   |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
(SHEET 1 OF 2)

Rev.