

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(53-1,32-3)1-3	GRUNDY & LIVINGSTON	11	5
FED. ROAD DIST. NO. -		ILLINOIS	PROJECT	

CLASS "A" PATCHING - FAI 55 NORTHBOUND LANES
LIVINGSTON COUNTY

LOCATION BY MILE MARKER	PASSING LANE						DRIVING LANE						REMARKS
	CLASS A PATCHING			PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	CLASS A PATCHING			PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	
	TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD				TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD				
215.00													PROJECT START BEGIN CONCRETE SECTION
215.32													
215.34	8			8	60		8			8	60		
215.37							13			13	68		
215.41	13			13	68		13			13	68		
215.43							11			11	64		
215.45			88	88	180	33							
215.47	11			11	64		11			11	64		
215.50								20		20	78		
215.53			47	47	118	17			47	47	118	17	
215.53							8			8	60		
215.55							8			8	60		
216.42								20		20	78		
216.43							8			8	60		
216.75		20		20	78			20		20	78		
216.77							8			8	60		
216.78							8			8	60		
217.04							11			11	64		
217.27				0			8			8	60		
217.33							13			13	68		
217.41	8			8	60								
217.46								40		40	108	15	
217.48							8			8	60		
217.49							8			8	60		
217.52							16			16	72		
217.52							11			11	64		
218.04							11			11	64		
218.07													
TOTALS	40	20	135	195	628	50	181	60	87	328	1596	32	GRUNDY/LIVINGSTON COUNTY LINE

WIDE FLANGE BEAM TERMINAL JOINT, COMPLETE SCHEDULE		
NORTHBOUND LANE		
MILE POST	217.55	1 EACH
MILE POST	217.62	1 EACH
SOUTHBOUND LANE		
MILE POST	217.62	1 EACH
MILE POST	217.55	1 EACH
TOTAL		4 EACH

CLASS "A" PATCHING - FAI 55 SOUTHBOUND LANES
LIVINGSTON COUNTY

LOCATION BY MILE MARKER	PASSING LANE						DRIVING LANE						REMARKS	
	CLASS A PATCHING			PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	CLASS A PATCHING			PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH		
	TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD				TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD					
218.07										40	40	108	15	GRUNDY/LIVINGSTON COUNTY LINE
218.05										33	33	98	12	
217.99										40	40	108	15	BITUMINOUS PATCH
217.80							11			11	64			
217.79									53	53	128	20		
217.70	8			8	60		8			8	60			
217.55									40	40	108	15		M.P. 216
216.01														
215.63							8			8	60			
215.55							8			8	60			
215.52							11			11	64			
215.51							8			8	60			
215.48							8			8	60			
215.46									27	27	88	10		
215.42							8			8	60			
215.42	11			11	64		11			11	64			
215.37									40	40	108	15		
215.36							8			8	60			
215.00														BEGIN BITUMINOUS OVERLAY SECTION M.P. 215
TOTALS	19			19	124		88		273	361	1358	102		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES
LIVINGSTON COUNTY

SCALE: VERT.
HORIZ.
DATE: 06/09/2005

DRAWN BY: RLW
CHECKED BY:

Date: 06/15/2005
File: c:\projects\cmaln06\cm32\details.dgn