

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(32-1)J	GRUNDY	4	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

HIGH TENSION CABLE MEDIAN BARRIER SYSTEM AND AGGREGATE SHOULDER

LOCATION	HIGH TENSION CABLE MEDIAN BARRIER SYSTEM	AGGREGATE SHOULDER, TYPE B
MM POSTS	FT	TONS
NBL		
227.7 TO 229.36	8,765	221.8
OMIT S.N. 032-0005		
229.51 TO 229.9	2,060	52.1
OMIT MAINT. X-OVER		
229.91 TO 230.26	1,848	46.8
OMIT S.N. 032-0007		
230.41 TO 230.7	1,531	38.7
OMIT MAINT. X-OVER		
230.71 TO 232.7	10,508	265.9
OMIT MAINT. X-OVER		
232.71 TO 233.1	2,060	52.1
SBL		
229.36	300	7.6
230.26	300	7.6
TOTAL	27,372	692.7

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTR. TYPE CODE
			ROADWAY SFTY-3J
48101200	AGGREGATE SHOULDERS, TYPE B	TON	693
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	LSUM	1
70100800	TRAFFIC CONTRTOL AND PROTECTION, STANDARD 701401	LSUM	1
20029650	HIGH TENSION CABLE MEDIAN BARRIER SYSTEM	FOOT	27372

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES & SUMMARY
 SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY

7/1/2005 c:\projects\ed06505\defal\is.dgn