

BITUMINOUS SURFACE TREATMENT, A-3				
LOCATION	BIT. MAT. (PRIME COAT)  (TON)	BIT. MAT. (COVER AND SEAL COAT)  (TON)	COVER COAT AGG  (TON)	SEAL COAT AGG  (TON)
<u>SAND RIDGE ROAD</u>				
STA 20+12.33 TO STA 185+50.12	53.9	161.7	756.0	378.0
HUNTER PARKING AREA NO. 1	1.0	2.8	13.0	6.5
HUNTER PARKING AREA NO. 2	0.6	1.7	8.0	4.0
HUNTER PARKING AREA NO. 3	0.4	1.2	5.7	2.9
HUNTER PARKING AREA NO. 4	1.0	3.0	13.8	6.9
HUNTER PARKING AREA NO. 5	0.8	2.5	11.8	5.9
HUNTER PARKING AREA NO. 6	0.5	1.4	6.6	3.3
TOTAL =	58.2	174.3	814.9	407.5

PIPE CULVERT, END SECTION, DELINEATOR, & INLET SCHEDULE						
LOCATION	PIPE CULVERTS		END SEC		DELIN. S. -WHITE CRYSTAL (EACH)	ADJUST INLETS (EACH)
	TYPE 1-15 CS, AA (FOOT)	TYPE 1-18" RCCP (FOOT)	METAL 15" (EACH)	PRC FL 18" (EACH)		
	<u>SAND RIDGE ROAD &amp; HUNTER PARKING</u>					
STA 25+00		30.0		2	2	
RT STA 26+79.45	44.0					
STA 35+00		30.0		2	2	
RT STA 42+00	49.0					
STA 43+00		30.0		2	2	
LT STA 43+36.16	48.0					
LT STA 54+76.53	44.0					
RT STA 56+56.32	50.0		2			
STA 57+00		30.0		2	2	
STA 67+00		30.0		2	2	
STA 78+00		30.0		2	2	
LT STA 79+01.66	50.0					
RT STA 82+28.77	55.0					
STA 89+00		30.0		2	2	
STA 95+00		30.0		2	2	
STA 101+00		30.0		2	2	
STA 110+00		30.0		2	2	
STA 116+00		30.0		2	2	
STA 121+00		30.0		2	2	
RT STA 121+76.00	50.0		2			
STA 135+00		30.0		2	2	
STA 145+00		30.0		2	2	
STA 176+70		30.0		2	2	
<u>JAKE WOLF FISH HATCHERY PARKING AREA</u>						
STA. 5+16.17 @ 27.85' LT						1
STA. 5+93.04 @ 26.09' RT						1
STA. 6+84.74 @ 25.41' RT						1
TOTAL =	390.0	450.0	4	30	30	3

ESTIMATED QUANTITIES		
ITEMS	UNIT	TOTAL
THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR REPAIR OF HAUL ROADS (SEE SPECIAL PROVISIONS)		
BITUMINOUS MIXTURE FOR PATCHING POTHOLES (COLD MIX)	TON	60
BITUMINOUS MATERIALS (COVER AND SEAL COATS), SPECIAL	GALLON	1060
SEAL COAT AGGREGATE, SPECIAL	TON	140

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES

SCALE: VERT. DATE  
 HORIZ. DRAWN BY  
 CHECKED BY