

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
..	..	MASON	86	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		
* PARK ROADS ** SAND RIDGE STATE FOREST INTERNAL ROADS 2004				

AGGREGATE & BITUMINOUS RESURFACING SCHEDULE								
LOCATION	BIT. MATERIALS (P.C.) (TON)	AGG (P.C.) (TON)	BIT. BASE CSE 8" (SQ YD)	LEVELING BINDER (TON)	BIT. CONC. SURF. CSE (TON)	AGG SURF. CSE T-A 3" (CA 06) (TON)	SUB-BASE GRAN. MAT T-B 5" (CA 02) (TON)	AGG SHLDS T-B (TON)
<u>SAND RIDGE ROAD</u>								
STA 20+12.33 TO STA 148+50				1,051.3		6,454.9	10,762.4	
HUNTER PARKING AREA NO. 1						110.9	184.9	
HUNTER PARKING AREA NO. 2						67.7	112.8	
HUNTER PARKING AREA NO. 3						48.7	81.2	
HUNTER PARKING AREA NO. 4						118.1	196.9	
HUNTER PARKING AREA NO. 5						100.7	167.8	
HUNTER PARKING AREA NO. 6						56.7	94.5	
<u>JAKE WOLF FISH HATCHERY RD.</u> <u>INCLUDING PARKING LOT AND</u> <u>SOUTH ENTRANCE RD.</u>								
STA 1+25.00 TO STA 60+02.96	7.2	26.8			1,577.0			215.5
LT STA 5+68.32			23					
LT STA 6+37.71			18					
TOTAL =	7.2	26.8	41	1,051.3	1,577.0	6,957.7	12,324	215.5

CURB AND GUTTER REMOVAL	
PARKING AREAS	CURB AND GUTTER REMOVAL (LF)
<u>JAKE WOLF FISH HATCHERY VISITOR PARKING</u>	
LT STA 5+68.32	38
LT STA 6+37.71	37
TOTAL =	75

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY