

SIGNING SCHEDULE					
LOCATION: SIGNS SHALL BE LOCATED AT THE FOLLOWING INTERSECTIONS IN CONJUNCTION WITH THE SIGN LOCATIONS MAP.	MUTCD NO.	MESSAGE	SIZE IN x IN	SIGN PANELS T-1 (SQ FT)	TELE. SIGN SUPPORT (FOOT)
1. GOOFY RIDGE BLACKTOP AND SAND RIDGE RD.		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
2. GOOFY RIDGE BLACKTOP AND PINE VALLEY DR.		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
3. GOOFY RIDGE BLACKTOP AND CACTUS DR.		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
4. SAND RIDGE RD. EAST ENTRANCE TO FOREST		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
5. FOREST CITY RD. (TR 13) EAST ENTRANCE TO FOREST		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
6. BISHOP RD. (TR 134) AND SOUTH ENTRANCE TO FOREST		BRAKE FOR WILDLIFE	36 x 36	9.00	17.0
	W 13-1A	20 MPH	24 x 24	4.00	
SAND RIDGE ROAD LT STA 20+65.00	R1-1(3030)	STOP	30 x 30	6.25	15.0
	W3-1a(3030)	STOP AHEAD	30 x 30	6.25	
JAKE WOLF FISH HATCHERY RT STA 4+16.01 RT STA 4+16.01	R7-8(1218)	HANDICAP	12 x 18	1.50	11.0
	R7-I101(612)	\$100 FINE	6 x 12	0.50	
RT STA 4+37.26 RT STA 4+37.26	R7-8(1218)	HANDICAP	12 x 18	1.50	11.0
	R7-I101(612)	\$100 FINE	6 x 12	0.50	
RT STA 4+53.32 RT STA 4+53.32	R7-8(1218)	HANDICAP	12 x 18	1.50	11.0
	R7-I101(612)	\$100 FINE	6 x 12	0.50	
TOTAL =				96.50	165.0
<p>NOTES: ALL POST UNLESS OTHERWISE NOTED SHALL MEET THE REQUIREMENTS OF SECTION 728 OF THE STANDARD SPECIFICATIONS. EACH POST SHALL ALSO INCLUDE A 2 1/4" x 2 1/4" x 4' BASE DRIVEN INTO THE GROUND EXCEPT THE LAST 2".</p> <p>ALL POST SHALL BE OFFSET FROM EDGE OF THE PAVEMENT BY 18". SEE STANDARD DRAWINGS FOR POST IN PAVEMENT.</p>					

PAVEMENT MARKING SCHEDULE				
LOCATION	THERMO. PAVT. MK LINE 5" (YELLOW) (FOOT)	THERMO. PAVT. MK. LINE 8" (YELLOW) (FOOT)	THERMO. PAVT. MK. LINE 12" (WHITE) (FOOT)	THERMO. PAVT. MK. L & S (WHITE) (SQ FT)
JAKE WOLF FISH HATCHERY PARKING AREA STA 1+25.06 TO STA 10+85.44	1624	374	164	111.3
TOTAL =	1624	374	164	111
NOTE: LETTERS & SYMBOLS SMALL DIRECTIONAL ARROW = 6.5 SQ FT HANDICAP SYMBOL = 4.6 SQ FT				

BUMPER BLOCK SCHEDULE (INCIDENTAL TO EARTH EXC.)		
PARKING AREAS	BUMPER BLOCK REMOVAL (EACH)	BUMPER BLOCK (NEW) (EACH)
JAKE WOLF FISH HATCHERY VISITOR PARKING	18	18
TOTAL =	18	18

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____
DATE _____

DRAWN BY _____
CHECKED BY _____