




SUMMARY OF QUANTITIES

		100% STATE SAFETY - 2A CASS COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
67100100	MOBILIZATION	LSUM	1.0	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1.0	1.0
X0324059	DEBRIS DEFLECTION SYSTEM, COMPLETE	LSUM	1.0	1.0
51201000	FURNISHING METAL PILE SHELLS, 12"	FOOT	158	158
51200950	FURNISHING METAL PILE SHELLS, 10"	FOOT	45	45
51202600	DRIVING AND FILLING SHELLS	FOOT	203	203

General Notes:

Plan dimensions and details relative to the existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the contractor's responsibility to verify such dimensions and details in the field and to make necessary approved adjustments prior to construction or ordering materials. Such variations shall not be cause for additional compensation or a change in scope of work. However, the contractor will be paid for the quantity of actually furnished at the unit bid price for the work. The contractor shall submit a procedure for driving the piles to the Engineer for approval. This shall include a means, such as crane mats, for distributing the load to the bridge deck and preventing damage to the concrete.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED	June 29 20 05  ENGINEER OF OPERATIONS
EXAMINED	June 20 20 05  ENGINEER OF PROGRAM IMPLEMENTATION
EXAMINED	JUNE 15 20 05  ENGINEER OF PROGRAM DEVELOPMENT

SUMMARY OF QUANTITIES
 FAP 614 (IL 78)
 SECTION (144BR-2)I-3,
 (144BR-3)I-2
 CASS COUNTY