F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	27-1R	ST. CLAIR	382	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76300

SUMMARY OF QUANTITIES

	CODE	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 20% STATE - 80% FEDERAL: RURAL SECTION STA 149+00 - 292+57			URBAN SECTION STA 292+57 - 336+00		
					1000-2A	SFTY-3N		1000-2A	SFTY-3N	
•	A2006814	TREE, QUERCUS MUEHLENDERBERGII (CHINKAPIN OAK), 1 - 3/4" CALIPER, BALLED AND BURLAPPED	EACH	3	3					
•	A2006914	TREE, QUERCUS PALUSTRIS (PIN OAK), 1 - 3/4" CALIPER, BALLED AND BURLAPPED	EACH	20	20					
•	A2007114	TREE, QUERCUS RUBRA (RED OAK), 1 - 3/4" CALIPER, BALLED AND BURLAPPED	EACH	6	5			1		
•	B2000412	TREE, ACER GRISEUM (PAPERBARK MAPLE), 1 - 1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	214	188			26		
•	B2001114	TREE, CERCIS CANADENS (EASTERN REDBUD), 1 - 3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	277	241			36		
•	B2003114	TREE, MALUS CORALBURST (CORALBURST CRAB APPLE), 1 - 3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	78	66			12		
•	B2004114	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRAB APPLE), 1 - 3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	59	56			3		
	XX005273	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N90	TON	473	244			229		
	X0325110	BIAXIAL GEOGRID	SQ YD	5635	5635					
	X0322729	MATERIAL TRANSFER DEVICE	TON	11192	8930			2262		
	X3560164	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 12 1/2 INCHES	SQ YD	2659	2497			162		
	X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D" , N90	TON	4902	2677			2225		
	X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL - 19.0, N90	TON	19106	6946			12160		
	X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	1606	1204			402		
	X4073061	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH) SUPERPAVE, 9"	SQ YD	26458	26045			413		
	X4073161	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH) SUPERPAVE, 14"	SQ YD	55265	55265					
	X4421000	PARTIAL DEPTH PATCHING	TON	18	16			2		
	X4510125	WIDE CRACK ROUTING (PAVEMENT)	FOOT	264	179			85		
	X4510150	WIDE CRACK FILLING	POUND	504	336			168		
•	X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	90	60			30		
•	X7200400	WORK ZONE PUBLIC INFORMATION SIGNS	EACH	4	2			2		
*	Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1	1					
*	Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1					
	Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	286				286		
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
	Z0017100	DOWEL BARS	EACH	1458	1301			157		
	Z0022800	FENCE REMOVAL	FOOT	2981	2431			550		
•	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON REDIRECTIVE), TEST LEVEL 3	EACH	14		12			2	
•	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON REDIRECTIVE), TEST LEVEL 3	EACH	6		4			2	
	Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	7	6			1		
	Z0075300	TIE BARS	EACH	129	129					
	Z0032900	LAND SECTION MARKERS	EACH	8	7			1		

Rev.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 4 OF 4 SHEETS
F.A.P. 103 (IL. RTE. 13/15)
SECTION 27-1R - ST. CLAIR CO.

SCALE: DRAWN BY YBA
DATE March 21, 2005 CHECKED BY RCY

c:\pro\jobs\ed8893\plan\df1a044c.dgn 03/31/05 2:00 p.m.