

CONSULTANTS

NO.	DATE	DESCRIPTION	PER IDOT COMMENTS	PER IDOT COMMENTS
1	7/7/05			
2	7/14/05			

- REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWING

PLAN SHEET DESIGNATION

- COVER
- G - GENERAL
- H - HAZARDOUS MATERIALS
- C - CIVIL
- L - LANDSCAPE
- S - STRUCTURAL
- A - ARCHITECTURAL
- I - INTERIORS
- E - EQUIPMENT
- F - FIRE PROTECTION
- P - PLUMBING
- M - MECHANICAL
- E - ELECTRICAL
- T - TELECOMMUNICATIONS
- R - RESOURCE

PROJECT NO: 031064
DWG FILE: 031064SUM.DWG
SCALE: AS SHOWN
DRAWING DATE: 06-17-05
DESIGNED BY: JER / DSD
DRAWN BY: TJB / DSD
CHECKED BY: LDH
PLOTTED BY: DSD 06-17-05

CLIENT

**VILLAGE OF PARK FOREST
ILLINOIS**

**(FAU 2830) MONEE ROAD
STP (LAPP) PROJECT**

SHEET TITLE

SCHEDULE OF QUANTITIES

ENTRANCES							
STATION	EXIST DRIVE APRONS (TYPE)	RES. OR COMM.	WIDTH @ 3' BACK OF E. O. P. (FT)	WIDTH @ E. O. P. (FT)	LENGTH (FT)	DRIVEWAY PAVEMENT (SY)	
12+22	LT	BIT	RES	22	25	3	7.8
12+64	RT	BIT	RES	20	23	3	7.2
13+00	LT	BIT	RES	14	17	3	5.2
13+24	LT	CONC	RES	-	16	3	-
13+81	RT	BIT	RES	15	18	3	5.5
13+95	LT	CONC	RES	-	17	3	-
14+47	RT	BIT	RES	36	38	3	12.3
14+66	LT	BIT	RES	14	17	3	5.2
15+50	RT	BIT	RES	24	27	3	8.5
15+69	LT	BIT	RES	17	19	3	6.0
16+07	LT	CONC	RES	-	13	3	-
17+12	RT	BIT	RES	16	20	3	6.0
17+98	LT	BIT	RES	24	28	3	8.7
19+12	LT	BIT	RES	14	19	3	5.5
19+28	LT	BIT	RES	12	13	3	4.2
19+42	RT	BIT	RES	27	31	3	9.7
20+31	LT	BIT	RES	14	19	3	5.5
20+40	RT	CONC	RES	-	28	3	-
20+41	LT	BIT	RES	11	13	3	4.0
21+03	RT	CONC	RES	-	25	3	-
21+06	LT	BIT	RES	13	15	3	4.7
22+19	LT	BIT	RES	34	37	3	11.8
23+24	LT	BIT	RES	12	15	3	4.5
23+46	LT	BIT	RES	14	19	3	5.5
24+61	LT	BIT	RES	29	33	3	10.3
25+80	LT	BIT	RES	33	40	3	12.2
26+88	LT	BIT	RES	15	20	3	5.8
27+11	LT	BIT	RES	20	24	3	7.3
28+17	LT	BIT	RES	28	31	3	9.8
28+34	RT	BIT	RES	14	14	3	4.7
28+85	LT	BIT	RES	20	21	3	6.8
29+28	RT	CONC	RES	-	17	3	-
29+52	LT	BIT	RES	15	20	VAR	9.1
TOTAL BITUMINOUS DRIVEWAY PAVEMENT **							193.8
TOTAL BITUMINOUS SURFACE REMOVAL AT PROJECT LIMITS							224.2
TOTAL BITUMINOUS SURFACE REMOVAL - BUTT JOINT **							418.0
** BITUMINOUS PAVEMENT REMOVAL AND REPLACEMENT SHALL BE PAID FOR AS SHOWN IN THE PROPOSED TYPICAL SECTIONS.							

SCHEDULE OF MANHOLE ADJUSTMENTS	
MANHOLES TO BE ADJUSTED	
29+25	13.0' RT
TOTAL	1 EACH

SCHEDULE OF CATCH BASIN ADJUSTMENTS	
CATCH BASINS TO BE ADJUSTED	
25+77	9.0' LT
25+77	14.0' LT
27+31	18.0' LT
30+20	32.0' LT
TOTAL	4 EACH

SCHEDULE OF SANITARY MANHOLE ADJUSTMENTS	
SANITARY MANHOLES TO BE ADJUSTED	
13+54	13.0' RT
16+98	24.0' RT
23+95	13.0' RT
26+97	13.0' RT
28+80	14.0' RT
TOTAL	5 EACH

SCHEDULE OF PAVEMENT PATCHING			
CLASS D PATCHES, TYPE III, 6"			
START	END	WIDTH	AREA
19+74	19+80	24	16.0
20+85	21+15	6	20.0
28+14	28+18	34	15.0
TOTAL			51.0 SQ YD

SCHEDULE OF PAVEMENT PATCHING			
CLASS D PATCHES, TYPE IV, 6"			
START	END	WIDTH	AREA
11+70	12+07	12	50.0
12+48	12+85	6	25.0
12+90	14+03	VARIES	74.0
15+17	15+97	5	44.0
16+77	17+31	VARIES	100.0
18+20	19+08	VARIES	63.0
20+19	20+54	VARIES	27.0
21+50	23+47	6	132.0
23+78	24+08	VARIES	53.0
24+67	25+29	6	42.0
24+88	25+24	12	48.0
25+74	27+22	VARIES	92.0
25+74	26+17	6	29.0
26+68	27+19	13	74.0
TOTAL			853.0 SQ YD

SCHEDULE OF PAVEMENT PATCHING			
CLASS D PATCHES, TYPE II, 6"			
START	END	WIDTH	AREA
11+49	11+65	6	11.0
12+43	12+47	12	6.0
15+32	15+61	4	14.0
16+42	16+53	5	6.0
29+03	29+21	6	12.0
TOTAL			49.0 SQ YD

PROPOSED

- SMH-A, MH-A, WV-A, AND WV-A, SANITARY MANHOLE, MANHOLE, WATER VALVE BOX OR WATER VALVE VAULT TO BE ADJUSTED
- MH-R (SP) MANHOLES TO BE RECONSTRUCTED WITH NEW GRATE (SPECIAL)
- BITUMINOUS SURFACE REMOVAL - BUTT JOINT
- CLASS D PATCHES, TYPE VARIES (I - IV) - 6" XX SQ. YD.
- DRIVEWAY REMOVAL & REPLACEMENT