

**DRIVEWAY PAVEMENT SCHEDULE**

LOCATION	EXIST. SURFACE	DRIVEWAY PAVT. REMOVAL			PCC DRIVEWAY PAVT. 6"		
		LENGTH	WIDTH	SQ. YD.	LENGTH	WIDTH	SQ. YD.
5+96 LT	CONC.	14'	8'	12.4	9.4'	12'	15.3
7+14 LT	AGG.	-	-	-	5.3'	12'	9.8
9+15 LT	VAR.	8'	12'	10.7	14.5'	12'	22.1
9+93 LT	CONC.	22'	9'	22.0	14.4'	12'	22.1
10+57 RT	AGG.	-	-	-	9.4'	20'	23.7
11+74 RT	AGG.	-	-	-	9.4'	18'	21.6
12+68 LT	CONC.	21'	20'	46.7	14.4'	19.5'	35.5
13+22 LT	NONE	-	-	-	8.6'	12'	14.2
15+07 RT	AGG.	-	-	-	14.4'	24'	41.2
16+59 LT	CONC.	9'	23'	23.0	10.3'	12'	30.2

TOTAL DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT 114.8 235.7

**PCC PAVEMENT 7" SPECIAL W/IC**

LOCATION	AREA (SQ. YD.)
CLEVELAND ST. EXISTING TRANSITION 4+50 TO 6+00	470
LINCOLN STREET INTERSECTION	110
CLEVELAND STREET MAINLINE 6+00 TO 17+31	3917
WEST PARK ENTRANCE	95
ADAMS STREET ENTRANCE	64
MADISON STREET INTERSECTION	156
VAN BUREN STREET INTERSECTION	63

TOTAL PCC PAVEMENT 7" SPECIAL W/IC 4875

**PAINT PAVEMENT MARKING LINE (FEET)**

LOCATION	CROSSWALK	STOP BAR	SKIP DASH CL.
	6" WHITE	12" WHITE	4" YELLOW
CENTERLINE 4+50 TO 17+31	-	-	320
STA. 4+64 RT	-	12	-
STA. 4+68 & 4+74	65	-	-
STA. 4+74 TO 4+89, 25'LT	-	15	-
STA. 4+74 TO 5+09, 18'RT & 24'RT	69	-	-
STA. 5+08 & 5+14	65	-	-
STA. 5+18 LT	-	18	-
STA. 5+57 TO 5+77, 25'RT	-	20	-
STA. 8+06 TO 8+18, 26'LT	-	12	-
STA. 11+28 TO 11+48, 27'LT	-	20	-
STA. 14+80 RT	-	15	-
STA. 14+94 TO 15+04, 27'LT	-	10	-
STA. 15+07 TO 15+20, 25'RT	-	13	-
STA. 15+37 LT	-	15	-

TOTAL PAVEMENT MARKING 199 150 320

**SIDEWALK SCHEDULE**

LOCATION	WIDTH	LENGTH	AREA (SQ. FT.)
4+50 TO 5+31 RT	4'	81'	324
4+72 RT	4'	6'	24
5+11 RT	4'	6'	24
LINCOLN ST. (WEST)	4'	28'	112
LINCOLN ST. (EAST)	4'	18'	72
STA. 5+80 TO 6+12 RT.	4'	35'	140
ADAMS ST. (WEST)	4'	18'	72
MADISON ST. (WEST)	4'	28'	112
STA. 13+60 LT	4'	18'	72
VAN BUREN ST. (WEST)	4'	26'	104
STA. 15+33 RT	4'	17'	68

TOTAL PC SIDEWALK 4" 1124

**STORM SEWER REMOVAL SCHEDULE**

LOCATION NUMBER	STATION	OFFSET (FEET)	LENGTH (FEET)					TRENCH BACKFILL CU. YDS.
			10"	12"	18"	24"	30"	
1	5+90 TO 6+29 LT	13		39				-
2	6+99 TO 7+15 LT	13	10					-
3	7+15 TO 7+25 LT	13		16				-
4	7+93 TO 8+01 LT	17		8				-
5	8+01 LT	13 TO 21		8				-
6	8+01 TO 8+35 LT	13		34				-
7	9+05 TO 9+27 LT	13		22				-
8	9+28 TO 9+76 LT	13		48				-
9	9+77 TO 10+05 LT	13		28				-
10	10+42 TO 10+71 RT	17		29				-
11	11+04 TO 11+29 LT	14 TO 27			28			-
12	11+30 LT	28 TO 49		21				-
13	11+30 TO 11+72 LT	16 TO 27			42			-
14	11+59 TO 11+88 RT	15		29				-
15	11+73 TO 11+90 LT	16			17			-
16	12+55 TO 12+80 LT	16			25			-
17	13+24 TO 13+80 LT	15			56			-
18	14+13 TO 14+92 LT	16				79		-
19	14+52 TO 15+52 RT	17		100				-
20	14+95 LT	16 TO 24			8			-
21	14+95 LT	24 TO 44		20				-
22	14+96 TO 15+20 LT	15				24		-
23	15+22 LT	16 TO 32				16		-
24	15+23 TO 15+35 LT	15					12	-
25	15+86 TO 16+88 LT	15				102		22.6

TOTAL STORM SEWER REMOVAL 10 402 192 205 12 22.6

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9477	05-00051-00-RP	FRANKLIN	23	4
CITY OF WEST FRANKFORT		CLEVELAND STREET		

CONTRACT NO. 99234

**SIDEWALK REMOVAL SCHEDULE**

LOCATION	WIDTH	LENGTH	SQ. FT.
STA. 4+50 TO 5+29 RT.	4'	79'	316
LINCOLN ST. (WEST)	4'	28'	112
LINCOLN ST. (EAST)	4'	21'	84
ADAMS ST. (WEST)	4'	14'	56
MADISON ST. (WEST)	4'	33'	132
STA. 12+31 RT.	2'	12'	24
STA. 13+70 LT.	4'	6'	24
STA. 14+56 LT.	8'	4'	32
VAN BUREN ST. (WEST)	4'	15'	60
STA. 15+33 RT.	4'	17'	68

TOTAL SIDEWALK REMOVAL 908

**COMBINATION CURB AND GUTTER REMOVAL SCHEDULE**

LOCATION	LENGTH (FOOT)
NW CORNER LINCOLN STREET	45
NE CORNER LINCOLN STREET	40
SOUTH SIDE LINCOLN STREET	84
STA. 5+25 TO 5+89 LT	64
NW CORNER MADISON STREET	60
NE CORNER MADISON STREET	52

TOTAL CURB & GUTTER REMOVAL 345

**MANHOLES TO BE ADJUSTED**

WITH NEW TYPE 1 FRAME AND CLOSED LID

LOCATION	LID ELEVATION		ADJUSTMENT (FOOT)
	EXIST.	PROPOSED	
0.5' RT 6+05	403.51	403.65	+0.14
1.5' RT 8+94.3	402.52	401.75	-0.77
1.0' RT 12+07.5	402.45	400.82	-1.63
1.5' RT 15+05	400.65	400.66	+0.01

TOTAL MANHOLES TO BE ADJUSTED 4 EACH