


CONTRACT NO. - 60445

## LEGEND

- 1) EXISTING PCC PAVEMENT (+/-) 200MM
- 2) EXISTING BITUMINOUS SURFACE (+/-) 190MM
- 3 EXISTING STABILIZED SHOULDER
- (4) EXISTING PCC SIDEWALK
- 5 PROPOSED AGGREGATE SUBGRADE 300MM (12")
- PROPOSED HMA PAVEMENT (FULL DEPTH), 325MM (13") (SEE MIXTURE TABLE FOR MIX. REQUIREMENT)
- 7) PROPOSED COMBINATION CONCRETE CURB & GUTTER B-15.30 (B-6.12)
- 8 PROPOSED PCC SIDEWALK 125MM (5")
- 9 PROPOSED FURNISH AND PLACE TOP SOIL 100MM (4")
- (10) PROPOSED HMA SHOULDER 200MM (8")
- PROPOSED AGGREGATE WEDGE SHOULDER TYPE B 150MM (6")
- 12) POROUS GRANULAR EMBANKMENT
- (13) PROPOSED SAFETY EDGE
- \* EXISTING SIDEWALK REMOVAL LOCATIONS MARKED ON THE PLANS
- \*\* MATCH THE EXISTING SIDEWALK AT STA. 1+514
- \*\*\* STA.1+470 TO STA. 1+495 (1.5 M SIDEWALK) STA. 1+495 TO STA. 1+520 (2.0 M SIDEWALK)
- # SUPER ELEVATION VARIES TO MATCH THE EXISTING CROSS SECTION (SEE THE CROSS SECTIONS AND THE DETAILED PROPOSED PAVEMENT ELEVATION PLAN)




REVISIONS
NAME DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

IL - 50 (GOVENOR'S HIGHWAY)

TYPICAL CROSS SECTION

SCALE: NONE DRAWN BY
DATE: 8/17/201/ CHECKED BY



PROPOSED TYPICAL CROSS SECTION STA. 1+600 TO STA. 1+640

TO DRAIN THE AGGREGATE SUB GRADE 300 mm, PROVIDE 100 mm DIAMETER TRAVERSE PIPE UNDER DRAIN AT 90 METER SPACING.